

CRAIG PAEPRER  
*Chairman*

ANTHONY GIANNICO  
*Vice Chairman*

**BOARD MEMBERS**  
RAYMOND COTE  
ROBERT FRENKEL  
VICTORIA CAUSA  
JOHN NUCULOVIC  
NICHOLAS BALZANO

**TOWN OF CARMEL**  
**PLANNING BOARD**



60 McAlpin Avenue  
Mahopac, New York 10541  
Tel. (845) 628-1500 – Ext.190  
[www.ci.carmel.ny.us](http://www.ci.carmel.ny.us)

MICHAEL CARNAZZA  
*Director of Code  
Enforcement*

RICHARD FRANZETTI,  
P.E., BCEE  
*Town Engineer*

PATRICK CLEARY,  
AICP, CEP, PP, LEED AP  
*Town Planner*

**PLANNING BOARD AGENDA**  
**FEBRUARY 28, 2024 – 7:00 P.M.**

**TAX MAP #   PUB. HEARING   MAP DATE   COMMENTS**

**SITE PLAN**

1. P & R Estate Corp – 122 Gleneida Ave, Carmel	44.13-2-68	5/16/23	Residential Site Plan
2. TTSHR, LLC – 25 & 27 Seminary Hill Road	55.6-1-69 & 70	12/19/23	Residential Site Plan
3. Diamond Point Development – 4 Baldwin Place Rd	86.10-1-2 & 3	2/2/24	Site Plan
4. Union Energy Center, LLC – 24 Miller Rd	86.11-1-14	2/16/24	Site Plan/Subdivision
5. Crecco – DAG Route 6, LLC – 395 Route 6	75.19-1-8 & 75.20-2-5	2/19/24	Site Plan

**MISCELLANEOUS**

6. MK Realty - Route 6 & Old Route 6, Carmel	55.6-1-44 & 45		Extension of Final Site Plan Approval
7. Jordano/Gervasi Subdivision – 182 Bullet Hole Rd	63.-1-16		Bond Return
8. Yankee Land Development – Bayberry Hill Rd & Owen Drive	76.15-1-12		Extension of Preliminary Subdivision (14 Lots)
9. Minutes – 01/11/24 & 01/24/24			

February 16, 2024

Mr Craig Paepre  
Planning Board Chair  
60 McAlpin Avenue  
Mahopac NY 10541


RE: Site Plan P&R Estate Corp.  
44.13-2-68

Dear Mr. Paepre,


As per our application to legalize a non conforming apartment building we would like to be placed on the next available agenda. Since the last meeting we have received Zoning Board of Appeals approval for the various variances we needed, including the Use Variance and multiple area variances. At this time again we would like to present the application for Planning Board Approval

I hope that these responses and enclosed plans clarify any questions you may have, Thank you I look forward to any comments you may have.

Best Regards




Robert M. Sherwood, RLA



SURVEY EXISTING CONDITIONS

- LEGEND**
- PROPERTY LINE
  - - - SETBACK LINE
  - - - WETLAND SETBACK
  - CENTER LINE
  - FENCE
  - - - WETLAND BOUNDARY
  - 100' — EXISTING CONTOUR
  - ☼ EXISTING TREE TO REMAIN
  - ⊗ TREE TO BE REMOVED
  - ⊙ DRAINAGE DESIGNED BY OTHERS
  - ⊕ EXISTING UTILITY POLE



SITE LOCATION MAP

**ZONING DATA**

TAX MAP DESIGNATION SECTION 44.13, BLOCK 2, LOT 168			
ZONING DISTRICT	COMMERCIAL		
ITEM	REQUIRED	PROPOSED	VARIANCE REQ.
LOT AREA	40,000 SF	17,360	22,640 SF.
LOT COVERAGE	30%	7%	NA
LOT WIDTH	200	147'	53'
LOT DEPTH	200	105	95'
FRONT YARD	40	22.8'	17.2'
SIDE YARD	75	29.7'	NA
REAR YARD	30	23.1	6.9'
HEIGHT	35	33'4"	NA
OFF STREET PARKING	8	8 SPACES	0
AREA OF DISTURBANCE		9,085 SF	NA
MIN. BUILDING AREA	5,000SF	3,200	NA

PARKING REQUIRED 2 PER APARTMENT, 8 REQUIRED

**NOTES:**

- Survey information taken from a SURVEY PREPARED BY LINK Land Surveying refer to this survey for information.
- Location of existing utilities not performed by this office confirm location of all utilities prior to construction. CALL CALL DIG SAFELY NY
- Contractor to verify all grades and dimensions prior to construction, contractor to inform Landscape Architect with any discrepancies.

**NEIGHBORS**

44-13-16A Thomas Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16B Lynell Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16C Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16D Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16E Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16F Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16G Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16H Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16I Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16J Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16K Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16L Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16M Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16N Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16O Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16P Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16Q Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16R Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16S Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16T Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16U Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16V Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16W Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16X Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16Y Walter Wilson 1140 W. 1st St. Carmel, NY 12016	44-13-16Z Walter Wilson 1140 W. 1st St. Carmel, NY 12016
---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---



tax map and radius

NOTE:

**ROBERTS HERWOOD**  
LANDSCAPE ARCHITECT, LLC


P.O. BOX 564, BROCKFIELD, CT 06804  
pt203.798.1547 c203.994.5337 erobertshw@rhm.com



**SITE CONFORMITY PLAN**

**P&R Estate Corp.**  
122 Glenside  
Carmel NY

#5 STATE DOT	5.16.23
#6 COMMENTS	2.27.23
#4 COMMENTS	4.12.22
#3	2.4.22
#2	3.30.21
#1 comments	12.15.18
REVISIONS:	AS NOTED
SCALE:	AS NOTED
DATE:	6.4.18
JOB NO:	18.14
DRAWING NO:	LP-1.0



- SEDIMENT AND EROSION CONTROL NOTES:**
1. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE CURRENT EDITION OF THE WESTCHESTER COUNTY BEST MANAGEMENT PRACTICES MANUAL FOR EROSION AND SEDIMENT CONTROL.
  2. SILT FENCE SHALL BE INSTALLED AS SHOWN ON THIS DRAWING PRIOR TO BEGINNING ANY CLEARING AND GRADING OR EARTHWORK.
  3. GRASS SEED MIX MAY BE APPLIED BY EITHER MECHANICAL OR HYDROSEEDING METHODS. HYDROSEEDING SHALL BE PERFORMED IN ACCORDANCE WITH THE CURRENT EDITION OF THE NYS DOT STANDARD SPECIFICATION CONSTRUCTION AND MATERIALS, SECTION 603.301, METHOD NO. 1.
  4. CUT OR FILL SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED IMMEDIATELY AFTER GRADING.
  5. PAVED ROADWAYS SHALL BE KEPT CLEAN AT ALL TIMES.
  6. AT THE SITE AT ALL TIMES SHALL BE GRAZED AND MAINTAINED SUCH THAT ALL STORY WATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.
  7. ALL STORY DRAINAGE OUTLETS SHALL BE STABILIZED, AS REQUIRED, BEFORE THE DISCHARGE POINTS BECOME OPERATIONAL.
  8. CUT AND FILL SHALL NOT ENDANGER ADJACENT PROPERTY, NOR DIVERT WATER ONTO THE PROPERTY OF OTHERS.
  9. SEDIMENTATION AND EROSION CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED ON A DAILY BASIS BY OWNERS FIELD REPRESENTATIVE (OFFER) TO INSURE THAT CHANNEL, TEMPORARY AND PERMANENT DITCHES AND PILES ARE CLEAR OF DEBRIS, THAT EMBANKMENTS AND BERRIS HAVE NOT BEEN ENLARGED AND THAT ALL SLOPES SHALL BE AS STATED. ANY FAILURE OF SEDIMENT AND EROSION CONTROL MEASURES SHALL BE IMMEDIATELY REMEDIATED BY THE CONTRACTOR AND INSPECTED FOR APPROVAL BY THE OWNER AND/OR SITE ENGINEER.
  10. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE OWNER.
  11. ALL FILLS SHALL BE COMPACTED TO PROVIDE STABILITY OF MATERIAL AND TO PREVENT SETTLEMENT.
  12. EXCAVATIONS AND FILLS TO BE ROLLED, SEALED AND STABILIZED AT COMPLETION OF EACH CONSTRUCTION DAY.
  13. CONSTRUCTION OF A TEMPORARY STABILIZED GRAVEL CONSTRUCTION ENTRANCE AS INDICATED ON THIS PLAN SHALL COMPLY WITH THE NYS DOT STANDARD SPECIFICATION CONSTRUCTION AND MATERIALS, SECTION 603.301 FOR THE PURPOSE OF CLEANING TIME TRUCKS PRIOR TO VEHICLES ENTERING LEFT OR RIGHT SIDE OF ROADWAY.
  14. CONTRACTOR RESPONSIBLE FOR MAINTAINING SEDIMENTATION AND EROSION CONTROL MEASURES UNTIL FINAL GRADING AND SEEDING STABILIZATION TAKE PLACE.

- LEGEND**
- PROPERTY LINE
  - - - - - SETBACK LINE
  - - - - - 100' WETLAND SETBACK
  - - - - - CENTER LINE
  - - - - - FENCE LINE
  - - - - - WETLAND BOUNDARY
  - - - - - EXISTING CONTOUR
  - EXISTING TREE TO REMAIN
  - ⊗ TREE TO BE REMOVED
  - DRAINAGE DESIGNED BY OTHERS
  - EXISTING UTILITY POLE

**DRAINAGE**

**DRAINAGE CALCULATIONS:**

PROPOSED INCREASE IN IMPERVIOUS SURFACE 1338 SF INCLUDING NEW DRIVEWAY AND DRIVEWAY

25 YEAR STORM EVENT = 6" OF RAINFALL MITIGATED FOR THE IMPERVIOUS SURFACE.

PRE DEVELOPMENT MIXED (1) COEFFICIENT SUBURBAN:  
 $Q = 1.76 \times 1338 \text{ OR } 468.3 \text{ CF}$


POST DEVELOPMENT DRIVEWAY (3) COEFFICIENT:  
 $Q = 5.8 \times 1338 \text{ OR } 6021 \text{ CF}$

POST DEVELOPMENT MINUS PRE DEVELOPMENT + STORAGE REQUIRED 2676 - 6021 = 134 CF

PERMEABLE ASPHALT UTILIZED WITH 24" DEEP GRAVEL RESERVOIR, 150+0.66 CF WATER STORAGE

TOTAL WATER STORAGE OF AREA + AREA X 6.6 2500 X 6.6 + 1650 CF WATER STORAGE AVAILABLE AS 134 CF ARE NEEDED

- △ SITE SPECIFIC NOTES:**
1. PERMEABLE ASPHALT
    1. ASPHALT DRIVEWAY AREA TO BE VACUUMED TWICE PER YEAR TO PREVENT CLOGGING
    2. NO ABRASIVES USED DURING WINTER MAINTENANCE, EX. SAND
    3. DRIVER MAY BE USED BUILT
    4. NO STORAGE OF DIRT OR MULCH MATERIALS/ CLEAN AREA IMMEDIATELY AND VACUUM
  2. WETLAND BUFFER NOTES
    1. DURING CONSTRUCTION NO MACHINES PARKED STORED IN WETLAND BUFFER
    2. IF EQUIPMENT STORED OVERNITE, TO BE STORED OVER 9 MIL POLY PLASTIC
    3. MACHINE NEEDING FUEL TO BE ACCOMPLISHED OUTSIDE OF BUFFER AREA
  3. SILT FENCE TO BE INSTALLED PRIOR TO TREE REMOVAL
  4. SITE CONTRACTOR TO HAVE EMERGENCY SPILL KIT ON SITE TO FACILITATE CLEANUP OF ANY SPILLS DURING CONSTRUCTION.



5. APPLICANT TO INSTALL 4 FOUR SIGNS ALONG BACK OF PARKING AREA INDICATING THE PROPERTY IS WITHIN A TOWN WETLAND BUFFER
6. ALL FILL BROUGHT TO THE SITE MUST BE CERTIFIED PER NYS DEC REGULATIONS AND HANDBOOKS. CERTIFICATION OF FILL MATERIAL BEING DELIVERED SHOULD BE PROVIDED.
7. ALL PLANTINGS TO BE VERIFIED BY THE TOWN OF CARMEL WETLANDS INSPECTOR AND ALL PLANTINGS TO BE INSTALLED PER SECTION 142 OF THE CARMEL TOWN CODE.

- △ CONSTRUCTION SEQUENCE:**
- 1) ESTABLISH DISTURBANCE LIMITS AND DENOTE RESOURCES TO BE PROTECTED.
  - 2) IF EXISTING CONSTRUCTION ENTRANCE IS NOT ADEQUATE, CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AT ROADWAY.
  - 3) INSTALL SILT FENCING AND SEDIMENT CONTROL.
  - 4) MAINTAIN ALL EIC CONTROLS, AS NECESSARY, THROUGHOUT COURSE OF CONSTRUCTION.
  - 5) CONSTRUCT SHRUBS AND TREE PROTECTION MEASURES
  - 6) ACCOMPLISH THE REQUIRED CLEARING/ GRUBBING OF SITE.
  - 7) TOPSOIL REMOVAL AND STOCKPILING PERFORMED WHERE SPECIFIED.
  - 8) STAGED PARKING AREA DURING CONSTRUCTION AND STABILIZE GRADING AS WORK PERFORMED.
  - 9) VEGETATION REMOVALS PER SITE PLAN.
  - 10) DRIVEWAY AND PARKING AREAS TO BE DEVELOPED AS PER PLAN
  - 11) REMOVE STAGING AREAS UPON COMPLETION OF CONSTRUCTION.
  - 12) SOIL RESTORATION OF DISTURBED AREAS
  - 13) REMOVE EROSION AND SEDIMENT CONTROL PRACTICES.

**GENERAL NOTES:**

1. BASE PLAN TAKEN FROM SURVEY PREPARED BY L&L LAND SURVEYORS
2. THE OWNER CONTRACTOR AND/OR HIS AGENT OR AGENTS MUST NOTIFY THE APPROPRIATE UTILITY COMPANIES AND/OR AGENCIES AT LEAST 10 HOURS PRIOR TO ANY CONSTRUCTION, EXCAVATION OR DISPOSAL AT OR NEAR UNDERGROUND FACILITIES IN ACCORDANCE WITH INDUSTRIAL CODE 53.
3. ALL CONTRACTORS SHALL VERIFY EXISTING ELEVATIONS PRIOR TO CONSTRUCTION OF STORM WATER MANAGEMENT SYSTEM. SHOULD INCONGRUENCES IN EXISTING ELEVATIONS BE DETERMINED, CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER PRIOR TO COMMENCING CONSTRUCTION OF THE STORM WATER MANAGEMENT SYSTEM.

**ROBERTS HERWOOD**  
 LANDSCAPE ARCHITECT PLLC  
 P.O. BOX 566, BROOKFIELD, CT 06804  
 P: 203.736.1547 C: 203.944.5337 erobertshw@rhm.com

**P&R Estate Corp.**  
 122 Glenwood  
 Carmel NY


**PROJECT:** GRADING AND DEMOLITION PLAN

**REVISIONS:**

#5 STATE DOT	5.16.23
#4 COMMENTS	2.27.23
#3 COMMENTS	5.23.22
#2 COMMENTS	5.4.22
#1 COMMENTS	4.12.22





**SCALE:** AS NOTED  
**DATE:** 2.4.22  
**JOB NO.:** 18.14  
**DRAWING NO.:** LP-2.0

2 OF 5



### PLANT SCHEDULE

Qty	Common & Botanical Name	Size
GA	Green Giant Arborvitae	8' HT.
YC	Thuja 'Green Giant'	2" Cal.
CC	Yucca Cherry Prunus yedoensis	2" cal.
BOX	Serviceberry Amelanchier canadensis	2" cal.
HYD	American Boxwood Buxus americana	24" HT.
IG	All summer beauty Hydrangeas Hydrangeas	5" Cont.
YB	Hibery Ilex glabra	36"
6	Nannyberry viburnum viburnum lentago	24"
10	Steads holly Ilex cornata steads	36"
10	Virginia Suesappire Itea virginica	24"
11	Joe Pye Weed Eutrochium purpureum	9" Cont.
22	Black Eyed Susan Rudbeckia hirta	1 Cont.
5	Penn Bedgie Carex pennsylvanica	9" Cont.
30	Big Blue Liriope Liriope muscari 'Big Blue'	9" Cont.



#### SEDIMENT AND EROSION CONTROL NOTES:

1. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE CURRENT EDITION OF THE CONNECTICUT COUNTY BEST MANAGEMENT PRACTICES MANUAL FOR EROSION AND SEDIMENT CONTROL.
2. SILT FENCE SHALL BE INSTALLED AS SHOWN ON THIS DRAWING PRIOR TO BEGINNING ANY CLEARING AND GRUBBING OR EARTHWORK.
3. GRASS SEED MIX MAY BE APPLIED BY EITHER MECHANICAL OR HYDROSEEDING METHODS. HYDROSEEDING SHALL BE PERFORMED IN ACCORDANCE WITH THE CURRENT EDITION OF THE NYS DOT STANDARD SPECIFICATION, CONSTRUCTION AND MATERIALS, SECTION 640-4.02, METHOD NO. 1.
4. CUT OR FILL SLOPES STEEPER THAN A 3:1 SHALL BE STABILIZED IMMEDIATELY AFTER GRADING.
5. PAVED ROADWAYS SHALL BE KEPT CLEAN AT ALL TIMES.
6. THE SITE AT ALL TIMES SHALL BE GRADED AND MAINTAINED SUCH THAT ALL STORM WATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.
7. ALL STORM DRAINAGE OUTLETS SHALL BE STABILIZED, AS REQUIRED, BEFORE THE DISCHARGE POINTS BECOME OPERATIONAL.

8. CUT AND FILL SHALL NOT ENDANGER ADJOINING PROPERTY, NOR DIVERT WATER ONTO THE PROPERTY OF OTHERS.
9. SEDIMENTATION AND EROSION CONTROL MEASURES SHALL BE MAINTAINED AND MAINTAINED ON A DAILY BASIS BY OWNERS FIELD REPRESENTATIVE (OFR) TO INSURE THAT CHANNEL, TEMPORARY AND PERMANENT BANKS AND PILES ARE CLEAN OF DEBRIS, THAT EROSION CONTROL MEASURES HAVE NOT BEEN BREACHED AND THAT ALL STRAIN BULKS ARE INTACT. ANY FAILURE OF SEDIMENT AND EROSION CONTROL MEASURES SHALL BE IMMEDIATELY REPAIRED BY THE CONTRACTOR AND IMPROVED FOR APPROVAL BY THE OPR AND/OR SITE ENGINEER.
10. DUST SHALL BE CONTROLLED BY SPRINKLING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE OPR.
11. ALL FILLS SHALL BE COMPACTED TO PROVIDE STABILITY OF MATERIAL AND TO PREVENT SETTLEMENT.
12. EXCAVATIONS AND FILLS TO BE ROLLED, SEALED AND STABILIZED AT COMPLETION OF EACH CONSTRUCTION DAY.
13. CONSTRUCTION OF A TEMPORARY STABILIZED GRAVEL CONSTRUCTION ENTRANCE AS INDICATED ON THIS PLAN SHALL COMPLY WITH A 14" THICK GRAVEL BASE 24 FEET WIDE WITH A TRAIL LENGTH OF 30 FEET FOR THE PURPOSE OF CLEANING TIRE TREADS PRIOR TO VEHICLES ENTERING BEST PRACTICE CURB LINE.
14. CONTRACTOR RESPONSIBLE FOR MAINTAINING SEDIMENTATION AND EROSION CONTROL MEASURES UNTIL FINAL GRADING AND SEEDING STABILIZATION TAKE PLACE.
15. ALL FILL BRINGED TO THE SITE MUST BE CERTIFIED PER NYSDOT REGULATIONS AND MANIFESTATION CERTIFICATION OF FILL MATERIAL BEING DELIVERED SHOULD BE PROVIDED.
16. ALL PLANTING TO BE VERIFIED BY THE TOWN OF CARROLL WETLANDS INSPECTOR AND ALL PLANTINGS TO BE INSTALLED PER SECTION 14 OF THE CARROLL TOWN CODE.

#### SEEDING NOTES:

NEW ENGLAND EROSION CONTROL RESTORATION MIX DIRT SERIES  
NEW ENGLAND WETLAND PLANTS, MIX 808 WEST ST. ATHENAS, MA 01022

1. FINE GRASS AND SEED AREAS DETERMINED BY CONSTRUCTION OPERATIONS AND AREAS NOT COVERED BY BUILDING STRUCTURES, PAVING OR PLANTING AREAS.
2. SPREAD STOCKPOOLED TOPSOIL, PROVIDE CLEAN FILL AND TOPSOIL AS REQUIRED TO MEET FINISH GRADES AS CALLED FOR.
3. THE RATE OF SEEDING SHALL BE PROVIDED PER 500 SF. EROSION MIX SHALL BE SOON BY HAND OR BY APPROVED MACHINE IN SUCH A MANNER THAT A UNIFORM STAND WILL RESULT AFTER SEEDING. THE SURFACE SHALL BE EVENLY RAKED WITH A FINE TOOTHED RAKE.
4. GRASS SEED SHALL BE SOON ONLY BETWEEN APRIL AND JUNE 1 AND BETWEEN AUGUST 15 AND OCTOBER 1 AND DURING APPROVED PERIODS WHEN LEATHER CONDITIONS ARE SUITABLE AS DETERMINED BY THE LANDSCAPE ARCHITECT.
5. LOOSELY APPLY STRAIN MULCH TO ALL SEEDED AREAS.
6. APPLY EROSION CONTROL BURLAP TO ALL SLOPED OVER 1 FOOT VERTICAL TO 2 FEET HORIZONTAL.
7. RESEED ALL AREAS THAT DO NOT SHOW A SATISFACTORY STAND OF GRASS AFTER 30 DAYS AND CONTINUE TO DO SO UNTIL A SATISFACTORY STAND OF GRASS HAS BEEN ESTABLISHED.

#### GENERAL NOTES:

1. BASE PLAN TAKEN FROM SURVEY PREPARED BY LINK LAND SURVEYORS
2. THE OWNER, CONTRACTOR AND/OR HIS AGENTS OR AGENCIES MUST NOTIFY THE APPROPRIATE UTILITY COMPANIES AND/OR AGENCIES AT LEAST 14 DAYS PRIOR TO ANY CONSTRUCTION, EXCAVATION OR DISRUPTION AT OR NEAR UNDERGROUND FACILITIES IN ACCORDANCE WITH INDUSTRIAL CODE 84.
3. ALL CONTRACTORS SHALL VERIFY EXISTING ELEVATIONS PRIOR TO CONSTRUCTION OF STORM WATER MANAGEMENT SYSTEM. SHOULD INCONSISTENCIES IN EXISTING ELEVATIONS BE DETERMINED CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER PRIOR TO COMMENCING CONSTRUCTION OF THE STORMWATER MANAGEMENT SYSTEM.

**ROBERTS HERWOOD**  
LANDSCAPE ARCHITECT, LLC


P.O. BOX 566, BROCKFIELD, CT 06804  
P: 203.736.1547 C: 203.944.5337 erobertshw@rhm.com

**LAYOUT & LANDSCAPE PLAN**

P&R Estate Corp.  
122 Glenwood  
Canaan, NY

PROJECT: #5 STATE DOT 5.18.23  
#4 COMMENTS 2.27.23  
#3 COMMENTS 5.23.22  
#2 COMMENTS 5.4.22  
#1 COMMENTS 4.12.22


REVISIONS:  
SCALE: AS NOTED  
DATE: 2.4.22  
JOB NO: 18.14  
DRAWING NO: LP-3.0  
3 OF 5



- NOTES:**
- POSTS SPACED @ 10' MAX. USE 2" DIA. GALVANIZED OR ALUMINUM POSTS.
  - CHAIN LINK TO POST FASTENERS SPACED @ 12" MAX. USE NO. 6 GA. ALUMINUM WIRE OR NO. 6 GALVANIZED STEEL. PRE-WROUGHT CLIP/CHAIN LINK TO TENSION WIRE FASTENERS SPACED @ 48" MAX. USE NO. 10 GALVANIZED STEEL WIRE. FABRIC TO CHAIN FASTENERS SPACED @ 24" MAX. CENTER TO CENTER.


SILT FENCE DETAIL

NTS



NEW ASPHALT PAVEMENT DETAIL


NTS




- INSTALLATION NOTES:**
- AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
  - HIGHWAY SLOPE OF STOCKPILE SHALL BE 1:1.
  - UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCE OR STRAW BALES, THEN STABILIZED AS NOTED.
  - TEMPORARILY STABILIZE AS NOTED IN SPECIFICATIONS.

SOIL STOCKPILING


NTS



ANTI TRACKING PAD




CURBSIDE OPTION "A" PLAN CURBSIDE OPTION "B" PLAN




CURBSIDE SECTION

- NOTES:**
- ALL MATERIAL TO MEET FILTERBOX SPECIFICATIONS.
  - FILTER MEDIA FILL TO MEET APPLICATION REQUIREMENTS.
  - COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.




PERMEABLE ASPHALT DETAIL

SCALE: NTS




CONCRETE WALK & CURB DETAIL

NOTE: ALL SIDEWALK PAVEMENT SHALL COMPLY WITH ALL STATE AND LOCAL CODES.




Concrete Curb

- NOTES:**
- CONCRETE SHALL BE NYSDOT SPECS CLASS "A" CONCRETE.




NEW CONC. CURB



Typical Reinforced Wall Section

MODULAR BLOCK RETAINING WALL

NTS



ROBERTS HERWOOD  
LANDSCAPE ARCHITECT LLC  
P.O. BOX 566, BROCKFIELD, CT 06804  
pt20373611547 c203.994.5337 robertshw@rhm.com




PROJECT: DETAILS PLAN  
CLIENT: P&R Estate Corp.  
122 Glenside  
Canaan, NY

REVISIONS:  
SCALE: AS NOTED  
DATE: 2.4.22  
JOB NO: 18.14  
DRAWING NO: LP-4.0

- GENERAL NOTES:**
- BASE PLAN TAKEN FROM SURVEY PREPARED BY LINK LAND SURVEYORS
  - THE OWNER, CONTRACTOR, AND/OR HIS AGENTS OR ASSAIGNS MUST NOTIFY THE APPROPRIATE UTILITY COMPANIES AND/OR AGENCIES AT LEAST 24 HOURS PRIOR TO ANY CONSTRUCTION, EXCAVATION OR DISRUPTION AT OR NEAR UNDERGROUND FACILITIES IN ACCORDANCE WITH INDUSTRIAL CODE 83.
  - ALL CONTRACTORS SHALL VERIFY EXISTING ELEVATIONS PRIOR TO CONSTRUCTION OF STORMWATER MANAGEMENT SYSTEMS. SHOULD INCONGRUENCIES IN EXISTING ELEVATIONS BE DETERMINED, CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER PRIOR TO COMMENCING CONSTRUCTION OF THE STORMWATER MANAGEMENT SYSTEMS.



SITE DISTANCE PLAN



LEGEND

- — — — — PROPERTY LINE
- - - - - SETBACK LINE
- - - - - 100' WETLAND SETBACK
- - - - - CENTER LINE
- — — — — FENCE
- - - - - WETLAND BOUNDARY
- — — — — — 100' — — — — — EXISTING CONTOUR
- — — — — — EXISTING TREE TO REMAIN
- ⊗ — — — — — TREE TO BE REMOVED
- — — — — — DRAINAGE DESIGNED BY OTHERS
- — — — — — EXISTING UTILITY POLE

**GENERAL NOTES:**

1. BASE PLAN TAKEN FROM SURVEY PREPARED BY LAND SURVEYORS
2. THE OWNER, CONTRACTOR, AND/OR HIS AGENTS OR ASSAIGNS MUST NOTIFY THE APPROPRIATE UTILITY COMPANIES AND/OR AGENCIES AT LEAST 24 HOURS PRIOR TO ANY CONSTRUCTION, EXCAVATION OR DISPOSAL AT OR NEAR UNDERGROUND FACILITIES IN ACCORDANCE WITH INDUSTRIAL CODE 83.
3. ALL CONTRACTORS SHALL VERIFY EXISTING ELEVATIONS PRIOR TO CONSTRUCTION OF STORM-WATER MANAGEMENT SYSTEMS. SHOULD INCONGRUENCES IN EXISTING ELEVATIONS BE DETERMINED, CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER PRIOR TO COMMENCING CONSTRUCTION OF THE STORM-WATER MANAGEMENT SYSTEMS.



ROBERTS HERWOOD  
LANDSCAPE ARCHITECT LLC  
P.O. BOX 564, BROCKFIELD, CT 06804  
pt203.798.1547 c203.994.5337 erobertshw@rhm.com



**SITE DISTANCE PLAN**

P&R Estate Corp.  
122 Glenside  
Canaan, NY

PROJECT:	
CLIENT:	
DATE:	
SCALE:	AS NOTED
DATE:	4.12.22
JOB NO:	18.14
DRAWING NO:	LP-5.0

#1 comments 3.31.23

REVISIONS:



**1 FRONT ELEVATION**

SCALE: 1/4" = 1'-0"



**2 RIGHT SIDE ELEVATION**

SCALE: 1/4" = 1'-0"



**3 REAR ELEVATION**

SCALE: 1/4" = 1'-0"



**4 LEFT SIDE ELEVATION**

SCALE: 1/4" = 1'-0"

<b>BBS DESIGN, LLC</b>		
17 Buckboard Lane New Milford, CT 06776 Tel: 203.798.0066 E-mail: bbsdesign@sbcglobal.net		
<b>AS BUILT CONDITIONS EXISTING BUILDING</b>		
122 GLENEIDA AVENUE CARMEL, NY		
SCHEMATIC DESIGN		
EXTERIOR ELEVATIONS		
Drawn by	CB	Drawing No.
Checked by	CB	SD-1
Date	10-09-23	
Scale	As noted	
Job No.	955	



February 19, 2024

Town of Carmel Planning Board  
60 McAlpin Avenue  
Mahopac, New York 10541

RE: Diamond Point Development  
4 Baldwin Place Road  
Town of Carmel  
TM#s: 86.10-1-2&3

Dear Chairman Paepre and Members of the Board:

Please find enclosed the following plans and documents in support of an application for site plan approval for the above referenced project:

- Notice of Complete Application from NYCDEP, dated January 19, 2024. (5 copies)
- Dimension Plan, by Colliers Engineering & Design, February 2, 2024. (5 copies)

In our previous correspondence our office has documented the progress made with respect to the outside agencies' review status of the proposed project. For this specific application it is our understanding the NYSDOT and NYCDEP represent the two outside agencies the Board is most concerned with impacting the overall layout for the project. As such we understand the Board is looking for these to agencies to commence with their review of the project.

Since last before the Board we have received the NYCDEP Notice of Complete Application. This is the first step in the NYCDEP process and comes after the initial review of the project. The NYCDEP is currently performing their technical review, but at this time we believe any remaining comments will be detailed in nature. A copy of the Notice of Complete Application has been enclosed for your records.

In addition, since we last appeared before the Board our team has continued to dialogue with the NYSDOT. As the Board may be aware, the NYSDOT has required the driveway be constructed as a right turn entrance only. The revised plans and updated Traffic Impact Report have been forwarded to Creighton Manning Engineering and the Board's consultants for review. With these changes Colliers has indicated that the application is ready to move forward, pending provision contractor information and other clerical information required by the NYSDOT just prior to the issuance of a permit.

It is understood that the Board must direct the Town Planner to provide a draft resolution for conditional Site Plan Approval. Based on the progress made with these two agencies we are requesting an appearance before the Board at your February 28, 2024 meeting to request that the draft resolution be provided for the Board's consideration at the March 14, 2024 meeting.

Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:   
Richard D. Williams, PE  
Senior Principal Engineer

RDW/adt

Enclosures

cc: (All via email only)

Aaron Sommer

Jason Sommer

Jennifer Grey, Esq

Insite File No. 22242.100



January 19, 2024

Mr. Richard D. Williams, Jr., P.E.  
Senior Principal Engineer  
Insite Engineering, Surveying & Landscape Architecture, P.C.  
3 Garrett Place, Carmel  
New York -10512

Via Email: [RWilliams@insite-eng.com](mailto:RWilliams@insite-eng.com)

Re: Diamond Point Development Stormwater Pollution Prevention Plan  
4 Baldwin Place Road  
(T) Carmel, Putnam County  
Tax Map# 86.10-1-2 & 3  
Amawalk Reservoir Basin  
Log # 2023-AM-0284-SP.1

**Rohit T. Aggarwala**  
*Commissioner*

**Paul V. Rush, P.E.**  
Deputy Commissioner  
[prush@dep.nyc.gov](mailto:prush@dep.nyc.gov)

465 Columbus Ave.  
Valhalla, New York  
10595

Tel. (845) 340-7800  
Fax (845) 334-7175

Dear Mr. Williams:

The above-referenced project received by this department was deemed complete on January 19, 2024. The department has commenced review and will notify you by March 4, 2024 of its determination.

If the department fails to notify you within the above referenced time frame, you may notify the Department of its failure by certified mail, return receipt requested. The notice should be sent to my attention at the address below. This notice must include your name, the location of the project, the office with which you filed the application originally, and a statement that a decision is sought in accordance with §18-23(d) (6) of the Rules and Regulations. If the Department fails to notify you within 10 days of the receipt of the notice, your application will be deemed approved, subject to standard terms and conditions as set forth in the regulations.

Should you have any questions regarding this letter, please call the undersigned at (914)749-5357.

Sincerely,

A handwritten signature in black ink that reads 'Mariyam Zachariah'.

Mariyam Zachariah  
Associate Project Manager II  
EOH Project Review Group  
Regulatory & Engineering Programs

Cc: Sommer Aaron, Owner, [asommer@diamondpointdevelopment.com](mailto:asommer@diamondpointdevelopment.com)  
Browne Natalie, DEC, [natalie.browne@dec.ny.gov](mailto:natalie.browne@dec.ny.gov)  
Palmer, Patrick M, NYSDOH, [patrick.palmer@health.ny.gov](mailto:patrick.palmer@health.ny.gov)  
Joseph Paravati, P.E., PCDOH, [Joseph.Paravati@putnamcountyny.gov](mailto:Joseph.Paravati@putnamcountyny.gov)  
Richard Franzetti, P.E., Town of Carmel Engineering, [rjf@ci.carmel.ny.us](mailto:rjf@ci.carmel.ny.us)  
Rose Trombetta, Town of Carmel Planning, [rtrombetta@ci.carmel.ny.us](mailto:rtrombetta@ci.carmel.ny.us)





February 19, 2024

Town of Carmel Planning Board  
60 McAlpin Avenue  
Mahopac, New York 10541

RE: Union Energy Center, LLC Site Plan  
24 Miller Road  
Mahopac, NY 10541  
TM#s: 86.11-1-14

Dear Chairman Paeprer and Members of the Board:

Please find enclosed the following plans and documents in support of an application for site plan approval for the above referenced project:

- Site Plan Set, last revised February 16, 2024.
- Preliminary SWPPP, dated February 16, 2024.
- NYS Governor Hochul Initial Findings from Inter-Agency Fire Safety Working Group on Emergency Response, released December 21, 2023.

In response to open comments received from Director of Code Enforcement, Michael Carnazza, dated December 11, 2023, we offer the below responses:

2. The project was introduced to the Environmental Conservation Board on January 18, 2024. It was generally well received and the members acknowledged the advantages of the battery energy storage system (BESS) technology that is proposed for the site, noting its potential to stabilize the grid and improve the viability renewable energy sources. Additional information about the operation and details of the mitigation and erosion controls were requested. Dialogue will be maintained with the ECB as the applicant pursues permits with NYSDEC and AOCE.
3. The applicant was recently asked by the Fire Department to reduce the driveway slope to 8%. Previously the driveway was shown at 12%. The fire code requires that the driveway be a maximum of 10%, but this maximum can be varied by the fire code official. The plans have been revised to show the driveway at the Fire Code prescribed 10%. Further reduction of the slope would cause the driveway to be further lengthened, which would create additional disturbance, including in the wetland buffer/adjacent area. The applicant is seeking approval of the 10% driveway as permitted by the code.

In response to open comments received from Town Engineer Richard Franzetti, PE, dated December 5, 2023, we offer the following responses:

General Comments

---

3 Garrett Place, Carmel, New York 10512 (845) 225-9690 Fax (845) 225-9717  
[www.insite-eng.com](http://www.insite-eng.com)

1. A revised Wetland Function, Value and Impact report will be provided with a future submission addressing these concerns.
2. The required permits are acknowledged with the exception of the NYSDOT, and PCDHF as there is no frontage or proposed work within a state or county right of way.
3. A Preliminary SWPPP is enclosed herewith.

#### Detailed Comments

1. Sight distance calculations and a driveway profile will be provided with a future submission.
2. A Preliminary SWPPP is enclosed herewith. Rims and inverts, hydraulic calculations and pipe sizing will be provided with a future submission.
3. A Preliminary SWPPP is enclosed herewith. Rims and inverts, hydraulic calculations and pipe sizing will be provided with a future submission.

In response to open comments received from Town Planner, Patrick Cleary, dated December 14, 2023, we offer the below responses:

3. To clarify, there is proposed tree clearing for the project. As has been discussed the site is wooded, and a proposed tree line is indicated on the plans. The limited tree pruning and brush removal along the frontage is in reference to the sight distance at the proposed driveway on Miller Road.

In response to comments received from the Board, we offer the below responses:

1. The enclosed findings report on the governor's inter-agency fire safety working group on emergency response was released on December 21, 2023. The report concludes that, "Based on available analyses of air quality, soil, or water data collected in the days following the incidents, the Working Group concluded that there were no reported injuries and no harmful levels of toxins detected...Based on the information available to date, there is no evidence of significant off-site migration of contaminants associated with the fires."
2. The applicant has inquired with the town assessor about when final assessment values are assigned to new construction and it was indicated that this is typically done after construction has begun.

We respectfully request to be placed on the February 28, 2024, Planning Board agenda for discussion of the project with the Board. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:   
Richard D. Williams, Jr., PE  
Senior Principal Engineer

RDW/adt

Enclosures

cc: (All via email only)

Scott Connuck

Compton Donohue

Frank Smith, Esq

William Shilling, Esq

Mahopac Volunteer Fire Dept

Insite Project#: 21120.100



February 19, 2024

Town of Carmel Planning Board  
60 McAlpin Avenue  
Mahopac, New York 10541

RE: Union Energy Center, LLC Subdivision  
24 Miller Road  
Mahopac, NY 10541  
TM#s: 86.11-1-14

Dear Chairman Paepre and Members of the Board:

In response to open comments received from Director of Code Enforcement, Michael Carnazza, dated December 11, 2023, we offer the below responses:

3. The project was introduced to the Environmental Conservation Board on January 18, 2024. It was generally well received, and the members acknowledged the advantages of the battery energy storage system (BESS) technology that is proposed for the site, noting its potential to stabilize the grid and improve the viability of renewable energy sources. Additional information about the operation and details of the mitigation and erosion controls were requested. Dialogue will be maintained with the ECB as the applicant pursues permits with NYSDEC and AOCE.

Please place the project on the February 28, 2024 Planning Board agenda for discussion of the project with the Board. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:   
Richard D. Williams, Jr., PE  
Senior Principal Engineer

RDW/adt

Enclosures

cc: (All via email only)

Scott Connuck  
Compton Donohue  
Frank Smith, Esq  
William Shilling, Esq  
Mahopac Volunteer Fire Dept

Insite Project#: 21120.100

---

3 Garrett Place, Carmel, New York 10512 (845) 225-9690 Fax (845) 225-9717  
[www.insite-eng.com](http://www.insite-eng.com)

Z:\E\21120100 East Point Energy, Union Valley Road\Correspondence\2024\021924cbp-subdivision.doc



For Immediate Release: 12/21/2023

GOVERNOR KATHY HOCHUL

**GOVERNOR HOCHUL ANNOUNCES RELEASE OF INITIAL FINDINGS FROM INTER-AGENCY  
FIRE SAFETY WORKING GROUP ON EMERGENCY RESPONSE**

***Available Analyses Find No Reported Injuries, No Harmful Levels of Toxins Detected at Sites  
of Battery Storage Fires***

***Draft Fire Code Reviews Recommendations Expected to be Released for Public Comment in  
First Quarter 2024***

***Statewide Battery Storage System Inspections Expected to Conclude by the Second Quarter  
2024***

Governor Kathy Hochul today released initial findings from the Inter-Agency Fire Safety Working Group, which was convened following fires at battery energy storage systems at facilities in Jefferson, Orange and Suffolk Counties this summer. The Working Group has made significant progress in evaluating both preventive and reactive standards and practices for battery system fire safety, in addition to analyzing the impacts of the fires. Based on available analyses of air quality, soil, or water data collected in the days following the incidents, the Working Group concluded that there were no reported injuries and no harmful levels of toxins detected. Additionally, statewide battery system project assessments and fire code reviews are currently underway with draft recommendations expected to be released for public comment in the first quarter of 2024.

“New York State is grateful to the first responders who were on the scene at these fires, and we are taking this opportunity to ensure they can continue to do their jobs safely and effectively,” **Governor Hochul said.** “As we continue to advance New York’s clean energy transition, maintaining this safety is of the utmost importance. Thankfully, the Working Group’s analysis shows no notable lasting impacts on the health or safety of the first responders or the communities they serve.”

The Working Group includes representatives from the Division of Homeland Security and Emergency Services (DHSES) Office of Fire Prevention and Control (OFPC) New York State Energy Research and Development Authority (NYSERDA), New York State Department of Environmental Conservation (DEC), Department of Public Service (DPS), and the Department of State (DOS). The group was convened in August 2023 and has gathered data and worked diligently with project developers, equipment manufacturers, and government officials to learn as much as possible about the fires at the three battery system sites.

The data assembled and analyzed by the Working Group includes:

- An air monitoring report from the OFPC, and soil and water sampling data received from DEC from the Chaumont site.
- On-site air monitoring results collected from the Warwick sites and relayed to the Working Group by local officials.

- On-site soil sampling results from the East Hampton site relayed to the Working Group by a project developer.
- An independent third-party site inspection report consisting of air monitoring and surface sampling at school buildings in the vicinity of the June 27, 2023, fire at the Warwick site.

Based on the information available to date, there is no evidence of significant off-site migration of contaminants associated with the fires.

**New York State Energy Research and Development Authority President and CEO Doreen M. Harris said,** “NYSERDA remains committed to working with our state agency partners, project developers and local communities to ensure a responsible transition to a zero-emissions grid and making available the data and resources needed to facilitate that transition in a safe and responsible manner.”

**New York State Division of Homeland Security and Emergency Services Commissioner Jackie Bray said,** “Battery energy storage sites are essential to securing our climate future. As these technologies continue to be implemented throughout the state, we will work closely with our partners to ensure they are operated safely.”

**Department of Public Service CEO Rory M. Christian said,** “The Department is pleased that the Working Group has made significant progress in evaluating both preventive and reactive standards and practices for battery system fire safety, in addition to analyzing the impacts of recent battery storage fires. Kudos to Governor Hochul for creating the working group. The Department will continue working to ensure safety comes first as more and more batteries come into service.”

**New York State Department of Environmental Conservation Commissioner Basil Seggos said,** “DEC applauds Governor Hochul for prioritizing New Yorkers’ safety and taking the lead to ensure energy storage deployment projects continue to be protective of our communities and the environment. DEC experts assisted the Fire Safety Working Group by analyzing current practices, assisting in site testing, enhancing emergency response measures, and identifying improvements in operations at facilities with vital roles in building a safe and responsible clean energy future for our state. We look forward to working with our partner agencies in continuing to advance this important work.”

In addition to the air, soil, and water quality analysis described above, the Working Group has partnered with subject matter experts to inspect all operational battery systems above 300 kW in New York, which accounts for the majority of commercial battery systems in service across the state. Inspections are currently underway and are slated to be complete by the second quarter of 2024. The goal of these inspections is to revise the current evaluation checklists and best-practices available for use by NYSERDA and others prior to energizing the systems, and to incorporate lessons learned from the battery fires while enhancing emergency response measures.

Battery energy storage systems are a critical component to achieving a reliable, zero-emissions grid. New York is taking the lead in addressing the incidents head on by forming the inter-agency fire and safety working group. The conclusions and recommendations will improve the way energy storage projects are deployed in New York and across the country. New York's Working Group has drawn national attention from other states as the industry is strongly invested in improving energy storage deployment best practices on a broader scale.

The Working Group is concluding negotiations with the impacted facilities’ battery manufacturers and utility companies to secure Root Cause Analysis (RCA) reports for the Warwick, East Hampton, and Chaumont fires. Subject matter experts will review and analyze the reports once they are made available.

Additionally, the Working Group has been collaborating with national labs and other nation-leading subject matter experts to review all existing codes and testing procedures pertinent to the development and electrification of battery energy storage systems. The Working Group is actively assessing all relevant codes and standards and will make recommendations to ensure building and fire codes are adequate and appropriate. Draft recommendations will be available for public comment in the first quarter of 2024.

Following the fires, the OFPC has made a Lithium-Ion Battery Awareness training course available on the [DHSES E-Learning Management System](#) for all first responders. According to the OFPC over 2,000 participants have taken the course to date.

New York State's nation-leading climate agenda calls for an orderly and just transition that creates family-sustaining jobs, continues to foster a green economy across all sectors and ensures that at least 35 percent, with a goal of 40 percent, of the benefits of clean energy investments are directed to disadvantaged communities. Guided by some of the nation's most aggressive climate and clean energy initiatives, New York is on a path to achieving a zero-emission electricity sector by 2040, including 70 percent renewable energy generation by 2030, and economywide carbon neutrality by mid-century. A cornerstone of this transition is New York's unprecedented clean energy investments, including more than \$52 billion in 118 large-scale renewable and transmission projects across the state, \$6.8 billion to reduce building emissions, \$3.3 billion to scale up solar, nearly \$3 billion for clean transportation initiatives, and over \$2 billion in NY Green Bank commitments. These and other investments are supporting more than 165,000 jobs in New York's clean energy sector in 2021 and over 3,000 percent growth in the distributed solar sector since 2011. To reduce greenhouse gas emissions and improve air quality, New York also adopted zero-emission vehicle regulations, including requiring all new passenger cars and light-duty trucks sold in the State be zero emission by 2035. Partnerships are continuing to advance New York's climate action with nearly 400 registered and more than 100 certified Climate Smart Communities, nearly 500 Clean Energy Communities, and the State's largest community air monitoring initiative in 10 disadvantaged communities across the state to help target air pollution and combat climate change.

###



## PRELIMINARY STORMWATER POLLUTION PREVENTION PLAN

For

Union Energy Center  
Miller Road  
Town of Carmel, New York

February 16, 2024

**Applicant Information:**

East Point Energy, LLC  
310 4<sup>th</sup> Street NE, 3<sup>rd</sup> Floor  
Charlottesville, VA 22902



**Note: This report in conjunction with the project plans make up the complete Stormwater Pollution Prevention Plan.**

Prepared by:  
Insite Engineering, Surveying & Landscape Architecture, P.C.  
3 Garrett Place  
Carmel, New York 10512



## CONTENTS

<b>1.0</b>	<b>INTRODUCTION</b> .....	<b>1</b>
1.1	Project Description .....	1
1.2	Existing Site Conditions (Pre-Development) .....	1
1.3	Proposed Site Conditions (Post Development).....	2
<b>2.0</b>	<b>STORMWATER MANAGEMENT</b> .....	<b>3</b>
2.1	Chapter 10: Enhanced Phosphorus Removal Standards .....	4
2.2	NYSDEC Runoff Reduction Volume (RR <sub>v</sub> ) .....	5
2.3	NYSDEC Water Quality Volume (WQ <sub>v</sub> ).....	6
2.4	NYSDEC Stream Channel Protection Volume (CP <sub>v</sub> ) .....	7
2.5	NYSDEC Overbank Flood Control (Q <sub>p</sub> ), and Extreme Flood Control (Q <sub>t</sub> ) .....	8
2.6	NYCDEP Requirements .....	8
<b>3.0</b>	<b>STORMWATER CONVEYANCE SYSTEM</b> .....	<b>10</b>
<b>4.0</b>	<b>EROSION AND SEDIMENT CONTROL</b> .....	<b>10</b>
4.1	Temporary Erosion and Sediment Control Facilities.....	11
4.2	Permanent Erosion and Sediment Control Facilities .....	12
<b>5.0</b>	<b>IMPLEMENTATION AND MAINTENANCE</b> .....	<b>12</b>
5.1	Construction Phase .....	12
5.2	Soil Restoration .....	14
5.3	Long Term Maintenance Plan .....	16

### APPENDICES

Appendix A	RR <sub>v</sub> Calculations
Appendix B	Pre-Development Computer Data
Appendix C	Post-Development Computer Data
Appendix D	NYSDEC SPDES for Construction Activities Construction Site Log Book
Appendix E	Project and Owner Information
Appendix F	NYSDEC Stormwater Management Practice Construction and Maintenance Checklists
Appendix G	Draft NYSDEC Notice of Intent and MS4 SWPPP Acceptance Form
Appendix H	Draft Stormwater Maintenance and Access Agreement

### FIGURES

Figure 1:	Location Map
Figure 2:	Pre-Development Drainage Map
Figure 3:	Post-Development Drainage Map



## 1.0 INTRODUCTION

### 1.1 Project Description

The subject project is located on three adjacent parcels totaling 95.5± acres on Miller Road and Union Valley Road in the Town of Carmel. The parcel and its surroundings are delineated on the attached Location Map (Figure 1). The property is designated as Tax Map Number 86.11-1-14, 86.11-1-15, and 86.8-2-85 and is located in the Commerce/Business Park (C/BP) zoning district. Tax map number 86.11-1-14 consisting of 0.4± acres is currently developed as a commercial facility known as The Teal Door Counseling Center. Tax map number 86.8-2-85 is currently developed as a New York State Electric and Gas (NYSEG) substation and consists of 1.6± acres. Tax map number 86.11-1-14 consists of 93.5± acres and is currently undeveloped woods. The NYSDEC Regulated Wetland F-26 is located across a large part of the project site. The subject project proposes a lot line adjustment between the three parcels whereas the proposed lots will consist of the following:

- Proposed Lot 1 (78.9± acres) is proposed to be developed as an energy storage facility and substation to connect to the adjacent NYSEG transmission lines that currently traverse an easement on the site.
- Proposed Lot 2 (12.3± acres) will contain the existing NYSEG substation and be further developed with a second utility substation to function as the connection between the project substation and NYSEG transmission lines.
- Proposed Lot 3 (4.3± acres) will contain the existing Teal Door Counseling Center development. There is no improvements proposed to this lot.

The project proposes to develop 9.2 acres of new impervious surfaces on the site consisting of gravel driveways and storage pads and battery enclosures. Approximately 18.7 acres of soil disturbance is proposed for the subject project. It is proposed to capture and treat the stormwater runoff associated with the proposed improvements. The project site is located in the Amawalk and Muscoot Watershed.

The following permits are required for the project:

PERMIT	STATUS
<b>TOWN OF CARMEL</b>	
Planning Board Site Plan & Subdivision Approval	Pending
Wetland Permit	Pending
<b>NEW YORK CITY DEPARTMENT OF ENVIRONMENTAL PROTECTION</b>	
SWPPP Approval	Pending
<b>U.S. ARMY CORP. OF ENGINEERS</b>	
Wetland Fill Permit	Not Submitted Yet
<b>NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION</b>	
SWPPP General Permit Coverage (GP-0-20-001)	Not Submitted Yet
Freshwater Wetlands Permit	Not Submitted Yet
Public Service Commission Section 68 Certificate of Public Convenience and Need	Not Submitted Yet

There are no known enforcement actions, and no lawsuits or administrative proceedings, commenced against the applicant, or any principle affiliate of the applicant, for any alleged violations of law related to the applicant of the site, in the five years preceding this application.

### 1.2 Existing Site Conditions (Pre-Development)

The subject property is located in the Town of Carmel, between Miller Road and Silver Gate Road and just north of the border between Town of Carmel, Putnam County and Town of Somers, Westchester County. The project site has frontage along Miller Road to the west and Union Valley Road to the north. The project site consists of three properties, two of which are currently developed as discussed above and one is currently undeveloped, and the ground cover consists of mostly wooded areas. There is an

existing NYSDEC Regulated Wetland F-26 across a large portion of the property. The NYSDEC Wetland is divided on the property by a ridge that runs north to south through the center of the site.

Stormwater runoff from the west side of the site flows overland to the NYSDEC Wetland and discharges off the property through a stream that is ultimately tributary to the Amawalk Reservoir. Stormwater runoff from the east side of the site flows overland to the NYSDEC Wetland which discharges off the property and is ultimately tributary to the Muscoot Reservoir.

The stormwater analysis included in the subject SWPPP utilizes two design points. The design points can be seen on Figure 2 and 3 and are identified as Design Point 1 and Design Point 2. Design Point 1, tributary to the Amawalk Reservoir, is located in the southwest corner of the site where the NYSDEC Regulated Wetland discharges offsite. Design Point 2, tributary to the Muscoot Reservoir, is located in the southeast corner of the site where the NYSDEC Regulated Wetland discharges offsite. The design points are used to assess the stormwater runoff from the property and any potential impacts from the proposed development to the existing natural resources and stormwater conveyance systems downstream of the project site. The pre-development contributing areas to the Design Points are identified as subcatchment PRE 1 and PRE 2.

The hydrologic soils groups for the project consists of "C", "D", "A/D", "B/D", and "C/D". The designations of the onsite soils located within the proposed limits of disturbance consist of Fluvaquents-Udifiuents complex (Ff), Natchaug muck (NcA), Paxton Fine Sandy Loam (PnB, PnC and PnD), Ridgebury Complex (RdA, RdB and RgB), and Sun Loam (Sh) as identified on the Soil Conservation Service Web Soil Survey. The soils boundaries are shown on Figure 2 and 3 of this report. The following soil group descriptions are as defined by Soil Conservation Service Web Soil Survey.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

When soils are assigned to a dual hydrologic group (A/D, B/D and C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes, therefore the soils with dual hydrologic groups were modeled as a "D" soil in Appendix B and C.

### 1.3 Proposed Site Conditions (Post Development)

The proposed project includes the construction of an energy storage facility and substation consisting of gravel driveways and storage pads for the battery storage and substations. Mitigation for the newly created impervious surfaces will be provided in the form of proposed stormwater management practices (SMP's) discussed further in later sections of this report. The proposed SMP's will be designed to capture and treat runoff from the impervious surfaces associated with the proposed improvements including the battery storage enclosures, gravel driveways and storage pads.

It is proposed to maintain the existing drainage patterns on the site to the maximum extent practical in the proposed condition to minimize the impact to the existing downstream wetland, watercourse and stormwater conveyance systems.

Stormwater treatment for the subject development will be accomplished with several different practices including dry pretreatment basins, I-2 Infiltration Basins, and P-1 Micropool Extended Detention Ponds prior to the discharge to the existing downstream NYSDEC Regulated Wetlands. The proposed standard stormwater management practices have been sized to capture and treat the Water Quality Volume from the proposed improvements.

As shown in the following sections of this report, the stormwater quality and quantity for the proposed development have been mitigated in accordance with the NYSDEC design standards. Additionally, an erosion and sediment control plan has been prepared in accordance with the New York State Standards and Specifications for Erosion and Sediment Control to protect the existing waterbodies and drainage features during construction activities and in the post development condition.

## 2.0 STORMWATER MANAGEMENT

The proposed stormwater management system for the Union Energy Center project has been designed to meet the requirements of local, regional, and state stormwater ordinances and guidelines, including but not limited to the Town of Carmel, NYCDEP and the NYSDEC. Specifically, the following codes / regulations have been used to design this SWPPP:

- *NYSDEC SPDES General Permit for Stormwater Discharges from Construction Activities, General Permit GP-0-20-001 (GP-0-20-001).*
- *NYCDEP Rules and Regulations for the Protection from Contamination, Degradation, and Pollution of the New York City Water Supply and its Sources (Rules and Regulations).*

Since the subject project proposes the disturbance of more than 1 acre, coverage under the New York State Department of Environmental Conservation (NYSDEC) SPDES General Permit for Stormwater Discharges from Construction Activities (GP-0-20-001) is required.

In order to meet the requirements set forth by GP-0-20-001, and the latest edition of the NYSDEC *New York State Stormwater Management Design Manual (Design Manual)*, including the requirements listed in Chapter 10: *Enhanced Phosphorus Removal Standards (Chapter 10)* was referenced for the design of the proposed stormwater collection, conveyance and treatment system. The Design Manual specifies five design criteria that are discussed in detail below. They are Runoff Reduction Volume (RR<sub>v</sub>), Water Quality Volume (WQ<sub>v</sub>), Stream Channel Protection Volume (CP<sub>v</sub>), Overbank Flood Control (Q<sub>f</sub>), and Extreme Storm Control (Q<sub>p</sub>). The first two requirements relate to treating water quality, while the latter pertain to stormwater quantity (peak flow) attenuation.

With regard to NYCDEP requirements, per Section 18-39(b)(4) of the Rules and Regulations, the project meets three (3) of the thresholds that require SWPPP approval from the NYCDEP. For further discussion on NYCDEP requirements, refer to Section 2.6 below. However, it should be noted that in addition to the Design Manual requirements, two different SMP's are required to be placed in series when drainage areas to an SMP is over 20% impervious and infiltration cannot be provided.

Where WQ<sub>v</sub>/RR<sub>v</sub> treatment is required, the following post construction green infrastructure and stormwater management practices are proposed for the project:

**Table 2.0.1 – Proposed GIP/SMP Design Criteria Summary Table**

GIP/SMP ID	Proposed Subcatchment	NYSSMDM Ch. 6 Design Designation	NYSDEC Uniform Stormwater Sizing Criteria Satisfied	NYCDEP Requirement Satisfied
1.1P	1.1S	P-1 Micropool Extended Detention	WQ <sub>v</sub> , CP <sub>v</sub> , Q <sub>p</sub> , Q <sub>f</sub>	Only Practice Required to be Provided
2.2P	2.2S			
2.3P	2.3S			
1.2P	1.2S	I-2 Infiltration Basin	WQ <sub>v</sub> , RR <sub>v</sub> , CP <sub>v</sub> , Q <sub>p</sub> , Q <sub>f</sub>	Only Practice Required to be Provided
1.3P	1.3S			
2.1P	2.1S			

To address stormwater quantity requirements of the NYSDEC, the “HydroCAD” Stormwater Modeling System,” by HydroCAD Software Solutions LLC in Tamworth, New Hampshire, was used to model and assess the peak stormwater flows for the subject project. HydroCAD is a computer aided design program for modeling the hydrology and hydraulics of stormwater runoff. It is based primarily on hydrology techniques developed by the United States Department of Agriculture, Soil Conservation Service (USDA, SCS) TR-20 method combined with standard hydraulic calculations. For details on the input data for the subcatchments and design storms, refer to Appendices A through C and for the supporting data relative to the soil breakdown within the overall contributing area shown in the HydroCAD analysis, see Appendix B and C of this report:

The input requirements for the HydroCAD computer program are as follows:

Subcatchments (contributing watershed/sub-watersheds)

- Design storm rainfall in inches
- CN (runoff curve number) values which are based on soil type and land use/ground cover
- Tc (time of concentration) flow path information

Flow Splitters / Stormwater Management Practices

- Surface area at appropriate elevations
- Flood elevation
- Outlet structure information

The following is a general description of the input data used to calculate the pre- and post-development stormwater runoff values. For detailed information for each subcatchment and pond, see Appendices B & C. The precipitation values for the 1-Year, 10-Year, 100-Year 24-hour design storm events and rainfall distribution curves utilized for this report were obtained from the information provided by Northeast Regional Climate Center (NRCC) and the Natural Resources Conservation Service(NRCS) which is available online at [www.precip.eas.cornell.edu](http://www.precip.eas.cornell.edu). The values provided for all design storms analyzed are listed below.

<b>Design Storm</b>	<b>24-Hour Rainfall</b>
1-Year	2.76”
10-Year	5.03”
100-Year	9.05”

The CN (runoff curve number) values utilized in this report were referenced from the USDA, SCS publication *Urban Hydrology for Small Watersheds*.

## 2.1 Chapter 10: Enhanced Phosphorus Removal Standards

As noted above, the New York City East of Hudson Watershed has been identified in the SPDES General Permit GP-0-20-001 as a watershed requiring compliance with the Enhanced Phosphorus Removal Standards when post-construction stormwater management practices are proposed. Chapter 10 establishes four goals to meet sizing performance standards:

- Goal 1: Reducing Runoff Volumes
- Goal 2: Effective Bypass Treatment
- Goal 3: Achieving Effluent Concentrations for Particulate Phosphorus
- Goal 4: Achieving Effluent Concentrations for Dissolved Phosphorus

In order to achieve the first goal, the site design shall, “ assess the feasibility of hydrological source controls and reduce the total water quality volume by source control, implementation of green infrastructure, or standard SMP’s with RR<sub>v</sub> capacity, according to the process defined in Chapters 3 and 4 of the Design Manual. Each plan must include a rationale for acceptance and rejection of the various controls.” A discussion on RR<sub>v</sub> can be found in section 2.2 below. Based upon the results of onsite soil testing, the soils onsite in select areas are suitable for infiltration. Therefore, the use an infiltration practice (classified as Standard SMP’s with RR<sub>v</sub> capacity) has been maximized, specifically infiltration

basins were selected to treat the stormwater runoff from a portion of the proposed impervious surfaces and satisfy RR<sub>v</sub> minimum requirements. As such, Goal 1 has been achieved in this SWPPP.

Goal 2 cites that proposed stormwater management practices should achieve less than 15% effective treatment bypass of the long-term runoff volume. Chapter 10 further notes this goal is satisfied by capturing and treating the 1-year 24-hour design storm. The NYSDEC stormwater quality treatment practices proposed for this have been designed in accordance with Chapter 10 by utilizing the 1-yr, 24-hour design storm to generate the WQ<sub>v</sub> / RR<sub>v</sub>. As such, Goal 2 has been achieved in this SWPPP.

Achieving effluent concentrations for particulate phosphorus, Goal 3, is satisfied by achieving an 80% net removal of particulate phosphorus for a median influent concentration of 0.5mg/l. Chapter 10 states that through designing proposed SMP's in accordance with Section 10.4 this goal will be achieved. The proposed I-2 infiltration basins and P-1 micropool extended detention ponds have been designed in accordance with Section 10.4 of Chapter 10 thus satisfying the requirements of this goal.

Goal 4, achieving effluent concentration for dissolved phosphorus, is achieved by obtaining a 60% net removal of dissolved phosphorus given a median influent concentration of 0.15mg/l. As with Goal 3, Goal 4 is achieved by designing the proposed SMP's in accordance with Section 10.4 of Chapter 10. As noted above the proposed I-2 infiltration basins and P-1 micropool extended detention ponds have been designed in accordance with section 10.4 of Chapter 10 thus satisfying the requirements of this goal.

## 2.2 NYSDEC Runoff Reduction Volume (RR<sub>v</sub>)

The Runoff Reduction Volume (RR<sub>v</sub>) criterion is intended to replicate pre-development hydrology by maintaining preconstruction infiltration, peak flow runoff, discharge volume, as well as minimizing concentrated stormwater flow. As stated in Chapter 4 of the Design Manual, RR<sub>v</sub> may be treated with standard stormwater management practices (SMP's) sized in accordance with the Chapter 4/6 requirements, or with green infrastructure practices (GIP's) sized in accordance with the requirements set forth for each practice in Chapter 5. Runoff reduction is achieved when runoff from a percentage of the impervious area on the site is captured, routed through a SMP or a GIP, infiltrated to the ground, reused, reduced by evapotranspiration, and eventually removed from the stormwater discharge from the site. However, if 100% of the WQ<sub>v</sub> cannot be reduced by applying a combination of green infrastructure techniques and standard SMP's with RR<sub>v</sub> capacity, "they must, at a minimum, reduce runoff from a percentage of the impervious area constructed as part of the project using the green infrastructure techniques and standard SMPs with RR<sub>v</sub> capacity. In addition, the designer must provide justification in the SWPPP that evaluates each of the green infrastructure techniques listed in Table 3.2 and identify the specific site limitations that make application of the technique(s) infeasible."

Although infiltration practices designed as SMPs with the runoff reduction capacity equal to 100% of the WQ<sub>v</sub> have been implemented to the maximum extend practical, the project SWPPP cannot provide 100% of the WQ<sub>v</sub> through the implementation of GIP's or standard SMP's with RR<sub>v</sub> capacity upstream of Design Point 1 and Design Point 2. This is due to the existing onsite soil conditions and topography in the area of the proposed improvements, thus minimizing the area where infiltration practices for treatment of the RR<sub>v</sub> / WQ<sub>v</sub> is possible.

Section 4.3 of the Design Manual states for sites that do not achieve runoff reduction to pre-construction condition must, at a minimum reduce a percentage of the runoff from impervious areas to be constructed on the site a minimum RR<sub>v</sub>. The following equation can be used to determine the minimum runoff reduction volume:

The minimum runoff reduction volume shall be  $RR_{v\text{minimum}} = \frac{(P)(R_v)(A_i)}{12}$

Where,

- S = Hydrologic Soil Group (HSG) Specific Reduction Factor
- A<sub>ic</sub> = Total Area of New Impervious Cover
- A<sub>i</sub> = Impervious cover targeted for Runoff Reduction
- = (S)(A<sub>ic</sub>)
- R<sub>v</sub> = 0.95

Although 100% of the WQ<sub>v</sub> can not be treated through the implementation of GIP's or standard SMP's with RR<sub>v</sub> capacity upstream of Design Point 1 and Design Point 2, the project SWPPP addresses and satisfies the RR<sub>v</sub> requirements of the Design Manual. In order to meet these requirements to the maximum extent practicable, the project SWPPP has minimized the creation of impervious surfaces to the maximum extent practicable. The types of GIP's and standard SMP's with RR<sub>v</sub> capacity that can be employed onsite are limited. The project SWPPP as required by the Design Manual meets and exceeds the RR<sub>v</sub> minimum required upstream of Design Point 1 and Design Point 2. For this project infiltration practices have been employed upstream of Design Point 1 and Design Point 2 to the maximum extent practical in order to meet the RR<sub>v</sub> requirements.

For a calculation of the Initial WQ<sub>v</sub> / RR<sub>v</sub>, the RR<sub>v</sub> minimum, the RR<sub>v</sub> / WQ<sub>v</sub> required, and the RR<sub>v</sub> provided, refer to Appendix A. In calculating the RR<sub>v</sub> minimum, onsite soils belong to the Hydrologic Soil Groups C and D. These soil groups have a specific reduction factor of 0.30 and 0.20, respectively. Listed in Table 2.2.1 below is a summary of the NYSDEC compliant practices, and their satisfaction of the NYSDEC RR<sub>v</sub> requirements:

**Table 2.2.1 Runoff Reduction Volume Summary**

Design Point	Subcatchment	RR <sub>v</sub> Required = WQ <sub>v</sub> (c.f.) From Appendix C	RR <sub>v</sub> Minimum (c.f.) Calculated in Appendix A	GIP/SMP ID	NYSDEC Practice Designation	Allowable % of WQ <sub>v</sub> provided to be applied towards RR <sub>v</sub>	Storage Volume Provided below System Outlet (c.f.) (From Appendix C)	RR <sub>v</sub> Provided (c.f.)
1	1.1S	10,106	10,850	1.1P	P-1 Pond	0%	-	29,621
	1.2S	12,720		1.2P	I-2 Infiltration Basin	100%	13,625	
	1.3S	16,901		1.3P			17,219	
2	2.1S	18,905	12,335	2.1P	I-2 Infiltration Basin	100%	19,500	18,905
	2.2S	18,339		2.2P	P-1 Pond	0%	-	
	2.3S	12,632		2.3P				

As previously stated, 100% of the RR<sub>v</sub>Required could not be provided upstream of Design Point 1 and Design Point 2 due to existing onsite soil conditions and topography which limited the area where infiltration is feasible. Although 100% of the RR<sub>v</sub>Required was not provided for Design Point 1 and 2, the project satisfies the RR<sub>v</sub> criteria by providing greater than the RR<sub>v</sub>minimum through the implementation of infiltration practices to the maximum extent practical.

### 2.3 NYSDEC Water Quality Volume (WQ<sub>v</sub>)

The proposed stormwater management practices have been sized in accordance with Chapter 4 and 6 of the Design Manual in order to treat the entire WQ<sub>v</sub> from the contributing area. The I-2 Infiltration Basins have been sized to provide storage of the entire WQ<sub>v</sub> between the bottom of the practice and the

outlet condition, as verified in Appendix C. The P-1 Micropool Extended Detention Ponds have been designed to provide the required WQ<sub>v</sub> storage volume within the permanent pool and in extended detention. The subject project is located in the New York City Watershed, which is listed as a phosphorus-limited watershed per the NYSDEC regulations. Therefore, the stormwater management practices have been designed in general accordance with the Enhanced Phosphorus Removal Supplement (Chapter 10) of the Design Manual. As outlined in Chapter 10, the treatment volume for the WQ<sub>v</sub> is the runoff volume produced during the 1-year 24-hour design storm. See table 2.6.1 for a summary of the WQ<sub>v</sub> generated by the proposed improvements during the 1-year, 24-hour storm.

Three P-1 Micropool Extended Detention Ponds are proposed to treat the water quality volume from subcatchments 1.1S, 2.2S and 2.3S. The P-1 Ponds have been sized in accordance with Chapter 6 and Chapter 10 of the Design Manual as shown in the table below.

**Table 2.3.2 P-1 Micropool Extended Detention Pond Summary**

Design Elements	Required			Provided			Remarks
	1.1P	2.2P	2.3P	1.1P	2.2P	2.3P	
Pond Location	Not within Jurisdictional Waters			Outside of Jurisdictional Waters			See Project Plans
Forebay Volume	10% of WQ <sub>v</sub>			3,500 cf	2,300 cf	1,400 cf	See Appendix C
	1,011 cf	1,834 cf	1,263 cf				
Forebay Depth	4' Min. – 6' Max.			4' Provided			See Project Plans
WQ <sub>v</sub> Storage	20% Min. within Permanent Pool			7,050 cf	7,200 cf	2,700 cf	See Appendix C
	2,021 cf	3,668 cf	2,526 cf				
Minimum Length to Width Ratio	1.5 : 1			Greater than 1.5 : 1			See Project Plans
Minimum Surface Area to Drainage Area Ratio	1 : 100			1 : 8	1 : 10	1 : 10	See Project Plans
Benches at Water Level	Aquatic Bench			Aquatic Bench			See Project Plans
Landscaping	Pond and Buffer Plantings Required			Pond and Buffer Plantings Provided			See Project Plans

In accordance with the Design Manual, pretreatment basin are proposed upstream of the infiltration basins to provide pretreatment greater than 25% of the water quality volume from the contributing area. The basin has been sized to provide a storage volume greater than 25% of the WQ<sub>v</sub> below the weir in the outlet structure as shown in Appendix C. The table below provide a summary of the pretreatment requirements for the pretreatment basins.

**Table 2.3.4 – Pretreatment Basin Sizing Summary**

Subcatchment	Pretreatment Basin	WQ <sub>v</sub> <sup>1</sup> (c.f.)	Required Pretreatment Volume (25% of WQ <sub>v</sub> ) (c.f.)	Storage Volume Provided in Pretreatment Basin <sup>1</sup> (c.f.)
1.2S	1.2PT	12,720	3,180	5,625
1.3S	1.3PT	16,901	4,225	8,118
2.1S	2.1PT	18,905	4,726	12,609

<sup>1</sup> For detailed calculations see Appendix C.

By sizing the proposed stormwater management practices to treat 100% of the WQ<sub>v</sub> from the contributing area in accordance with the Design Manual, the WQ<sub>v</sub> criteria has been met.

**2.4 NYSDEC Stream Channel Protection Volume (CP<sub>v</sub>)**

The Stream Channel Protection (CP<sub>v</sub>) criterion is intended to protect stream channels from erosion and is accomplished by the 24-hour extended detention of the one-year, 24-hour storm event. As shown in Appendix C, the stormwater infiltration basins have been designed with a storage volume greater than

the volume of stormwater runoff from the 1-year storm, and therefore fully infiltrate the runoff from the 1-year, 24-hour storm event. The P-1 Micropool Extended Detention Ponds have been designed to provide 24-hour extended detention of the 1-year, 24-hour design storm. By providing a stormwater infiltration practice to fully infiltrate the volume of stormwater runoff from the 1-year, 24-hour design storm and ponds to provide 24-hour extended detention of the 1-year, 24-hour design storm, the CP<sub>v</sub> has been met for the project. Soil and infiltration testing will be performed and witnessed by the NYCDEP in the locations of the proposed stormwater management practices to verify the design criteria of including infiltration rate for the infiltration basins. Preliminary testing was performed across the project site and the stormwater management practices were designed based on the preliminary test results. Conservatively, an infiltration rate of 1 inch per hour was used in the HydroCAD modeling in Appendix C for the infiltration basins based on the observed soils.

2.5 NYSDEC Overbank Flood Control (Q<sub>p</sub>), and Extreme Flood Control (Q<sub>f</sub>)

The Overbank Flood Control (Q<sub>p</sub>) requirement is intended to prevent an increase in the frequency and magnitude of out-of-bank flooding events generated by urban development. Overbank control requires storage to attenuate the post-development 10-year, 24-hour peak discharge to pre-development rates. The Extreme Flood Control (Q<sub>f</sub>) requirement is intended to prevent the increased risk of flood damage from large storm events, maintain the boundaries of the pre-development 100-year flood plain, and protect the physical integrity of stormwater management practice. Extreme flood control requires storage to attenuate the post-development 100-year, 24-hour peak discharge to pre-development rates. As shown in Table 2.5.1, attenuation for both the 10-year and 100-year 24-hour storms has been provided thus satisfying the Q<sub>p</sub> and Q<sub>f</sub> requirements.

**Table 2.5.1– Existing and Proposed Conditions Peak Flows**

24-HOUR DESIGN STORM PEAK FLOWS (c.f.s.)				
	10-YEAR (Overbank Flood Control)		100-YEAR (Extreme Flood Control)	
	Pre	Post	Pre	Post
Design Point 1	25.95	25.92	61.35	60.55
Design Point 2	50.80	48.08	115.75	108.86

As shown in the above table the peak flows from the contributing areas to the design points in the post development condition has been mitigated to below the existing condition levels, thus meeting the general requirements of the NYSDEC.

A summary of the runoff volumes in the pre and post-development condition to each Design Point is provided in the table below for the 1-year, 10-year, and 100-year, 24-hour storm event.

**Table 2.5.2– Existing and Proposed Conditions Runoff Volumes**

24-HOUR DESIGN STORM RUNOFF VOLUME (a.f.)						
	1-YEAR		10-YEAR		100-YEAR	
	Pre	Post	Pre	Post	Pre	Post
Design Point 1	1.143	1.023	3.794	3.693	9.613	9.775
Design Point 2	3.674	3.786	11.255	11.389	27.292	27.383

2.6 NYCDEP Requirements

As previously discussed the proposed project requires a NYCDEP SWPPP approval from the NYCDEP per Section 18-39(b)(4) of the Rules and Regulations which state:

- (i) Plans for development or sale of land that will result in the disturbance of five (5) or more acres of total land area.
- (iii) Construction of a new industrial, institutional, municipal, commercial, or multi-family residential project that will result in the creation of an impervious surface totaling over 40,000 square feet in size.
- (iv) A land clearing project, involving two or more acres, located at least in part within the limiting distance of 100 feet of a watercourse or wetland, or within the limiting distance of 300 feet of a reservoir, reservoir stem or controlled lake or on a slope exceeding 15 percent.

There are no proposed stormwater discharge from industrial activities for the proposed development. The proposed project does not include any new solid waste management facilities or alterations / modifications to existing facilities.

The Rules and Regulations parallel the requirements of the NYSDEC and the Town of Carmel, with the exception that two different NYSDEC standard SMP's are required in series when the drainage area to a SMP is greater than 20% impervious and an infiltration practice is not provided. Subcatchment 1.2S, 1.3S and 2.1S do not require two different practices in series as an infiltration practice is proposed. The remaining subcatchments propose less than 20% impervious and therefore do not require two different practices in series.

Per the Rules and Regulations, the stormwater treatment volume used shall be the greater of the runoff volume from the 1-year, 24-hour storm event or the volume generated by the 90% storm. The initial  $WQ_v$  from the 1-year storm event was discussed above. The following equation, per Chapter 4, was used to determine the water quality volume for the 90% storm event for the subcatchments.

$$\text{The water quality volume shall be } WQ_v = \frac{(P)(R_v n)(A n)}{12}$$

Where,

- $WQ_{v90}$  = water quality volume (in a.f.)
- P = 90% Rainfall Event Number (1.4 in)
- $R_v$  =  $0.05 + 0.009(I)$ , where I is percent impervious cover
- A = site area in acres

**Table 2.6.1 - Water Quality Volume Calculation Summary 90% Storm vs. 1-Year Storm Comparison**

Subcatchments	P (in.)	$R_v^{3,4}$	A <sup>1</sup> (ac.)	$WQ_{v90}$ (a.f.)	$WQ_v^2$ 1-year (a.f.)
1.1S	1.4	0.22	2.6	0.067	0.232
1.2S		0.58	2.4	0.162	0.292
1.3S		0.64	2.9	0.217	0.388
2.1S		0.61	3.4	0.242	0.434
2.2S		0.62	3.0	0.217	0.421
2.3S		0.75	1.8	0.158	0.290

<sup>1</sup> Information regarding contributing areas for each subcatchment is shown in Appendix C.

<sup>2</sup> Refer to Appendix C for 1-year 24-hour water quality volume calculation.

<sup>3</sup> A minimum  $R_v$  of 0.20 is used.

<sup>4</sup> The  $R_v$  was calculated with gravel surfaces included as impervious.

As shown in Table 2.6.1 above, the volume produced by the 1-year, 24-hour design storm for all subcatchments is larger than the volume produced by the 90% storm. Therefore, the 1-year, 24-hour design storm volumes shall be used for the  $WQ_v$  sizing for all of the proposed stormwater management practices.

The following table summarizes the amount of proposed impervious surfaces for each subcatchment and shows the proposed stormwater management practice that will treat each sub-watershed:

**Table 2.6.2 – Imperviousness of Tributary Areas & Stormwater Management Practice**

Sub-Catchments	Total Area (acres)	Existing Impervious Surface Within Subcatchment	Proposed Impervious Surface Within Subcatchment <sup>2</sup>	% Impervious Surface of Total Subcatchment Area	Proposed Stormwater Management Practice (SMP) Treatment Train <sup>1</sup>	
					RR <sub>v</sub> /SMP 1	SMP 2 (A second practice in series is only provided when % impervious is greater than 20% and infiltration is not provided)
1.2S	2.4	0.0	0.3	13%	I-2, Infiltration Basin	Not Required
1.3S	2.9	0.0	0.5	17%		
2.1S	3.4	0.0	0.5	15%		
1.1S	2.6	0.0	0.0	0%	P-1 Micropool Extended Detention Pond	Not Required
2.2S	3.0	0.0	0.0	0%		
2.3S	1.8	0.0	0.0	0%		

<sup>1</sup> This table lists the standard SMP's used to treat the balance of the WQ<sub>v</sub>/ RR<sub>v</sub> after the application of GIP's.

<sup>2</sup> Per the NYCDEP regulations, the gravel surfaces are considered to be pervious for these calculations, but are accounted for per NYSDEC regulations in the WQ<sub>v</sub> and RR<sub>v</sub> calculations.

As shown in the above table, since gravel surfaces are considered to be pervious in accordance with the NYCDEP regulations, all the subcatchments include less than 20% impervious, therefore two practices in series is not required.

### 3.0 STORMWATER CONVEYANCE SYSTEM

The stormwater conveyance system for the project consists of grass swales, precast concrete drainage structures and HDPE drainage piping. In the locations of proposed stormwater conveyance system, the system has been sized utilizing the Rational Method and is a standard method used by engineers to develop flow rates for sizing collection systems. The Rational Method calculates flows based on a one-hour design storm. The collection system has been sized to convey, at a minimum, the 10-year design storm. Sizing calculations for the stormwater conveyance piping and grass swales will be provided in future reports.

### 4.0 EROSION AND SEDIMENT CONTROL

Erosion and sediment control should be accomplished by four basic principles: diversion of clean water, containment of sediment, treatment of dirty water, and stabilization of disturbed areas. Diversion of clean water should be accomplished with swales. This diverted water should be safely conveyed around the construction area as necessary and discharged downstream of the disturbed areas. Sediment should be contained with the use of silt fence at the toe of disturbed slopes. Disturbed areas should be permanently stabilized within 7 days of final grading to limit the required length of time that the temporary facilities must be utilized. The owner will be

responsible for the maintenance of the temporary erosion control facilities. Refer to the Project Drawings for further information implementation of the Erosion Control Plan and Construction Sequence.

#### 4.1 Temporary Erosion and Sediment Control Facilities

Temporary erosion and sediment control facilities should be installed and maintained as required to reduce the impacts to off-site properties. The owner will be required to provide maintenance for the temporary erosion and sediment control facilities. In general, the following temporary methods and materials should be used to control erosion and sedimentation from the project site:

- Stabilized Construction Entrance
- Dust Control
- Silt Fence Barriers
- Storm Drain Inlet Protection
- Temporary Soil Stabilization
- Temporary Sediment Trap
- Site Pollution Prevention
- Stone Check Dams
- Geotextile Anchoring

All temporary erosion control measures will be designed, installed and maintained in accordance with the November 2016 New York State Standards and Specifications for Erosion and Sediment Control as well as the Erosion & Sediment Control Maintenance Schedule contained on the Project Drawings, and as discussed below.

A stabilized construction entrance should be installed at the site entrance as shown on the project plans. The design drawings will include details to guide the contractor in the construction of this access. The intent of the stabilized construction access is to prevent the “tracking” of soil from the site.

Dust control should be accomplished with water sprinkling trucks if required. During dry periods, sprinkler trucks should wet all exposed earth surfaces as required to prevent the transport of air-borne particles to adjoining areas.

Siltation barriers constructed of geosynthetic filter cloth should be installed at the toe of all disturbed slopes. The intent of these barriers is to contain silt and sediment at the source and inhibit its transport by stormwater runoff. The siltation barriers will also help reduce the rate of runoff by creating filters through which the stormwater must pass. During construction, the siltation barriers shall be inspected weekly and after a rainfall event and shall be cleaned/replaced when needed.

Storm drain inlet protection in the form of excavated drop inlet protection will be constructed around all proposed inlets. The excavated drop inlet protection will serve to filter stormwater runoff before it enters the collection system. Throughout construction the concrete drainage structures, associated piping and inlet protections shall be inspected weekly and after a rainfall event. These items shall be cleaned, repaired and/or replaced when needed.

The P-1 Micropool Extended Detention Ponds and pretreatment basins will act as temporary sediment traps during construction of the site. The stormwater runoff from disturbed areas will be directed to the sediment traps. The sediment traps will be sized in accordance with the New York State Standards and Specifications for Erosion and Sediment Control. Sizing calculations for the temporary sediment traps will be provided in future reports.

When land is exposed during development, the exposure shall be kept to the shortest practical period, but in no case more than 7 days. Temporary grass seed and mulch shall be applied to any construction area idle for two weeks. The temporary seeding and mulching shall be performed in accordance with the seeding notes illustrated on the project drawings. Disturbance shall be minimized in the areas required to perform construction. Upon completion of final grading topsoil, permanent seeding and mulch shall be applied in accordance with the project drawings.

Site Pollution Prevention shall be performed for non-sediment pollutants during construction. Care shall be taken during construction to prevent the generation of pollutants due to the improper handling, storage, and spills and prevent the movement of toxic substances from the site into surface waters. Site pollution prevention details are discussed further in Section 5.1 below.

Stone Check Dams are proposed to be installed across the proposed grassed swales to reduce erosion by slowing down the velocity of flow in the channel. The stone check dams are also proposed to provide a form of pretreatment for the O-2 Wet Swals, and as such the check dams shall be installed during construction and shall remain as a permanent structure. The check dams shall be installed in accordance with the notes and details on the project plans. Maintenance of the check dams including removal of sediment, repairs and replacement shall be performed during and after construction.

Geotextile anchoring is proposed on all disturbed slopes steeper than 3H:1V. Erosion control blankets are proposed to aid in soil stabilization on steep slopes and promote germination. Disturbed areas should be topsoiled, raked and seeded prior to installing erosion control blankets. Blankets shall be inspected weekly and after each rainfall event until final stabilization is achieved for that area. See project plans for additional notes and details.

The stormwater runoff will be managed by the temporary erosion and sediment control facilities during construction. As discussed in the construction sequences provided the project plans the stabilized construction entrance shall be installed at the site entrance and silt fence shall be installed along the down hill perimeter of where soil disturbing activities will occur containing sediment laden stormwater runoff on-site.

#### 4.2 Permanent Erosion and Sediment Control Facilities

Permanent erosion and sediment control will be accomplished by diverting stormwater runoff from steep slopes, controlling/reducing stormwater runoff velocities and volumes, and vegetative and structural surface stabilization. All of the permanent facilities are relatively maintenance free and only require periodic inspections. The owner will provide maintenance for all the permanent erosion and sediment control facilities.

Rock outlet protection or a level spreader will be provided at the discharge end of all piped drainage systems, and will be sized in accordance with the Blue Book. The purpose of the rock outlet protection is to reduce the depth, velocity, and energy of water, such that the flow will not erode the receiving downstream reach. The rock outlet protection shall be inspected for evidence of scour beneath the riprap and/or for any dislodged stones. Inspections of the rock outlet protection and level spreader shall be performed during the inspections of the post-construction SMP's for the project.

Other than the paved or gravel surfaces, disturbed surfaces will be stabilized with vegetation within 7 days of final grading. Permanent seed mix and mulch shall be applied to idle areas to minimize the amount of exposed soil. Permanent seed mixtures are proposed for the project and illustrated on project drawings. Application rates for the seed and mulch are provided on the project drawings. The vegetation will control stormwater runoff by preventing soil erosion, reducing runoff volume and velocities, and providing a filter medium. Permanent seeding should optimally be undertaken in the spring from March 21<sup>st</sup> through May 20<sup>th</sup> and in late summer from August 15<sup>th</sup> to October 15<sup>th</sup>.

## 5.0 IMPLEMENTATION AND MAINTENANCE

### 5.1 Construction Phase

Details associated with the implementation and maintenance of the proposed stormwater facilities and erosion control measures during construction are shown on the project drawings. Soil disturbance for the subject project shall not exceed five acres at any given time. The erosion control plan will include associated details and notes to aid the contractor in implementing the plan. Construction is anticipated to begin in the summer of 2024 and anticipated to be completed by the fall of 2025.

During construction, a Site Log Book, Appendix D, is required to be kept per NYSDEC SPDES General Permit GP-0-20-001. Erosion and sediment control inspections are required to be conducted as necessary under coverage of the permit (minimum twice a week) and an updated logbook and a copy of the SWPPP is required to be kept on site for the duration of the construction activities. The Construction Site Log Book is an appendix taken from the *New York Standards and Specifications for Erosion and Sediment Control* (Blue Book).

In addition to the proposed erosion and sediment control facilities, the following good housekeeping best management practices shall be implemented to mitigate potential pollution during the construction phase of the project. The general contractor overseeing the day-to-day site operation shall be responsible for the good housekeeping best management practices included in the following general categories:

- Material Handling and Waste Management
- Establishment of Building Material Staging Areas
- Establishment of Washout Areas
- Proper Equipment Fueling and Maintenance Practices
- Spill Prevention and Control Plan

All construction waste materials shall be collected and removed from the site regularly by the general contractor. The general contractor shall supply waste barrels for proper disposal of waste materials. All personnel working on the site shall be instructed of the proper procedures for construction waste disposal.

Although it is not anticipated any hazardous waste materials will be utilized during construction, any hazardous waste materials shall be disposed of in accordance with federal, state, and local regulations. No hazardous waste shall be disposed of on-site. Hazardous waste materials shall be stored in appropriate and clearly marked containers and segregated from the other non-waste materials. All hazardous waste shall be stored in a structurally sound and sealed shipping containers located in the staging areas. Material safety data sheets, material inventory, and emergency contact numbers will be maintained in the office trailer. All personnel working on the site shall be instructed of the proper procedures for hazardous waste disposal.

Temporary sanitary facilities (portable toilets) shall be provided on site during the entire length of construction. The sanitary facilities shall be located in the project staging area, or in an alternate area away from the construction activities on the site. The portable toilets shall be inspected weekly for evidence of leaking holding tanks.

All recyclables, including wood pallets, cardboard boxes, and all other recyclable construction scraps shall be disposed of in a designated recycling barrel provided by the contractor and removed from the site regularly. All personnel working on the site shall be instructed of the proper procedures for construction waste recycling.

All construction equipment and maintenance materials shall be stored in a construction staging area. Silt fence shall be installed down gradient of the construction staging area. Shipping containers shall be utilized to store hand tools, small parts, and other construction materials, not taken off site daily. Construction waste barrels, recycling barrels and if necessary hazardous waste containers shall be located within the limits of the construction staging area.

Throughout the construction of the project, several types of vehicles and equipment will be used on-site. Fueling of the equipment shall occur within the limits of the construction staging area. Fuel will be delivered to the site as needed, by the general contractor, or a party chosen by the general contractor. Only minor vehicle equipment maintenance shall occur on-site, all major maintenance shall be performed off-site. All equipment fluids generated from minor maintenance activities shall be disposed of into designated drums and stored in accordance with the hazardous waste storage as previously discussed.

The designated temporary concrete washout areas shall be constructed in accordance with the detail in the general locations as shown on the project plans. The temporary concrete washout areas shall be lined with plastic sheeting as specified on the detail free of holes or tears. Should the liner rip or tear at any time it shall be replaced immediately. All concrete mixer trucks and chutes shall be washed in the designated concrete wash

areas. All personnel working on the site including concrete equipment operators shall be instructed of the locations and proper procedures for concrete washout. When the temporary concrete washout areas are no longer needed the hardened concrete and materials used to construct the washout area shall be broken up and removed from the site and disposed of in a landfill.

Vehicles and equipment shall be inspected on each day of use. Any leak discovered shall be repaired immediately. All leaking equipment unable to be repaired shall be removed from the site. Ample supplies of absorbent, spill-cleanup materials, and spill kits shall be located in the construction staging area. All spills shall be cleaned up immediately upon discovery. Spent absorbent materials and rags shall be hauled off-site immediately after the spill is cleaned for disposal at a local landfill. All personnel working on the site shall be instructed of the proper procedures for spill prevention and control. Petroleum spills (if applicable) and hazardous material spills must be reported to the NYSDEC Spill Hotline (1-800-457-7362). For spills not deemed reportable, it is strongly recommended that the facts concerning the incident be documented by the spiller and record maintained for one year. Any spill large enough to discharge to surface water will be immediately reported to the local fire / police departments, NYCDEP, and the National Response Center 1-800-424-8802. The contractor shall contain, recover all spills/contaminants as soon as possible to minimize any damages to the environment. Cleanup and corrective actions of releases shall be performed by a qualified contractor in accordance with all pertinent regulations.

Vegetation should be inspected every 30 days and after every major storm event until established, after which inspections should take place on a quarterly basis and after every large storm event. Damaged areas should be immediately re-seeded and re-mulched.

## 5.2 Soil Restoration

Soil Restoration is required to be applied across areas of the development site where soils have been disturbed and will be vegetated. The purpose is to recover the original properties and porosity of the soil compacted during construction activity. Soil Restoration is applied in the cleanup, restoration, and landscaping phase of construction followed by the permanent establishment of an appropriate, deep-rooted groundcover to help maintain the restored soil structure. Soil restoration includes mechanical decompaction and compost amendment. The table below describes various soil disturbance activities related to land development, soil types and the requirements for soil restoration for each activity as identified in the Design Manual. Restoration is applied across areas of a development site where soils have been compacted and will be vegetated according to the criteria defined in the table below:

<b>Soil Restoration Requirements<sup>1, 2,4</sup></b>			
(Onsite soils within the limit of disturbance belong to Hydrologic Soil Groups (HSG) B, C & D)			
<b>Type of Soil Disturbance</b>	<b>Soil Restoration Requirement</b>		<b>Comments/Examples</b>
No soil disturbance	Restoration not permitted		Preservation of Natural Features
Minimal soil disturbance	Restoration not required		Clearing and grubbing
Areas where topsoil is stripped only - no change in grade	HSG A & B	HSG C&D	Protect area from any ongoing construction activities.
	Apply 6 inches of topsoil	Aerate <sup>3</sup> and apply 6 inches of topsoil	
Areas of cut or fill	HSG A & B	HSG C&D	
	Aerate <sup>1</sup> and apply 6 inches of topsoil	Apply full Soil Restoration <sup>2</sup>	
Heavy traffic areas on site (especially in a zone 5-25 feet around buildings but not within a 5-foot perimeter around foundation walls)	Apply full Soil Restoration (decompaction and compost Enhancement <sup>6</sup> )		
Areas where Runoff Reduction and/or Infiltration practices are applied	Restoration not required, but may be applied to enhance the reduction specified for appropriate practices.		Keep construction equipment from crossing these areas. To protect newly installed practice from any ongoing construction activities construct a single phase operation fence area
Redevelopment projects	Soil Restoration is required on redevelopment projects in areas where existing impervious area will be converted to pervious area.		

1. Aeration includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the soil, a roller with many spikes making indentations in the soil, or prongs which function like a mini-subsoiler.
2. Per "Deep Ripping and De-compaction, DEC 2008".
3. Aeration includes the use of machines such as tractor-drawn implements with coulters making a narrow slit in the soil, a roller with many spikes making indentations in the soil, or prongs which functions like a mini-subsoiler.
4. During periods of relatively low to moderate subsoil moisture, the disturbed soils are returned to rough grade and the following Soil Restoration steps applied:
  - 5.1. Apply 3 inches of compost over subsoil.
  - 5.2. Till compost into subsoil to a depth of at least 12 inches using a cat-mounted ripper, tractor-mounted disc, or tiller, mixing, and circulating air and compost into subsoils.
  - 5.3. Rock-pick until uplifted stone/rock materials of four inches and larger size area cleaned off the site.
  - 5.4. Apply topsoil to a depth of 6 inches.
  - 5.5. Vegetate as required by seeding notes located on the project drawings.
  - 5.6. Tilling should not be performed within the drip line of any existing trees or over any utility installations that are within 24 inches of the surface.
6. Compost shall be aged, from plant derived materials, free of viable weed seeds, have no visible free water or dust produced when handling, pass through a half inch screen and have a pH suitable to grow desired plants.

After soil restoration is completed an inspector should be able to push a 3/8" metal bar twelve inches into the soil with just body weight. Following decompaction/soil restoration activities, the following maintenance is anticipated during the first year:

- Initial inspections for the first six months (once after each storm greater than a half-inch).
- Reseeding to repair bare or eroding areas to assure grass stabilization.

- Water once every three days for first month, and then provide a half inch of water per week during first year. Irrigation plan may be adjusted according to the rain event.
- Fertilization may be needed in the fall after the first growing season to increase plant vigor.

In order to ensure the soil remains decompacted the following ongoing maintenance is recommended:

- Planting the appropriate ground cover with deep roots to maintain the soil structure.
- Keeping the site free of vehicular and foot traffic or other weight loads. Consider pedestrian footpaths (sometimes it may be necessary to de-thatch the turf every few years).

### 5.3 Long Term Maintenance Plan

The stormwater facilities for the subject project have been designed to minimize the required maintenance. This section discusses the minimum maintenance requirements to insure long-term performance of the stormwater facilities. Initially the stormwater facilities will require an increased maintenance and inspection schedule until all portions of the site are stable. Generally the stormwater facilities consist of either collection and conveyance components or treatment components.

The stormwater collection and conveyance system is composed of grass swales, HDPE drainage pipe and precast concrete drainage structures. The owner will assume the maintenance responsibilities for the drainage system. Minimal maintenance is typically required for these facilities. All pipes should be checked for debris and blockages and cleaned as required. All drain inlet sumps shall be cleaned to removed deposited sediment. During the cleaning process, the pipes should be inspected for structural integrity and overall condition; repairs and/or replacement should be made as required.

Additionally, the stormwater management practices including the infiltration basins, pretreatment basins, and stormwater ponds shall be checked for deposited sediment as well. Inspection and maintenance requirements for the proposed stormwater management practices per the Design Manual are provided in Appendix F of this report.

**APPENDIX A**  
**RR<sub>v</sub> Calculations**



# RRv Calculation Worksheet - Design Point 1

Project: Union Energy Center  
 Project #: 21120.100  
 Date: 2/16/2024



1. *RRv Initial = Water Quality Volume (WQv)* 0.912 ac-ft = 39,727 c.f.  
 (refer to HydroCAD Subcatchments 1.1S, 1.2S and 1.3S for Water Quality Volume)

2. *RRv Minimum* =  $[(P)(Rv)(S)(Aic)]/12$  where...  
 P = Rainfall (in.) = 2.76 in.  
 Rv = 0.05 + 0.009 (100%) = 0.95  
 S = Hydrologic Soil Group Specific Reduction Factor = 0.30  
     [HSG A = 0.55] [HSG B = 0.40] [HSG C = 0.30] [HSG D = 0.20]  
 Aic = Total area of new impervious cover = 3.8 Acres  
  
*RRv Minimum* = 10,850 c.f.

3. *RRv Required = RRv Initial - Green Infrastructure Practice (GIP) with Area Reduction*

GIP with Area Reduction Applied in Project

5.3.1 Conservation of Natural Area N/A  
 5.3.2 Sheet Flow to Riparian Buffers or Filter Strips N/A  
 5.3.4 Tree Planting / Tree Box c.f.  
 5.3.5 Disconnection of Rooftop Runoff -  
 5.3.6 Stream Daylighting N/A

*RRv Required (=WQv-RRV by area)(Refer to HydroCAD output in this Appendix)* = 39,727 c.f.

4. *RRv Provided*

GIP with Volume Reduction Applied in Project	WQv Treated (c.f.)	% of WQv Applied to RRv Provided	RRv Provided (c.f.)
5.3.3 Vegetated Open Swales [HSG A / B = 20%] [HSG C / D = 10%] {Modified HSG C - D = 15% - 12%}		20%	0
		10%	0
5.3.7 Rain Garden [No underdrains / Good Soils = 100%] [With underdrains / Poor Soils = 40%]		40%	0
5.3.8 Green Roof [RRv provided equals volume provided in Green Roof]		100%	0
5.3.9 Stormwater Planters [Infiltration Planters = 100%] [Flow Through HSG C = 45%] [Flow Through HSG D = 30%]		45%	0
5.3.10 Rain Tank / Cisterns		100%	0
5.3.11 Porous Pavement		100%	0
Infiltration Practice (Standard SMP)	29621	100%	29,621
Bioretention Practice (Standard SMP) [Without Underdrains HSG A/B = 80%] [With Underdrain HSG C/D = 40%]		40%	0
Dry Swale (Open Channel Practice) (Standard SMP) [HSG A/B = 40%] [HSG C/D = 20%]		20%	0
<b>RRv Provided =</b>			<b>29,621</b>

5. Summary

RRv Initial = 39,727 c.f.  
 RRv Required = 39,727 c.f.  
 RRv Minimum = 10,850 c.f.  
 RRv Provided = 29,621 c.f.  
 WQv Required for Downstream SMP = 10,106 c.f. (= RRv Required - RRv Provided)  
 Is RRv Provided greater than or equal to RRv Minimum? Yes

## RRv Calculation Worksheet - Design Point 2

Project: Union Energy Center  
 Project #: 21120.100  
 Date: 2/16/2024



1. *RRv Initial = Water Quality Volume (WQv)* 1.145 ac-ft = 49,876 c.f.  
 (refer to HydroCAD Subcatchments 2.1S, 2.2S, 2.3S and 2.4S for Water Quality Volume)

2. *RRv Minimum* =  $[(P)(Rv)(S)(Aic)]/12$  where...  
 P = Rainfall (in.) = 2.76 in.  
 Rv =  $0.05 + 0.009(100\%)$  = 0.95  
 S = Hydrologic Soil Group Specific Reduction Factor = 0.24  
     [HSG A = 0.55] [HSG B = 0.40] [HSG C = 0.30] [HSG D = 0.20]  
 Aic = Total area of new impervious cover = 5.4 Acres  
  
*RRv Minimum* = 12,335 c.f.

3. *RRv Required = RRv Initial - Green Infrastructure Practice (GIP) with Area Reduction*

GIP with Area Reduction Applied in Project

5.3.1 Conservation of Natural Area N/A  
 5.3.2 Sheet Flow to Riparian Buffers or Filter Strips N/A  
 5.3.4 Tree Planting / Tree Box c.f.  
 5.3.5 Disconnection of Rooftop Runoff -  
 5.3.6 Stream Daylighting N/A

*RRv Required (=WQv-RRV by area)(Refer to HydroCAD output in this Appendix)* = 49,876 c.f.

4. *RRv Provided*



GIP with Volume Reduction Applied in Project	WQv Treated (c.f.)	% of WQv Applied to RRv Provided	RRv Provided (c.f.)
5.3.3 Vegetated Open Swales [HSG A / B = 20%] [HSG C / D = 10%] {Modified HSG C - D = 15% - 12%}		20%	0
		10%	0
5.3.7 Rain Garden [No underdrains / Good Soils = 100%] [With underdrains / Poor Soils = 40%]		40%	0
5.3.8 Green Roof [RRv provided equals volume provided in Green Roof]		100%	0
5.3.9 Stormwater Planters [Infiltration Planters = 100%] [Flow Through HSG C = 45%] [Flow Through HSG D = 30%]		45%	0
5.3.10 Rain Tank / Cisterns		100%	0
5.3.11 Porous Pavement		100%	0
Infiltration Practice (Standard SMP)	18905	100%	18,905
Bioretention Practice (Standard SMP) [Without Underdrains HSG A/B = 80%] [With Underdrain HSG C/D = 40%]		40%	0
Dry Swale (Open Channel Practice) (Standard SMP) [HSG A/B = 40%] [HSG C/D = 20%]		20%	0
<i>RRv Provided =</i>			18,905

5. Summary

RRv Initial = 49,876 c.f.  
 RRv Required = 49,876 c.f.  
 RRv Minimum = 12,335 c.f.  
 RRv Provided = 18,905 c.f.  
 WQv Required for Downstream SMP = 30,971 c.f. (= RRv Required - RRv Provided)  
 Is RRv Provided greater than or equal to RRv Minimum? Yes

**APPENDIX B**  
**Pre-Development Computer Data**





**Routing Diagram for East Point Energy - Pre Development**

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C., Printed 2/14/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC



**Summary for Subcatchment PRE 1:**

Runoff = 7.51 cfs @ 12.43 hrs, Volume= 1.143 af, Depth= 0.67"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"


Area (ac)	CN	Description
6.200	77	Woods, Good, HSG D
14.300	70	Woods, Good, HSG C
20.500	72	Weighted Average
20.500		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
4.5	425	0.1000	1.58		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
5.1	1,113	0.0270	3.63	9.80	<b>Channel Flow,</b> Area= 2.7 sf Perim= 7.2' r= 0.38' n= 0.035 Earth, dense weeds
30.6	1,638	Total			

**Subcatchment PRE 1:**

Hydrograph



**Summary for Subcatchment PRE 2:**

Runoff = 16.38 cfs @ 12.96 hrs, Volume= 3.674 af, Depth= 0.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
37.600	77	Woods, Good, HSG D
17.000	70	Woods, Good, HSG C
54.600	75	Weighted Average
54.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.7	100	0.0100	0.06		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
40.1	2,463	0.0420	1.02		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
67.8	2,563	Total			

**Subcatchment PRE 2:**

Hydrograph



**East Point Energy - Pre Development**

NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/14/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 4

**Summary for Subcatchment PRE 1:**

Runoff = 25.95 cfs @ 12.39 hrs, Volume= 3.794 af, Depth= 2.22"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"


Area (ac)	CN	Description
6.200	77	Woods, Good, HSG D
14.300	70	Woods, Good, HSG C
20.500	72	Weighted Average
20.500		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
4.5	425	0.1000	1.58		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
5.1	1,113	0.0270	3.63	9.80	<b>Channel Flow,</b> Area= 2.7 sf Perim= 7.2' r= 0.38' n= 0.035 Earth, dense weeds
30.6	1,638	Total			

**Subcatchment PRE 1:**

Hydrograph



# East Point Energy - Pre Development

NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/14/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 5

## Summary for Subcatchment PRE 2:

Runoff = 50.80 cfs @ 12.90 hrs, Volume= 11.255 af, Depth= 2.47"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Area (ac)	CN	Description
37.600	77	Woods, Good, HSG D
17.000	70	Woods, Good, HSG C
54.600	75	Weighted Average
54.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.7	100	0.0100	0.06		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
40.1	2,463	0.0420	1.02		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
67.8	2,563	Total			

## Subcatchment PRE 2:

Hydrograph



**Summary for Subcatchment PRE 1:**

Runoff = 61.35 cfs @ 12.37 hrs, Volume= 9.613 af, Depth= 5.63"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"


Area (ac)	CN	Description
6.200	77	Woods, Good, HSG D
14.300	70	Woods, Good, HSG C
20.500	72	Weighted Average
20.500		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
4.5	425	0.1000	1.58		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
5.1	1,113	0.0270	3.63	9.80	<b>Channel Flow,</b> Area= 2.7 sf Perim= 7.2' r= 0.38' n= 0.035 Earth, dense weeds
30.6	1,638	Total			

**Subcatchment PRE 1:**

Hydrograph



**Summary for Subcatchment PRE 2:**

Runoff = 115.75 cfs @ 12.88 hrs, Volume= 27.292 af, Depth= 6.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"


Area (ac)	CN	Description
37.600	77	Woods, Good, HSG D
17.000	70	Woods, Good, HSG C
54.600	75	Weighted Average
54.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.7	100	0.0100	0.06		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
40.1	2,463	0.0420	1.02		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
67.8	2,563	Total			




**Subcatchment PRE 2:**

Hydrograph



**APPENDIX C**  
**Post-Development Computer Data**







# East Point Energy - Post Development

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 2

## Summary for Subcatchment 1.0S:

Runoff = 5.33 cfs @ 12.42 hrs, Volume= 0.791 af, Depth= 0.71"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"


Area (ac)	CN	Description
5.400	77	Woods, Good, HSG D
7.900	70	Woods, Good, HSG C
13.300	73	Weighted Average
13.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
4.5	425	0.1000	1.58		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
5.1	1,113	0.0270	3.63	9.80	<b>Channel Flow,</b> Area= 2.7 sf Perim= 7.2' r= 0.38' n= 0.035 Earth, dense weeds
30.6	1,638	Total			

## Subcatchment 1.0S:

Hydrograph



# East Point Energy - Post Development

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 3

## Summary for Subcatchment 1.1S:

Runoff = 3.52 cfs @ 12.05 hrs, Volume= 0.232 af, Depth= 1.07"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
0.500	96	Gravel surface, HSG D
0.900	78	Meadow, non-grazed, HSG D
0.300	71	Meadow, non-grazed, HSG C
0.600	77	Woods, Good, HSG D
0.300	70	Woods, Good, HSG C
2.600	80	Weighted Average
2.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.2000	0.30		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
0.8	152	0.2300	3.36		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
6.4	252	Total			

## Subcatchment 1.1S:

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 4

**Summary for Subcatchment 1.2S:**

Runoff = 3.56 cfs @ 12.12 hrs, Volume= 0.292 af, Depth= 1.46"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
1.100	96	Gravel surface, HSG C
0.300	98	Paved parking, HSG C
1.000	71	Meadow, non-grazed, HSG C
2.400	86	Weighted Average
2.100		87.50% Pervious Area
0.300		12.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.5	70	0.0200	0.11		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
0.5	30	0.0200	1.10		<b>Sheet Flow,</b> Smooth surfaces n= 0.011 P2= 3.34"
0.3	50	0.0200	2.87		<b>Shallow Concentrated Flow,</b> Paved Kv= 20.3 fps
0.8	206	0.0200	4.28	5.35	<b>Trap/Vee/Rect Channel Flow,</b> Bot.W=1.00' D=0.50' Z= 3.0 '/' Top.W=4.00' n= 0.022 Earth, clean & straight
12.1	356	Total			

Subcatchment 1.2S:

Hydrograph



**Summary for Subcatchment 1.3S:**

Runoff = 6.17 cfs @ 12.04 hrs, Volume= 0.388 af, Depth= 1.61"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
1.400	96	Gravel surface, HSG C
0.500	98	Paved parking, HSG C
1.000	71	Meadow, non-grazed, HSG C
2.900	88	Weighted Average
2.400		82.76% Pervious Area
0.500		17.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.3S:**

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 7

**Summary for Subcatchment 2.0S:**

Runoff = 13.71 cfs @ 12.96 hrs, Volume= 3.075 af, Depth= 0.81"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
31.900	77	Woods, Good, HSG D
13.800	70	Woods, Good, HSG C
45.700	75	Weighted Average
45.700		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.7	100	0.0100	0.06		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
40.1	2,463	0.0420	1.02		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
67.8	2,563	Total			

**Subcatchment 2.0S:**

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 8

**Summary for Subcatchment 2.1S:**

Runoff = 6.90 cfs @ 12.04 hrs, Volume= 0.434 af, Depth= 1.53"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
1.600	96	Gravel surface, HSG C
0.500	98	Paved parking, HSG C
1.300	71	Meadow, non-grazed, HSG C
3.400	87	Weighted Average
2.900		85.29% Pervious Area
0.500		14.71% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 2.1S:**

Hydrograph



# East Point Energy - Post Development

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 9

## Summary for Subcatchment 2.2S:

Runoff = 4.41 cfs @ 12.18 hrs, Volume= 0.421 af, Depth= 1.68"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"


Area (ac)	CN	Description
1.900	96	Gravel surface, HSG D
0.800	78	Meadow, non-grazed, HSG D
0.300	71	Meadow, non-grazed, HSG C
3.000	89	Weighted Average
3.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.0	100	0.0200	0.12		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
1.0	230	0.0200	3.79	1.90	<b>Trap/Vee/Rect Channel Flow,</b> Bot.W=1.00' D=0.50' n= 0.022 Earth, clean & straight
1.8	485	0.0100	4.54	3.56	<b>Pipe Channel,</b> 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
16.8	815	Total			

## Subcatchment 2.2S:

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 10

**Summary for Subcatchment 2.3S:**

Runoff = 4.56 cfs @ 12.04 hrs, Volume= 0.290 af, Depth= 1.94"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Area (ac)	CN	Description
1.400	96	Gravel surface, HSG D
0.400	78	Meadow, non-grazed, HSG D
1.800	92	Weighted Average
1.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 2.3S:**

Hydrograph




### Summary for Reach DP 1:

Inflow Area = 21.200 ac, 3.77% Impervious, Inflow Depth = 0.58" for 1-yr event  
Inflow = 5.42 cfs @ 12.42 hrs, Volume= 1.023 af  
Outflow = 5.42 cfs @ 12.42 hrs, Volume= 1.023 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs

### Reach DP 1:

Hydrograph




**Summary for Reach DP 2:**

Inflow Area = 53.900 ac, 0.93% Impervious, Inflow Depth = 0.84" for 1-yr event  
Inflow = 13.93 cfs @ 12.96 hrs, Volume= 3.786 af  
Outflow = 13.93 cfs @ 12.96 hrs, Volume= 3.786 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs

**Reach DP 2:**

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 13

**Summary for Pond 1.1P: P-1 Pond**

Inflow Area = 2.600 ac, 0.00% Impervious, Inflow Depth = 1.07" for 1-yr event  
 Inflow = 3.52 cfs @ 12.05 hrs, Volume= 0.232 af  
 Outflow = 0.16 cfs @ 15.15 hrs, Volume= 0.232 af, Atten= 96%, Lag= 186.0 min  
 Primary = 0.16 cfs @ 15.15 hrs, Volume= 0.232 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 625.00' Surf.Area= 6,400 sf Storage= 7,050 cf  
 Peak Elev= 626.11' @ 15.15 hrs Surf.Area= 10,634 sf Storage= 12,639 cf (5,589 cf above start)

Plug-Flow detention time= 1,480.8 min calculated for 0.070 af (30% of inflow)  
 Center-of-Mass det. time= 620.8 min ( 1,490.1 - 869.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	620.00'	3,500 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	620.00'	41,950 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		45,450 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
620.00	100	0	0
622.00	300	400	400
624.00	700	1,000	1,400
625.00	3,500	2,100	3,500

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
620.00	100	0	0
622.00	400	500	500
624.00	800	1,200	1,700
625.00	2,900	1,850	3,550
627.00	10,500	13,400	16,950
629.00	14,500	25,000	41,950


Device	Routing	Invert	Outlet Devices
#1	Primary	625.00'	<b>2.0" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	626.00'	<b>9.0" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=0.16 cfs @ 15.15 hrs HW=626.11' TW=0.00' (Dynamic Tailwater)

- ↑ **1=Orifice/Grate** (Orifice Controls 0.11 cfs @ 4.89 fps)
- ↳ **2=Orifice/Grate** (Orifice Controls 0.05 cfs @ 1.15 fps)

Pond 1.1P: P-1 Pond

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 15

**Summary for Pond 1.2P: Infiltration Basin**

Inflow Area = 2.400 ac, 12.50% Impervious, Inflow Depth = 1.46" for 1-yr event  
 Inflow = 0.45 cfs @ 12.76 hrs, Volume= 0.292 af  
 Outflow = 0.11 cfs @ 21.75 hrs, Volume= 0.292 af, Atten= 77%, Lag= 539.8 min  
 Discarded = 0.11 cfs @ 21.75 hrs, Volume= 0.292 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 667.58' @ 21.75 hrs Surf.Area= 4,580 sf Storage= 5,989 cf

Plug-Flow detention time= 635.8 min calculated for 0.291 af (100% of inflow)  
 Center-of-Mass det. time= 635.5 min ( 1,755.4 - 1,119.9 )

Volume	Invert	Avail.Storage	Storage Description
#1	666.00'	20,500 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
666.00	3,000	0	0
668.00	5,000	8,000	8,000
670.00	7,500	12,500	20,500


Device	Routing	Invert	Outlet Devices
#1	Discarded	666.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	669.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.11 cfs @ 21.75 hrs HW=667.58' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.11 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=666.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.2P: Infiltration Basin

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying &amp; Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 17

**Summary for Pond 1.2PT: Pretreatment Basin**

Inflow Area = 2.400 ac, 12.50% Impervious, Inflow Depth = 1.46" for 1-yr event  
 Inflow = 3.56 cfs @ 12.12 hrs, Volume= 0.292 af  
 Outflow = 0.45 cfs @ 12.76 hrs, Volume= 0.292 af, Atten= 87%, Lag= 38.1 min  
 Primary = 0.45 cfs @ 12.76 hrs, Volume= 0.292 af  
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 668.44' @ 12.92 hrs Surf.Area= 4,438 sf Storage= 5,348 cf

Plug-Flow detention time= 271.0 min calculated for 0.292 af (100% of inflow)  
 Center-of-Mass det. time= 270.4 min ( 1,119.9 - 849.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	667.00'	20,250 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
667.00	3,000	0	0
668.00	4,000	3,500	3,500
670.00	6,000	10,000	13,500
671.00	7,500	6,750	20,250


Device	Routing	Invert	Outlet Devices
#1	Primary	667.00'	<b>4.0" Round Culvert</b> L= 30.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 667.00' / 666.00' S= 0.0333 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	668.50'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.45 cfs @ 12.76 hrs HW=668.43' TW=666.34' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.45 cfs @ 5.20 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=667.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.2PT: Pretreatment Basin

Hydrograph



**Summary for Pond 1.3P: Infiltration Basin**

Inflow Area = 2.900 ac, 17.24% Impervious, Inflow Depth = 1.61" for 1-yr event  
 Inflow = 0.51 cfs @ 12.95 hrs, Volume= 0.388 af  
 Outflow = 0.17 cfs @ 22.94 hrs, Volume= 0.388 af, Atten= 67%, Lag= 599.4 min  
 Discarded = 0.17 cfs @ 22.94 hrs, Volume= 0.388 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 663.44' @ 22.94 hrs Surf.Area= 7,155 sf Storage= 8,731 cf

Plug-Flow detention time= 551.3 min calculated for 0.388 af (100% of inflow)  
 Center-of-Mass det. time= 551.0 min ( 1,584.4 - 1,033.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	662.00'	32,500 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
662.00	5,000	0	0
664.00	8,000	13,000	13,000
666.00	11,500	19,500	32,500


Device	Routing	Invert	Outlet Devices
#1	Discarded	662.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	664.50'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.17 cfs @ 22.94 hrs HW=663.44' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.17 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=662.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.3P: Infiltration Basin

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 21

**Summary for Pond 1.3PT: Pretreatment Basin**

Inflow Area = 2.900 ac, 17.24% Impervious, Inflow Depth = 1.61" for 1-yr event  
 Inflow = 6.17 cfs @ 12.04 hrs, Volume= 0.388 af  
 Outflow = 0.51 cfs @ 12.95 hrs, Volume= 0.388 af, Atten= 92%, Lag= 54.6 min  
 Primary = 0.51 cfs @ 12.95 hrs, Volume= 0.388 af  
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 665.62' @ 12.95 hrs Surf.Area= 5,933 sf Storage= 7,649 cf

Plug-Flow detention time= 199.4 min calculated for 0.388 af (100% of inflow)  
 Center-of-Mass det. time= 198.9 min ( 1,033.4 - 834.5 )

Volume	Invert	Avail.Storage	Storage Description
#1	664.00'	26,000 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
664.00	3,500	0	0
666.00	6,500	10,000	10,000
668.00	9,500	16,000	26,000


Device	Routing	Invert	Outlet Devices
#1	Primary	664.00'	<b>4.0" Round Culvert</b> L= 40.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 664.00' / 662.00' S= 0.0500 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	665.70'	<b>2.5' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.51 cfs @ 12.95 hrs HW=665.62' TW=662.28' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.51 cfs @ 5.81 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=664.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.3PT: Pretreatment Basin

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 23

**Summary for Pond 2.1P: Infiltration Basin**

Inflow Area = 3.400 ac, 14.71% Impervious, Inflow Depth > 1.52" for 1-yr event  
 Inflow = 0.33 cfs @ 14.14 hrs, Volume= 0.431 af  
 Outflow = 0.20 cfs @ 25.98 hrs, Volume= 0.431 af, Atten= 38%, Lag= 710.4 min  
 Discarded = 0.20 cfs @ 25.98 hrs, Volume= 0.431 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 665.70' @ 25.98 hrs Surf.Area= 8,781 sf Storage= 5,138 cf

Plug-Flow detention time= 278.1 min calculated for 0.431 af (100% of inflow)  
 Center-of-Mass det. time= 277.9 min ( 1,602.0 - 1,324.1 )

Volume	Invert	Avail.Storage	Storage Description
#1	665.00'	34,000 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
665.00	6,000	0	0
666.00	10,000	8,000	8,000
668.00	16,000	26,000	34,000


Device	Routing	Invert	Outlet Devices
#1	Discarded	665.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	667.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.20 cfs @ 25.98 hrs HW=665.70' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.20 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=665.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 2.1P: Infiltration Basin

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying &amp; Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 25

**Summary for Pond 2.1PT: Pretreatment Basin**

Inflow Area = 3.400 ac, 14.71% Impervious, Inflow Depth = 1.53" for 1-yr event  
 Inflow = 6.90 cfs @ 12.04 hrs, Volume= 0.434 af  
 Outflow = 0.33 cfs @ 14.14 hrs, Volume= 0.431 af, Atten= 95%, Lag= 125.9 min  
 Primary = 0.33 cfs @ 14.14 hrs, Volume= 0.431 af  
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 666.91' @ 14.14 hrs Surf.Area= 12,100 sf Storage= 10,333 cf

Plug-Flow detention time= 488.9 min calculated for 0.431 af (99% of inflow)  
 Center-of-Mass det. time= 484.9 min ( 1,324.1 - 839.2 )

Volume	Invert	Avail.Storage	Storage Description
#1	666.00'	39,250 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
666.00	10,500	0	0
668.00	14,000	24,500	24,500
669.00	15,500	14,750	39,250


Device	Routing	Invert	Outlet Devices
#1	Primary	666.00'	<b>4.0" Round Culvert</b> L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 666.00' / 665.00' S= 0.0200 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	667.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.33 cfs @ 14.14 hrs HW=666.91' TW=665.21' (Dynamic Tailwater)  
 ↑1=Culvert (Barrel Controls 0.33 cfs @ 3.74 fps)

**Secondary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=666.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 2.1PT: Pretreatment Basin

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 27

**Summary for Pond 2.2P: P-1 Pond**

Inflow Area = 3.000 ac, 0.00% Impervious, Inflow Depth = 1.68" for 1-yr event  
 Inflow = 4.41 cfs @ 12.18 hrs, Volume= 0.421 af  
 Outflow = 0.23 cfs @ 15.32 hrs, Volume= 0.421 af, Atten= 95%, Lag= 188.0 min  
 Primary = 0.23 cfs @ 15.32 hrs, Volume= 0.421 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 653.00' Surf.Area= 2,800 sf Storage= 7,200 cf  
 Peak Elev= 654.90' @ 15.32 hrs Surf.Area= 9,353 sf Storage= 18,523 cf (11,323 cf above start)

Plug-Flow detention time= 1,446.2 min calculated for 0.256 af (61% of inflow)  
 Center-of-Mass det. time= 865.1 min ( 1,704.7 - 839.6 )

Volume	Invert	Avail.Storage	Storage Description
#1	649.00'	2,300 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	649.00'	49,300 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		51,600 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
649.00	300	0	0
651.00	500	800	800
653.00	1,000	1,500	2,300

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
649.00	700	0	0
651.00	1,200	1,900	1,900
653.00	1,800	3,000	4,900
654.00	7,000	4,400	9,300
656.00	10,000	17,000	26,300
658.00	13,000	23,000	49,300


Device	Routing	Invert	Outlet Devices
#1	Primary	653.00'	<b>2.0" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	654.80'	<b>1.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.23 cfs @ 15.32 hrs HW=654.90' TW=0.00' (Dynamic Tailwater)

- 1=Orifice/Grate (Orifice Controls 0.14 cfs @ 6.49 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 0.09 cfs @ 0.89 fps)

### Pond 2.2P: P-1 Pond

Hydrograph



**East Point Energy - Post Development**

NY-East Point Energy 24-hr S1 1-yr Rainfall=2.76"

Prepared by Insite Engineering, Surveying & Landscape Architecture, P.C.

Printed 2/16/2024

HydroCAD® 10.00-15 s/n 02171 © 2015 HydroCAD Software Solutions LLC

Page 29

**Summary for Pond 2.3P: P-1 Pond**

Inflow Area = 1.800 ac, 0.00% Impervious, Inflow Depth = 1.94" for 1-yr event  
 Inflow = 4.56 cfs @ 12.04 hrs, Volume= 0.290 af  
 Outflow = 0.12 cfs @ 16.48 hrs, Volume= 0.290 af, Atten= 97%, Lag= 266.4 min  
 Primary = 0.12 cfs @ 16.48 hrs, Volume= 0.290 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 646.00' Surf.Area= 1,300 sf Storage= 2,700 cf  
 Peak Elev= 648.22' @ 16.48 hrs Surf.Area= 6,407 sf Storage= 11,117 cf (8,417 cf above start)

Plug-Flow detention time= 1,452.5 min calculated for 0.228 af (79% of inflow)  
 Center-of-Mass det. time= 1,077.6 min ( 1,890.6 - 813.0 )

Volume	Invert	Avail.Storage	Storage Description
#1	642.00'	1,400 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	642.00'	22,100 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		23,500 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
642.00	100	0	0
644.00	300	400	400
646.00	700	1,000	1,400

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
642.00	100	0	0
644.00	300	400	400
646.00	600	900	1,300
647.00	4,200	2,400	3,700
648.00	5,400	4,800	8,500
650.00	8,200	13,600	22,100


Device	Routing	Invert	Outlet Devices
#1	Primary	646.00'	<b>1.5" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	648.20'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.12 cfs @ 16.48 hrs HW=648.22' TW=0.00' (Dynamic Tailwater)

- 1=Orifice/Grate (Orifice Controls 0.09 cfs @ 7.07 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 0.03 cfs @ 0.39 fps)

### Pond 2.3P: P-1 Pond

Hydrograph



**Summary for Subcatchment 1.0S:**

Runoff = 17.54 cfs @ 12.39 hrs, Volume= 2.554 af, Depth= 2.30"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"


Area (ac)	CN	Description
5.400	77	Woods, Good, HSG D
7.900	70	Woods, Good, HSG C
13.300	73	Weighted Average
13.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
4.5	425	0.1000	1.58		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
5.1	1,113	0.0270	3.63	9.80	<b>Channel Flow,</b> Area= 2.7 sf Perim= 7.2' r= 0.38' n= 0.035 Earth, dense weeds
30.6	1,638	Total			

**Subcatchment 1.0S:**

Hydrograph



**Summary for Subcatchment 1.1S:**

Runoff = 8.48 cfs @ 12.05 hrs, Volume= 0.632 af, Depth= 2.92"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Area (ac)	CN	Description
0.500	96	Gravel surface, HSG D
0.900	78	Meadow, non-grazed, HSG D
0.300	71	Meadow, non-grazed, HSG C
0.600	77	Woods, Good, HSG D
0.300	70	Woods, Good, HSG C
2.600	80	Weighted Average
2.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.2000	0.30		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
0.8	152	0.2300	3.36		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
6.4	252	Total			

**Subcatchment 1.1S:**

Hydrograph



**Summary for Subcatchment 1.2S:**

Runoff = 7.40 cfs @ 12.12 hrs, Volume= 0.699 af, Depth= 3.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"


Area (ac)	CN	Description
1.100	96	Gravel surface, HSG C
0.300	98	Paved parking, HSG C
1.000	71	Meadow, non-grazed, HSG C
2.400	86	Weighted Average
2.100		87.50% Pervious Area
0.300		12.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.5	70	0.0200	0.11		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
0.5	30	0.0200	1.10		<b>Sheet Flow,</b> Smooth surfaces n= 0.011 P2= 3.34"
0.3	50	0.0200	2.87		<b>Shallow Concentrated Flow,</b> Paved Kv= 20.3 fps
0.8	206	0.0200	4.28	5.35	<b>Trap/Vee/Rect Channel Flow,</b> Bot.W=1.00' D=0.50' Z= 3.0 '/' Top.W=4.00' n= 0.022 Earth, clean & straight
12.1	356	Total			

### Subcatchment 1.2S:

Hydrograph



**Summary for Subcatchment 1.3S:**

Runoff = 11.92 cfs @ 12.04 hrs, Volume= 0.894 af, Depth= 3.70"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Area (ac)	CN	Description
1.400	96	Gravel surface, HSG C
0.500	98	Paved parking, HSG C
1.000	71	Meadow, non-grazed, HSG C
2.900	88	Weighted Average
2.400		82.76% Pervious Area
0.500		17.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.3S:**

Hydrograph



**Summary for Subcatchment 2.0S:**

Runoff = 42.52 cfs @ 12.90 hrs, Volume= 9.420 af, Depth= 2.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"


Area (ac)	CN	Description
31.900	77	Woods, Good, HSG D
13.800	70	Woods, Good, HSG C
45.700	75	Weighted Average
45.700		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.7	100	0.0100	0.06		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
40.1	2,463	0.0420	1.02		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
67.8	2,563	Total			

**Subcatchment 2.0S:**

Hydrograph



**Summary for Subcatchment 2.1S:**

Runoff = 13.65 cfs @ 12.04 hrs, Volume= 1.019 af, Depth= 3.60"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Area (ac)	CN	Description
1.600	96	Gravel surface, HSG C
0.500	98	Paved parking, HSG C
1.300	71	Meadow, non-grazed, HSG C
3.400	87	Weighted Average
2.900		85.29% Pervious Area
0.500		14.71% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 2.1S:**

Hydrograph



**Summary for Subcatchment 2.2S:**

Runoff = 8.59 cfs @ 12.18 hrs, Volume= 0.950 af, Depth= 3.80"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"


Area (ac)	CN	Description
1.900	96	Gravel surface, HSG D
0.800	78	Meadow, non-grazed, HSG D
0.300	71	Meadow, non-grazed, HSG C
3.000	89	Weighted Average
3.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.0	100	0.0200	0.12		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
1.0	230	0.0200	3.79	1.90	<b>Trap/Vee/Rect Channel Flow,</b> Bot.W=1.00' D=0.50' n= 0.022 Earth, clean & straight
1.8	485	0.0100	4.54	3.56	<b>Pipe Channel,</b> 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
16.8	815	Total			

**Subcatchment 2.2S:**

Hydrograph



**Summary for Subcatchment 2.3S:**

Runoff = 8.02 cfs @ 12.04 hrs, Volume= 0.618 af, Depth= 4.12"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 10-yr Rainfall=5.03"

Area (ac)	CN	Description
1.400	96	Gravel surface, HSG D
0.400	78	Meadow, non-grazed, HSG D
1.800	92	Weighted Average
1.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 2.3S:**

Hydrograph




### Summary for Reach DP 1:

Inflow Area = 21.200 ac, 3.77% Impervious, Inflow Depth = 2.09" for 10-yr event  
Inflow = 25.92 cfs @ 12.36 hrs, Volume= 3.693 af  
Outflow = 25.92 cfs @ 12.36 hrs, Volume= 3.693 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs

### Reach DP 1:

Hydrograph




### Summary for Reach DP 2:

Inflow Area = 53.900 ac, 0.93% Impervious, Inflow Depth = 2.54" for 10-yr event  
Inflow = 48.08 cfs @ 12.87 hrs, Volume= 11.389 af  
Outflow = 48.08 cfs @ 12.87 hrs, Volume= 11.389 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs

### Reach DP 2:

Hydrograph



**Summary for Pond 1.1P: P-1 Pond**

Inflow Area = 2.600 ac, 0.00% Impervious, Inflow Depth = 2.92" for 10-yr event  
 Inflow = 8.48 cfs @ 12.05 hrs, Volume= 0.632 af  
 Outflow = 1.53 cfs @ 12.59 hrs, Volume= 0.632 af, Atten= 82%, Lag= 32.5 min  
 Primary = 1.53 cfs @ 12.59 hrs, Volume= 0.632 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 625.00' Surf.Area= 6,400 sf Storage= 7,050 cf  
 Peak Elev= 626.81' @ 12.59 hrs Surf.Area= 13,263 sf Storage= 18,485 cf (11,435 cf above start)

Plug-Flow detention time= 562.5 min calculated for 0.470 af (74% of inflow)  
 Center-of-Mass det. time= 316.5 min ( 1,157.0 - 840.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	620.00'	3,500 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	620.00'	41,950 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		45,450 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
620.00	100	0	0
622.00	300	400	400
624.00	700	1,000	1,400
625.00	3,500	2,100	3,500


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
620.00	100	0	0
622.00	400	500	500
624.00	800	1,200	1,700
625.00	2,900	1,850	3,550
627.00	10,500	13,400	16,950
629.00	14,500	25,000	41,950

Device	Routing	Invert	Outlet Devices
#1	Primary	625.00'	<b>2.0" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	626.00'	<b>9.0" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=1.53 cfs @ 12.59 hrs HW=626.81' TW=0.00' (Dynamic Tailwater)  
 ↗ **1=Orifice/Grate** (Orifice Controls 0.14 cfs @ 6.32 fps)  
 ↘ **2=Orifice/Grate** (Orifice Controls 1.40 cfs @ 3.16 fps)

### Pond 1.1P: P-1 Pond

Hydrograph



**Summary for Pond 1.2P: Infiltration Basin**

Inflow Area =      2.400 ac, 12.50% Impervious, Inflow Depth > 2.35" for 10-yr event  
 Inflow      =      0.50 cfs @ 12.28 hrs, Volume=      0.470 af  
 Outflow      =      0.12 cfs @ 25.00 hrs, Volume=      0.470 af, Atten= 76%, Lag= 763.4 min  
 Discarded =      0.12 cfs @ 25.00 hrs, Volume=      0.470 af  
 Primary      =      0.00 cfs @ 0.00 hrs, Volume=      0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 668.21' @ 25.00 hrs    Surf.Area= 5,267 sf    Storage= 9,095 cf

Plug-Flow detention time= 824.5 min calculated for 0.470 af (100% of inflow)  
 Center-of-Mass det. time= 824.5 min ( 2,103.6 - 1,279.1 )

Volume	Invert	Avail.Storage	Storage Description
#1	666.00'	20,500 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
666.00	3,000	0	0
668.00	5,000	8,000	8,000
670.00	7,500	12,500	20,500


Device	Routing	Invert	Outlet Devices
#1	Discarded	666.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	669.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.12 cfs @ 25.00 hrs HW=668.21' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.12 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=666.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.2P: Infiltration Basin

Hydrograph



**Summary for Pond 1.2PT: Pretreatment Basin**

Inflow Area = 2.400 ac, 12.50% Impervious, Inflow Depth = 3.50" for 10-yr event  
 Inflow = 7.40 cfs @ 12.12 hrs, Volume= 0.699 af  
 Outflow = 3.95 cfs @ 12.32 hrs, Volume= 0.699 af, Atten= 47%, Lag= 11.9 min  
 Primary = 0.50 cfs @ 12.28 hrs, Volume= 0.470 af  
 Secondary = 3.44 cfs @ 12.32 hrs, Volume= 0.229 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 669.17' @ 12.32 hrs Surf.Area= 5,168 sf Storage= 8,853 cf

Plug-Flow detention time= 288.2 min calculated for 0.698 af (100% of inflow)  
 Center-of-Mass det. time= 289.7 min ( 1,113.4 - 823.7 )

Volume	Invert	Avail.Storage	Storage Description
#1	667.00'	20,250 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
667.00	3,000	0	0
668.00	4,000	3,500	3,500
670.00	6,000	10,000	13,500
671.00	7,500	6,750	20,250


Device	Routing	Invert	Outlet Devices
#1	Primary	667.00'	<b>4.0" Round Culvert</b> L= 30.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 667.00' / 666.00' S= 0.0333 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	668.50'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.50 cfs @ 12.28 hrs HW=669.16' TW=666.62' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.50 cfs @ 5.73 fps)

**Secondary OutFlow** Max=3.42 cfs @ 12.32 hrs HW=669.16' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir (Weir Controls 3.42 cfs @ 2.57 fps)

### Pond 1.2PT: Pretreatment Basin

Hydrograph



**Summary for Pond 1.3P: Infiltration Basin**

Inflow Area = 2.900 ac, 17.24% Impervious, Inflow Depth = 2.55" for 10-yr event  
 Inflow = 0.57 cfs @ 12.19 hrs, Volume= 0.615 af  
 Outflow = 0.19 cfs @ 27.37 hrs, Volume= 0.615 af, Atten= 67%, Lag= 910.4 min  
 Discarded = 0.19 cfs @ 27.37 hrs, Volume= 0.615 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 664.06' @ 27.37 hrs Surf.Area= 8,107 sf Storage= 13,491 cf

Plug-Flow detention time= 751.0 min calculated for 0.615 af (100% of inflow)  
 Center-of-Mass det. time= 750.6 min ( 1,848.1 - 1,097.5 )

Volume	Invert	Avail.Storage	Storage Description
#1	662.00'	32,500 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
662.00	5,000	0	0
664.00	8,000	13,000	13,000
666.00	11,500	19,500	32,500


Device	Routing	Invert	Outlet Devices
#1	Discarded	662.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	664.50'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.19 cfs @ 27.37 hrs HW=664.06' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.19 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=662.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.3P: Infiltration Basin

Hydrograph



**Summary for Pond 1.3PT: Pretreatment Basin**

Inflow Area = 2.900 ac, 17.24% Impervious, Inflow Depth = 3.70" for 10-yr event  
 Inflow = 11.92 cfs @ 12.04 hrs, Volume= 0.894 af  
 Outflow = 4.86 cfs @ 12.21 hrs, Volume= 0.893 af, Atten= 59%, Lag= 10.4 min  
 Primary = 0.57 cfs @ 12.19 hrs, Volume= 0.615 af  
 Secondary = 4.30 cfs @ 12.21 hrs, Volume= 0.278 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 666.37' @ 12.21 hrs Surf.Area= 7,051 sf Storage= 12,488 cf

Plug-Flow detention time= 184.5 min calculated for 0.893 af (100% of inflow)  
 Center-of-Mass det. time= 184.1 min ( 993.8 - 809.8 )

Volume	Invert	Avail.Storage	Storage Description
#1	664.00'	26,000 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
664.00	3,500	0	0
666.00	6,500	10,000	10,000
668.00	9,500	16,000	26,000


Device	Routing	Invert	Outlet Devices
#1	Primary	664.00'	<b>4.0" Round Culvert</b> L= 40.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 664.00' / 662.00' S= 0.0500 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	665.70'	<b>2.5' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.56 cfs @ 12.19 hrs HW=666.36' TW=662.39' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.56 cfs @ 6.46 fps)

**Secondary OutFlow** Max=4.26 cfs @ 12.21 hrs HW=666.36' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir (Weir Controls 4.26 cfs @ 2.57 fps)

### Pond 1.3PT: Pretreatment Basin

Hydrograph



**Summary for Pond 2.1P: Infiltration Basin**

Inflow Area =      3.400 ac, 14.71% Impervious, Inflow Depth > 2.17" for 10-yr event  
 Inflow      =      0.38 cfs @ 12.29 hrs, Volume=      0.614 af  
 Outflow      =      0.22 cfs @ 29.15 hrs, Volume=      0.614 af, Atten= 42%, Lag= 1,011.2 min  
 Discarded =      0.22 cfs @ 29.15 hrs, Volume=      0.614 af  
 Primary      =      0.00 cfs @ 0.00 hrs, Volume=      0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 665.87' @ 29.15 hrs    Surf.Area= 9,475 sf    Storage= 6,722 cf

Plug-Flow detention time= 348.3 min calculated for 0.614 af (100% of inflow)  
 Center-of-Mass det. time= 348.2 min ( 1,745.2 - 1,397.0 )

Volume	Invert	Avail.Storage	Storage Description
#1	665.00'	34,000 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
665.00	6,000	0	0
666.00	10,000	8,000	8,000
668.00	16,000	26,000	34,000


Device	Routing	Invert	Outlet Devices
#1	Discarded	665.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	667.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.22 cfs @ 29.15 hrs HW=665.87' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.22 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=665.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 2.1P: Infiltration Basin

Hydrograph



**Summary for Pond 2.1PT: Pretreatment Basin**

Inflow Area = 3.400 ac, 14.71% Impervious, Inflow Depth = 3.60" for 10-yr event  
 Inflow = 13.65 cfs @ 12.04 hrs, Volume= 1.019 af  
 Outflow = 4.22 cfs @ 12.29 hrs, Volume= 1.016 af, Atten= 69%, Lag= 15.2 min  
 Primary = 0.38 cfs @ 12.29 hrs, Volume= 0.614 af  
 Secondary = 3.84 cfs @ 12.29 hrs, Volume= 0.401 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 667.47' @ 12.29 hrs Surf.Area= 13,073 sf Storage= 17,332 cf

Plug-Flow detention time= 350.9 min calculated for 1.016 af (100% of inflow)  
 Center-of-Mass det. time= 349.0 min ( 1,163.0 - 814.0 )

Volume	Invert	Avail.Storage	Storage Description
#1	666.00'	39,250 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
666.00	10,500	0	0
668.00	14,000	24,500	24,500
669.00	15,500	14,750	39,250


Device	Routing	Invert	Outlet Devices
#1	Primary	666.00'	<b>4.0" Round Culvert</b> L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 666.00' / 665.00' S= 0.0200 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	667.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.38 cfs @ 12.29 hrs HW=667.47' TW=665.13' (Dynamic Tailwater)  
 ↑1=Culvert (Barrel Controls 0.38 cfs @ 4.35 fps)

**Secondary OutFlow** Max=3.84 cfs @ 12.29 hrs HW=667.47' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir (Weir Controls 3.84 cfs @ 2.04 fps)

### Pond 2.1PT: Pretreatment Basin

Hydrograph



**Summary for Pond 2.2P: P-1 Pond**

Inflow Area =      3.000 ac,    0.00% Impervious,    Inflow Depth =    3.80"    for 10-yr event  
 Inflow        =      8.59 cfs @    12.18 hrs,    Volume=            0.950 af  
 Outflow      =      2.87 cfs @    12.64 hrs,    Volume=            0.950 af,    Atten= 67%,    Lag= 27.5 min  
 Primary      =      2.87 cfs @    12.64 hrs,    Volume=            0.950 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 653.00'    Surf.Area= 2,800 sf    Storage= 7,200 cf  
 Peak Elev= 655.67' @ 12.64 hrs    Surf.Area= 10,509 sf    Storage= 25,410 cf    (18,210 cf above start)

Plug-Flow detention time= 666.4 min calculated for 0.784 af (83% of inflow)  
 Center-of-Mass det. time= 465.7 min ( 1,281.1 - 815.4 )

Volume	Invert	Avail.Storage	Storage Description
#1	649.00'	2,300 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	649.00'	49,300 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		51,600 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
649.00	300	0	0
651.00	500	800	800
653.00	1,000	1,500	2,300


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
649.00	700	0	0
651.00	1,200	1,900	1,900
653.00	1,800	3,000	4,900
654.00	7,000	4,400	9,300
656.00	10,000	17,000	26,300
658.00	13,000	23,000	49,300

Device	Routing	Invert	Outlet Devices
#1	Primary	653.00'	<b>2.0" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	654.80'	<b>1.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=2.86 cfs @ 12.64 hrs    HW=655.67'    TW=0.00'    (Dynamic Tailwater)  
 ↖ **1=Orifice/Grate** (Orifice Controls 0.17 cfs @ 7.75 fps)  
 ↖ **2=Broad-Crested Rectangular Weir** (Weir Controls 2.70 cfs @ 3.09 fps)

### Pond 2.2P: P-1 Pond

Hydrograph



**Summary for Pond 2.3P: P-1 Pond**

Inflow Area = 1.800 ac, 0.00% Impervious, Inflow Depth = 4.12" for 10-yr event  
 Inflow = 8.02 cfs @ 12.04 hrs, Volume= 0.618 af  
 Outflow = 3.48 cfs @ 12.20 hrs, Volume= 0.618 af, Atten= 57%, Lag= 9.6 min  
 Primary = 3.48 cfs @ 12.20 hrs, Volume= 0.618 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 646.00' Surf.Area= 1,300 sf Storage= 2,700 cf  
 Peak Elev= 648.63' @ 12.20 hrs Surf.Area= 6,989 sf Storage= 13,611 cf (10,911 cf above start)

Plug-Flow detention time= 703.1 min calculated for 0.556 af (90% of inflow)  
 Center-of-Mass det. time= 568.6 min ( 1,359.4 - 790.7 )

Volume	Invert	Avail.Storage	Storage Description
#1	642.00'	1,400 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	642.00'	22,100 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		23,500 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
642.00	100	0	0
644.00	300	400	400
646.00	700	1,000	1,400

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
642.00	100	0	0
644.00	300	400	400
646.00	600	900	1,300
647.00	4,200	2,400	3,700
648.00	5,400	4,800	8,500
650.00	8,200	13,600	22,100


Device	Routing	Invert	Outlet Devices
#1	Primary	646.00'	<b>1.5" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	648.20'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=3.48 cfs @ 12.20 hrs HW=648.63' TW=0.00' (Dynamic Tailwater)

- 1=Orifice/Grate (Orifice Controls 0.09 cfs @ 7.72 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 3.38 cfs @ 1.94 fps)

Pond 2.3P: P-1 Pond

Hydrograph



**Summary for Subcatchment 1.0S:**

Runoff = 40.65 cfs @ 12.37 hrs, Volume= 6.374 af, Depth= 5.75"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"


Area (ac)	CN	Description
5.400	77	Woods, Good, HSG D
7.900	70	Woods, Good, HSG C
13.300	73	Weighted Average
13.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
21.0	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
4.5	425	0.1000	1.58		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
5.1	1,113	0.0270	3.63	9.80	<b>Channel Flow,</b> Area= 2.7 sf Perim= 7.2' r= 0.38' n= 0.035 Earth, dense weeds
30.6	1,638	Total			

**Subcatchment 1.0S:**

Hydrograph



**Summary for Subcatchment 1.1S:**

Runoff = 16.61 cfs @ 12.05 hrs, Volume= 1.433 af, Depth= 6.62"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"

Area (ac)	CN	Description
0.500	96	Gravel surface, HSG D
0.900	78	Meadow, non-grazed, HSG D
0.300	71	Meadow, non-grazed, HSG C
0.600	77	Woods, Good, HSG D
0.300	70	Woods, Good, HSG C
2.600	80	Weighted Average
2.600		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.2000	0.30		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
0.8	152	0.2300	3.36		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
6.4	252	Total			

**Subcatchment 1.1S:**

Hydrograph



**Summary for Subcatchment 1.2S:**

Runoff = 13.46 cfs @ 12.12 hrs, Volume= 1.471 af, Depth= 7.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"


Area (ac)	CN	Description
1.100	96	Gravel surface, HSG C
0.300	98	Paved parking, HSG C
1.000	71	Meadow, non-grazed, HSG C
2.400	86	Weighted Average
2.100		87.50% Pervious Area
0.300		12.50% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.5	70	0.0200	0.11		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
0.5	30	0.0200	1.10		<b>Sheet Flow,</b> Smooth surfaces n= 0.011 P2= 3.34"
0.3	50	0.0200	2.87		<b>Shallow Concentrated Flow,</b> Paved Kv= 20.3 fps
0.8	206	0.0200	4.28	5.35	<b>Trap/Vee/Rect Channel Flow,</b> Bot.W=1.00' D=0.50' Z= 3.0 '/' Top.W=4.00' n= 0.022 Earth, clean & straight
12.1	356	Total			

### Subcatchment 1.2S:

Hydrograph



**Summary for Subcatchment 1.3S:**

Runoff = 20.76 cfs @ 12.04 hrs, Volume= 1.836 af, Depth= 7.60"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"

Area (ac)	CN	Description
1.400	96	Gravel surface, HSG C
0.500	98	Paved parking, HSG C
1.000	71	Meadow, non-grazed, HSG C
2.900	88	Weighted Average
2.400		82.76% Pervious Area
0.500		17.24% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.3S:**

Hydrograph



**Summary for Subcatchment 2.0S:**

Runoff = 96.88 cfs @ 12.88 hrs, Volume= 22.844 af, Depth= 6.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"


Area (ac)	CN	Description
31.900	77	Woods, Good, HSG D
13.800	70	Woods, Good, HSG C
45.700	75	Weighted Average
45.700		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
27.7	100	0.0100	0.06		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.34"
40.1	2,463	0.0420	1.02		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
67.8	2,563	Total			

**Subcatchment 2.0S:**

Hydrograph



**Summary for Subcatchment 2.1S:**

Runoff = 24.09 cfs @ 12.04 hrs, Volume= 2.118 af, Depth= 7.47"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"

Area (ac)	CN	Description
1.600	96	Gravel surface, HSG C
0.500	98	Paved parking, HSG C
1.300	71	Meadow, non-grazed, HSG C
3.400	87	Weighted Average
2.900		85.29% Pervious Area
0.500		14.71% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 2.1S:**

Hydrograph



**Summary for Subcatchment 2.2S:**

Runoff = 15.16 cfs @ 12.18 hrs, Volume= 1.930 af, Depth= 7.72"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"

Area (ac)	CN	Description
1.900	96	Gravel surface, HSG D
0.800	78	Meadow, non-grazed, HSG D
0.300	71	Meadow, non-grazed, HSG C
3.000	89	Weighted Average
3.000		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
14.0	100	0.0200	0.12		<b>Sheet Flow,</b> Grass: Dense n= 0.240 P2= 3.34"
1.0	230	0.0200	3.79	1.90	<b>Trap/Vee/Rect Channel Flow,</b> Bot.W=1.00' D=0.50' n= 0.022 Earth, clean & straight
1.8	485	0.0100	4.54	3.56	<b>Pipe Channel,</b> 12.0" Round Area= 0.8 sf Perim= 3.1' r= 0.25' n= 0.013 Corrugated PE, smooth interior
16.8	815	Total			

**Subcatchment 2.2S:**

Hydrograph



**Summary for Subcatchment 2.3S:**

Runoff = 13.33 cfs @ 12.04 hrs, Volume= 1.213 af, Depth= 8.08"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 NY-East Point Energy 24-hr S1 100-yr Rainfall=9.05"

Area (ac)	CN	Description
1.400	96	Gravel surface, HSG D
0.400	78	Meadow, non-grazed, HSG D
1.800	92	Weighted Average
1.800		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 2.3S:**

Hydrograph




### Summary for Reach DP 1:

Inflow Area = 21.200 ac, 3.77% Impervious, Inflow Depth = 5.53" for 100-yr event  
Inflow = 60.55 cfs @ 12.32 hrs, Volume= 9.775 af  
Outflow = 60.55 cfs @ 12.32 hrs, Volume= 9.775 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs

### Reach DP 1:

Hydrograph




### Summary for Reach DP 2:

Inflow Area = 53.900 ac, 0.93% Impervious, Inflow Depth = 6.10" for 100-yr event  
Inflow = 108.86 cfs @ 12.84 hrs, Volume= 27.383 af  
Outflow = 108.86 cfs @ 12.84 hrs, Volume= 27.383 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs

### Reach DP 2:

Hydrograph



**Summary for Pond 1.1P: P-1 Pond**

Inflow Area = 2.600 ac, 0.00% Impervious, Inflow Depth = 6.62" for 100-yr event  
 Inflow = 16.61 cfs @ 12.05 hrs, Volume= 1.433 af  
 Outflow = 2.90 cfs @ 12.61 hrs, Volume= 1.433 af, Atten= 83%, Lag= 33.8 min  
 Primary = 2.90 cfs @ 12.61 hrs, Volume= 1.433 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 625.00' Surf.Area= 6,400 sf Storage= 7,050 cf  
 Peak Elev= 628.01' @ 12.61 hrs Surf.Area= 16,018 sf Storage= 32,061 cf (25,011 cf above start)

Plug-Flow detention time= 314.3 min calculated for 1.271 af (89% of inflow)  
 Center-of-Mass det. time= 210.7 min ( 1,024.3 - 813.7 )

Volume	Invert	Avail.Storage	Storage Description
#1	620.00'	3,500 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	620.00'	41,950 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		45,450 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
620.00	100	0	0
622.00	300	400	400
624.00	700	1,000	1,400
625.00	3,500	2,100	3,500


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
620.00	100	0	0
622.00	400	500	500
624.00	800	1,200	1,700
625.00	2,900	1,850	3,550
627.00	10,500	13,400	16,950
629.00	14,500	25,000	41,950

Device	Routing	Invert	Outlet Devices
#1	Primary	625.00'	<b>2.0" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	626.00'	<b>9.0" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=2.90 cfs @ 12.61 hrs HW=628.01' TW=0.00' (Dynamic Tailwater)  
 1=Orifice/Grate (Orifice Controls 0.18 cfs @ 8.23 fps)  
 2=Orifice/Grate (Orifice Controls 2.72 cfs @ 6.15 fps)

### Pond 1.1P: P-1 Pond

Hydrograph



**Summary for Pond 1.2P: Infiltration Basin**

Inflow Area = 2.400 ac, 12.50% Impervious, Inflow Depth > 2.67" for 100-yr event  
 Inflow = 0.49 cfs @ 12.21 hrs, Volume= 0.535 af  
 Outflow = 0.13 cfs @ 24.47 hrs, Volume= 0.535 af, Atten= 74%, Lag= 735.7 min  
 Discarded = 0.13 cfs @ 24.47 hrs, Volume= 0.535 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 668.38' @ 24.47 hrs Surf.Area= 5,477 sf Storage= 9,997 cf

Plug-Flow detention time= 888.5 min calculated for 0.535 af (100% of inflow)  
 Center-of-Mass det. time= 888.5 min ( 2,097.8 - 1,209.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	666.00'	20,500 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
666.00	3,000	0	0
668.00	5,000	8,000	8,000
670.00	7,500	12,500	20,500


Device	Routing	Invert	Outlet Devices
#1	Discarded	666.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	669.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.13 cfs @ 24.47 hrs HW=668.38' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.13 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=666.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.2P: Infiltration Basin

Hydrograph



**Summary for Pond 1.2PT: Pretreatment Basin**

Inflow Area = 2.400 ac, 12.50% Impervious, Inflow Depth = 7.35" for 100-yr event  
 Inflow = 13.46 cfs @ 12.12 hrs, Volume= 1.471 af  
 Outflow = 10.20 cfs @ 12.22 hrs, Volume= 1.470 af, Atten= 24%, Lag= 6.5 min  
 Primary = 0.49 cfs @ 12.21 hrs, Volume= 0.535 af  
 Secondary = 9.71 cfs @ 12.22 hrs, Volume= 0.936 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 669.79' @ 12.22 hrs Surf.Area= 5,788 sf Storage= 12,252 cf

Plug-Flow detention time= 175.1 min calculated for 1.470 af (100% of inflow)  
 Center-of-Mass det. time= 174.8 min ( 974.6 - 799.8 )

Volume	Invert	Avail.Storage	Storage Description
#1	667.00'	20,250 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
667.00	3,000	0	0
668.00	4,000	3,500	3,500
670.00	6,000	10,000	13,500
671.00	7,500	6,750	20,250


Device	Routing	Invert	Outlet Devices
#1	Primary	667.00'	<b>4.0" Round Culvert</b> L= 30.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 667.00' / 666.00' S= 0.0333 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	668.50'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.49 cfs @ 12.21 hrs HW=669.78' TW=667.36' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.49 cfs @ 5.60 fps)

**Secondary OutFlow** Max=9.61 cfs @ 12.22 hrs HW=669.78' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir (Weir Controls 9.61 cfs @ 3.76 fps)

### Pond 1.2PT: Pretreatment Basin

Hydrograph



**Summary for Pond 1.3P: Infiltration Basin**

Inflow Area = 2.900 ac, 17.24% Impervious, Inflow Depth = 3.32" for 100-yr event  
 Inflow = 0.57 cfs @ 12.12 hrs, Volume= 0.803 af  
 Outflow = 0.20 cfs @ 28.59 hrs, Volume= 0.803 af, Atten= 65%, Lag= 987.9 min  
 Discarded = 0.20 cfs @ 28.59 hrs, Volume= 0.803 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 664.43' @ 28.59 hrs Surf.Area= 8,744 sf Storage= 16,560 cf

Plug-Flow detention time= 897.2 min calculated for 0.802 af (100% of inflow)  
 Center-of-Mass det. time= 896.8 min ( 1,997.9 - 1,101.0 )

Volume	Invert	Avail.Storage	Storage Description
#1	662.00'	32,500 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
662.00	5,000	0	0
664.00	8,000	13,000	13,000
666.00	11,500	19,500	32,500


Device	Routing	Invert	Outlet Devices
#1	Discarded	662.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	664.50'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.20 cfs @ 28.59 hrs HW=664.43' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.20 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=662.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 1.3P: Infiltration Basin

Hydrograph



**Summary for Pond 1.3PT: Pretreatment Basin**

Inflow Area = 2.900 ac, 17.24% Impervious, Inflow Depth = 7.60" for 100-yr event  
 Inflow = 20.76 cfs @ 12.04 hrs, Volume= 1.836 af  
 Outflow = 13.28 cfs @ 12.13 hrs, Volume= 1.836 af, Atten= 36%, Lag= 5.5 min  
 Primary = 0.57 cfs @ 12.12 hrs, Volume= 0.803 af  
 Secondary = 12.71 cfs @ 12.13 hrs, Volume= 1.033 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 667.03' @ 12.13 hrs Surf.Area= 8,043 sf Storage= 17,478 cf

Plug-Flow detention time= 143.5 min calculated for 1.836 af (100% of inflow)  
 Center-of-Mass det. time= 143.1 min ( 930.2 - 787.0 )

Volume	Invert	Avail.Storage	Storage Description
#1	664.00'	26,000 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
664.00	3,500	0	0
666.00	6,500	10,000	10,000
668.00	9,500	16,000	26,000


Device	Routing	Invert	Outlet Devices
#1	Primary	664.00'	<b>4.0" Round Culvert</b> L= 40.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 664.00' / 662.00' S= 0.0500 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	665.70'	<b>2.5' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.57 cfs @ 12.12 hrs HW=667.02' TW=662.96' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.57 cfs @ 6.54 fps)

**Secondary OutFlow** Max=12.60 cfs @ 12.13 hrs HW=667.02' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir (Weir Controls 12.60 cfs @ 3.82 fps)

### Pond 1.3PT: Pretreatment Basin

Hydrograph



**Summary for Pond 2.1P: Infiltration Basin**

Inflow Area = 3.400 ac, 14.71% Impervious, Inflow Depth > 2.53" for 100-yr event  
 Inflow = 0.42 cfs @ 12.14 hrs, Volume= 0.717 af  
 Outflow = 0.23 cfs @ 28.52 hrs, Volume= 0.717 af, Atten= 46%, Lag= 982.6 min  
 Discarded = 0.23 cfs @ 28.52 hrs, Volume= 0.717 af  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 665.95' @ 28.52 hrs Surf.Area= 9,810 sf Storage= 7,529 cf

Plug-Flow detention time= 382.9 min calculated for 0.717 af (100% of inflow)  
 Center-of-Mass det. time= 382.9 min ( 1,713.0 - 1,330.1 )

Volume	Invert	Avail.Storage	Storage Description
#1	665.00'	34,000 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
665.00	6,000	0	0
666.00	10,000	8,000	8,000
668.00	16,000	26,000	34,000


Device	Routing	Invert	Outlet Devices
#1	Discarded	665.00'	<b>1.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.01'
#2	Primary	667.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Discarded OutFlow** Max=0.23 cfs @ 28.52 hrs HW=665.95' (Free Discharge)  
 ↑1=Exfiltration (Exfiltration Controls 0.23 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=665.00' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir ( Controls 0.00 cfs)

### Pond 2.1P: Infiltration Basin

Hydrograph



**Summary for Pond 2.1PT: Pretreatment Basin**

Inflow Area = 3.400 ac, 14.71% Impervious, Inflow Depth = 7.47" for 100-yr event  
 Inflow = 24.09 cfs @ 12.04 hrs, Volume= 2.118 af  
 Outflow = 14.16 cfs @ 12.15 hrs, Volume= 2.115 af, Atten= 41%, Lag= 6.6 min  
 Primary = 0.42 cfs @ 12.14 hrs, Volume= 0.717 af  
 Secondary = 13.74 cfs @ 12.15 hrs, Volume= 1.397 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Peak Elev= 668.02' @ 12.15 hrs Surf.Area= 14,034 sf Storage= 24,819 cf

Plug-Flow detention time= 210.6 min calculated for 2.115 af (100% of inflow)  
 Center-of-Mass det. time= 209.6 min ( 1,000.2 - 790.6 )

Volume	Invert	Avail.Storage	Storage Description
#1	666.00'	39,250 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
666.00	10,500	0	0
668.00	14,000	24,500	24,500
669.00	15,500	14,750	39,250


Device	Routing	Invert	Outlet Devices
#1	Primary	666.00'	<b>4.0" Round Culvert</b> L= 50.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 666.00' / 665.00' S= 0.0200 '/' Cc= 0.900 n= 0.012, Flow Area= 0.09 sf
#2	Secondary	667.00'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=0.42 cfs @ 12.14 hrs HW=668.02' TW=665.37' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.42 cfs @ 4.84 fps)

**Secondary OutFlow** Max=13.73 cfs @ 12.15 hrs HW=668.02' TW=0.00' (Dynamic Tailwater)  
 ↑2=Broad-Crested Rectangular Weir (Weir Controls 13.73 cfs @ 3.36 fps)

### Pond 2.1PT: Pretreatment Basin

Hydrograph



**Summary for Pond 2.2P: P-1 Pond**

Inflow Area = 3.000 ac, 0.00% Impervious, Inflow Depth = 7.72" for 100-yr event  
 Inflow = 15.16 cfs @ 12.18 hrs, Volume= 1.930 af  
 Outflow = 8.22 cfs @ 12.44 hrs, Volume= 1.930 af, Atten= 46%, Lag= 15.7 min  
 Primary = 8.22 cfs @ 12.44 hrs, Volume= 1.930 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 653.00' Surf.Area= 2,800 sf Storage= 7,200 cf  
 Peak Elev= 656.60' @ 12.44 hrs Surf.Area= 11,902 sf Storage= 34,881 cf (27,681 cf above start)

Plug-Flow detention time= 369.1 min calculated for 1.764 af (91% of inflow)  
 Center-of-Mass det. time= 279.0 min ( 1,072.3 - 793.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	649.00'	2,300 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	649.00'	49,300 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		51,600 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
649.00	300	0	0
651.00	500	800	800
653.00	1,000	1,500	2,300


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
649.00	700	0	0
651.00	1,200	1,900	1,900
653.00	1,800	3,000	4,900
654.00	7,000	4,400	9,300
656.00	10,000	17,000	26,300
658.00	13,000	23,000	49,300

Device	Routing	Invert	Outlet Devices
#1	Primary	653.00'	<b>2.0" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	654.80'	<b>1.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=8.21 cfs @ 12.44 hrs HW=656.60' TW=0.00' (Dynamic Tailwater)  
 ↖ **1=Orifice/Grate** (Orifice Controls 0.20 cfs @ 9.03 fps)  
 ↖ **2=Broad-Crested Rectangular Weir** (Weir Controls 8.02 cfs @ 4.45 fps)

### Pond 2.2P: P-1 Pond

Hydrograph



**Summary for Pond 2.3P: P-1 Pond**

Inflow Area = 1.800 ac, 0.00% Impervious, Inflow Depth = 8.08" for 100-yr event  
 Inflow = 13.33 cfs @ 12.04 hrs, Volume= 1.213 af  
 Outflow = 9.89 cfs @ 12.11 hrs, Volume= 1.213 af, Atten= 26%, Lag= 4.3 min  
 Primary = 9.89 cfs @ 12.11 hrs, Volume= 1.213 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-120.00 hrs, dt= 0.05 hrs  
 Starting Elev= 646.00' Surf.Area= 1,300 sf Storage= 2,700 cf  
 Peak Elev= 649.02' @ 12.11 hrs Surf.Area= 7,526 sf Storage= 16,126 cf (13,426 cf above start)

Plug-Flow detention time= 388.1 min calculated for 1.151 af (95% of inflow)  
 Center-of-Mass det. time= 325.1 min ( 1,096.3 - 771.2 )

Volume	Invert	Avail.Storage	Storage Description
#1	642.00'	1,400 cf	<b>Forebay (Prismatic)</b> Listed below (Recalc)
#2	642.00'	22,100 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)
		23,500 cf	Total Available Storage

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
642.00	100	0	0
644.00	300	400	400
646.00	700	1,000	1,400


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
642.00	100	0	0
644.00	300	400	400
646.00	600	900	1,300
647.00	4,200	2,400	3,700
648.00	5,400	4,800	8,500
650.00	8,200	13,600	22,100

Device	Routing	Invert	Outlet Devices
#1	Primary	646.00'	<b>1.5" Vert. Orifice/Grate</b> C= 0.600
#2	Primary	648.20'	<b>4.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32

**Primary OutFlow** Max=9.75 cfs @ 12.11 hrs HW=649.01' TW=0.00' (Dynamic Tailwater)  
 1=Orifice/Grate (Orifice Controls 0.10 cfs @ 8.27 fps)  
 2=Broad-Crested Rectangular Weir (Weir Controls 9.64 cfs @ 2.97 fps)

### Pond 2.3P: P-1 Pond

Hydrograph





**APPENDIX D**

**NYSDEC SPDES for Construction Activities Construction Site Log Book**



**APPENDIX F  
CONSTRUCTION SITE INSPECTION  
AND MAINTENANCE LOG BOOK**

**STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM FOR CONSTRUCTION  
ACTIVITIES**

**SAMPLE CONSTRUCTION SITE LOG BOOK**

Table of Contents

---

- I. Pre-Construction Meeting Documents
  - a. Preamble to Site Assessment and Inspections
  - b. Pre-Construction Site Assessment Checklist
  
- II. Construction Duration Inspections
  - a. Directions
  - b. Modification to the SWPPP

**I. PRE-CONSTRUCTION MEETING DOCUMENTS**

**Project Name** \_\_\_\_\_  
**Permit No.** \_\_\_\_\_ **Date of Authorization** \_\_\_\_\_  
**Name of Operator** \_\_\_\_\_  
**Prime Contractor** \_\_\_\_\_

**a. Preamble to Site Assessment and Inspections**

The Following Information To Be Read By All Person’s Involved in The Construction of Stormwater Related Activities:

The Operator agrees to have a qualified inspector<sup>1</sup> conduct an assessment of the site prior to the commencement of construction<sup>2</sup> and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Operator shall certify in this site logbook that the SWPPP has been prepared in accordance with the State’s standards and meets all Federal, State and local erosion and sediment control requirements. A preconstruction meeting should be held to review all of the SWPPP requirements with construction personnel.

When construction starts, site inspections shall be conducted by the qualified inspector at least every 7 calendar days. The Operator shall maintain a record of all inspection reports in this site logbook. The site logbook shall be maintained on site and be made available to the permitting authorities upon request.

Prior to filing the Notice of Termination or the end of permit term, the Operator shall have a qualified inspector perform a final site inspection. The qualified inspector shall certify that the site has undergone final stabilization<sup>3</sup> using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Operator must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

1 Refer to “Qualified Inspector” inspection requirements in the current SPDES General Permit for Stormwater Discharges from Construction Activity for complete list of inspection requirements.  
2 “Commencement of construction” means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.  
3 “Final stabilization” means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures.

**b. Pre-construction Site Assessment Checklist**  
**(NOTE: Provide comments below as necessary)**

1. Notice of Intent, SWPPP, and Contractors Certification:

**Yes No NA**

- Has a Notice of Intent been filed with the NYS Department of Conservation?
- Is the SWPPP on-site? Where? \_\_\_\_\_
- Is the Plan current? What is the latest revision date? \_\_\_\_\_
- Is a copy of the NOI (with brief description) onsite? Where? \_\_\_\_\_
- Have all contractors involved with stormwater related activities signed a contractor's certification?

2. Resource Protection

**Yes No NA**

- Are construction limits clearly flagged or fenced?
- Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, have been flagged for protection.
- Creek crossings installed prior to land-disturbing activity, including clearing and blasting.

3. Surface Water Protection

**Yes No NA**

- Clean stormwater runoff has been diverted from areas to be disturbed.
- Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- Appropriate practices to protect on-site or downstream surface water are installed.
- Are clearing and grading operations divided into areas <5 acres?

4. Stabilized Construction Access

**Yes No NA**

- A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- Sediment tracked onto public streets is removed or cleaned on a regular basis.

5. Sediment Controls

**Yes No NA**

- Silt fence material and installation comply with the standard drawing and specifications.
- Silt fences are installed at appropriate spacing intervals
- Sediment/detention basin was installed as first land disturbing activity.
- Sediment traps and barriers are installed.

6. Pollution Prevention for Waste and Hazardous Materials

**Yes No NA**

- The Operator or designated representative has been assigned to implement the spill prevention avoidance and response plan.
- The plan is contained in the SWPPP on page \_\_\_\_\_
- Appropriate materials to control spills are onsite. Where? \_\_\_\_\_

## II. CONSTRUCTION DURATION INSPECTIONS

### a. Directions:

**Inspection Forms will be filled out during the entire construction phase of the project.**

Required Elements:

- 1) On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;
- 2) Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;
- 3) Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;
- 4) Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);
- 5) Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and
- 6) Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

**SITE PLAN/SKETCH**

\_\_\_\_\_  
**Inspector (print name)**

\_\_\_\_\_  
**Date of Inspection**

\_\_\_\_\_  
**Qualified Inspector (print name)**

\_\_\_\_\_  
**Qualified Inspector Signature**

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.

**Maintaining Water Quality**

**Yes No NA**

- Is there an increase in turbidity causing a substantial visible contrast to natural conditions at the outfalls?
- Is there residue from oil and floating substances, visible oil film, or globules or grease at the outfalls?
- All disturbance is within the limits of the approved plans.
- Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

**Housekeeping**

1. General Site Conditions

**Yes No NA**

- Is construction site litter, debris and spoils appropriately managed?
- Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- Is construction impacting the adjacent property?
- Is dust adequately controlled?

2. Temporary Stream Crossing

**Yes No NA**

- Maximum diameter pipes necessary to span creek without dredging are installed.
- Installed non-woven geotextile fabric beneath approaches.
- Is fill composed of aggregate (no earth or soil)?
- Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.

3. Stabilized Construction Access

**Yes No NA**

- Stone is clean enough to effectively remove mud from vehicles.
- Installed per standards and specifications?
- Does all traffic use the stabilized entrance to enter and leave site?
- Is adequate drainage provided to prevent ponding at entrance?

**Runoff Control Practices**

1. Excavation Dewatering

**Yes No NA**

- Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- Clean water from upstream pool is being pumped to the downstream pool.
- Sediment laden water from work area is being discharged to a silt-trapping device.
- Constructed upstream berm with one-foot minimum freeboard.

**Runoff Control Practices (continued)**

2. Flow Spreader

**Yes No NA**

- Installed per plan.
- Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.
- Flow sheets out of level spreader without erosion on downstream edge.

3. Interceptor Dikes and Swales

**Yes No NA**

- Installed per plan with minimum side slopes 2H:1V or flatter.
- Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.
- Sediment-laden runoff directed to sediment trapping structure

4. Stone Check Dam

**Yes No NA**

- Is channel stable? (flow is not eroding soil underneath or around the structure).
- Check is in good condition (rocks in place and no permanent pools behind the structure).
- Has accumulated sediment been removed?.

5. Rock Outlet Protection

**Yes No NA**

- Installed per plan.
- Installed concurrently with pipe installation.

**Soil Stabilization**

1. Topsoil and Spoil Stockpiles

**Yes No NA**

- Stockpiles are stabilized with vegetation and/or mulch.
- Sediment control is installed at the toe of the slope.

2. Revegetation

**Yes No NA**

- Temporary seedings and mulch have been applied to idle areas.
- 4 inches minimum of topsoil has been applied under permanent seedings

**Sediment Control Practices**

1. Silt Fence and Linear Barriers

**Yes No NA**

- Installed on Contour, 10 feet from toe of slope (not across conveyance channels).
- Joints constructed by wrapping the two ends together for continuous support.
- Fabric buried 6 inches minimum.
- Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation is \_\_\_% of design capacity.

**Sediment Control Practices (continued)**

2. Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated; Filter Sock or Manufactured practices)

**Yes No NA**

- Installed concrete blocks lengthwise so open ends face outward, not upward.
- Placed wire screen between No. 3 crushed stone and concrete blocks.
- Drainage area is 1acre or less.
- Excavated area is 900 cubic feet.
- Excavated side slopes should be 2:1.
- 2" x 4" frame is constructed and structurally sound.
- Posts 3-foot maximum spacing between posts.
- Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.
- Posts are stable, fabric is tight and without rips or frayed areas.
- Manufactured insert fabric is free of tears and punctures.
- Filter Sock is not torn or flattened and fill material is contained within the mesh sock.

Sediment accumulation \_\_\_% of design capacity.

3. Temporary Sediment Trap

**Yes No NA**

- Outlet structure is constructed per the approved plan or drawing.
- Geotextile fabric has been placed beneath rock fill.
- Sediment trap slopes and disturbed areas are stabilized.

Sediment accumulation is \_\_\_% of design capacity.

4. Temporary Sediment Basin

**Yes No NA**

- Basin and outlet structure constructed per the approved plan.
- Basin side slopes are stabilized with seed/mulch.
- Drainage structure flushed and basin surface restored upon removal of sediment basin facility.
- Sediment basin dewatering pool is dewatering at appropriate rate.

Sediment accumulation is \_\_\_% of design capacity.

Note: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design. All practices shall be maintained in accordance with their respective standards.

Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.



**APPENDIX E**  
**Project and Owner Information**

Site Data:

24 Miller Road  
Mahopac, New York 10541  
Tax Map No.: 86.11-1-14 & 86.8-2-85  
Area: 95.1 acres ±

Owner/Operator Information:

East Point Energy, LLC  
24 Miller Road  
Mahopac, New York 10541  
434-465-6211  
sconnuck@eastpointenergy.com

Parties Responsible for Implementation of the Short and Long Term Maintenance Plan:

East Point Energy, LLC  
24 Miller Road  
Mahopac, New York 10541  
434-465-6211  
sconnuck@eastpointenergy.com

and or the current owner(s) of the subject property.

Qualified Professional Responsible for Inspection of the Stormwater Pollution Prevention Plan:

Insite Engineering, Surveying & Landscape Architecture, P.C.  
3 Garrett Place  
Carmel, New York 10512  
845-225-9690



## **APPENDIX F**

### **NYSDEC Stormwater Management Practice Construction and Maintenance Checklists**

## Open Channel System Construction Inspection Checklist

Project:  
 Location:  
 Site Status:

Date:

Time:

Inspector:

CONSTRUCTION SEQUENCE	SATISFACTORY / UNSATISFACTORY	COMMENTS
<b>1. Pre-Construction</b>		
Pre-construction meeting		
Runoff diverted		
Facility location staked out		
<b>2. Excavation</b>		
Size and location		
Side slope stable		
Soil permeability		
Groundwater / bedrock		
Lateral slopes completely level		
Longitudinal slopes within design range		
Excavation does not compact subsoils		
<b>3. Check dams</b>		
Dimensions		
Spacing		
Materials		

CONSTRUCTION SEQUENCE	SATISFACTORY / UNSATISFACTORY	COMMENTS
<b>4. Structural Components</b>		
Underdrain installed correctly		
Inflow installed correctly		
Pretreatment devices installed		
<b>5. Vegetation</b>		
Complies with planting specifications		
Topsoil adequate in composition and placement		
Adequate erosion control measures in place		
<b>6. Final inspection</b>		
Dimensions		
Check dams		
Proper outlet		
Effective stand of vegetation and stabilization		
Contributing watershed stabilized before flow is routed to the facility		

**Comments:**

---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



---



## Infiltration Basin Construction Inspection Checklist

Project:  
 Location:  
 Site Status:

Date:

Time:

Inspector:

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>1. Pre-Construction</b>		
Runoff diverted		
Soil permeability tested		
Groundwater / bedrock depth		
<b>2. Excavation</b>		
Size and location		
Side slopes stable		
Excavation does not compact subsoils		
<b>3. Embankment</b>		
Barrel		
Anti-seep collar or Filter diaphragm		
Fill material		



## Stormwater/Wetland Pond Construction Inspection Checklist

Project:  
 Location:  
 Site Status:

Date:

Time:

Inspector:

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>Pre-Construction/Materials and Equipment</b>		
Pre-construction meeting		
Pipe and appurtenances on-site prior to construction and dimensions checked		
1. Material (including protective coating, if specified)		
2. Diameter		
3. Dimensions of metal riser or pre-cast concrete outlet structure		
4. Required dimensions between water control structures (orifices, weirs, etc.) are in accordance with approved plans		
5. Barrel stub for prefabricated pipe structures at proper angle for design barrel slope		
6. Number and dimensions of prefabricated anti-seep collars		
7. Watertight connectors and gaskets		
8. Outlet drain valve		
Project benchmark near pond site		
Equipment for temporary de-watering		

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>2. Subgrade Preparation</b>		
Area beneath embankment stripped of all vegetation, topsoil, and organic matter		
<b>3. Pipe Spillway Installation</b>		
Method of installation detailed on plans		
<b>A. Bed preparation</b>		
Installation trench excavated with specified side slopes		
Stable, uniform, dry subgrade of relatively impervious material (If subgrade is wet, contractor shall have defined steps before proceeding with installation)		
Invert at proper elevation and grade		
<b>B. Pipe placement</b>		
Metal / plastic pipe		
1. Watertight connectors and gaskets properly installed		
2. Anti-seep collars properly spaced and having watertight connections to pipe		
3. Backfill placed and tamped by hand under “haunches” of pipe		
4. Remaining backfill placed in max. 8 inch lifts using small power tamping equipment until 2 feet cover over pipe is reached		

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>3. Pipe Spillway Installation</b>		
Concrete pipe		
1. Pipe set on blocks or concrete slab for pouring of low cradle		
2. Pipe installed with rubber gasket joints with no spalling in gasket interface area		
3. Excavation for lower half of anti-seep collar(s) with reinforcing steel set		
4. Entire area where anti-seep collar(s) will come in contact with pipe coated with mastic or other approved waterproof sealant		
5. Low cradle and bottom half of anti-seep collar installed as monolithic pour and of an approved mix		
6. Upper half of anti-seep collar(s) formed with reinforcing steel set		
7. Concrete for collar of an approved mix and vibrated into place (protected from freezing while curing, if necessary)		
8. Forms stripped and collar inspected for honeycomb prior to backfilling. Parge if necessary.		
<b>C. Backfilling</b>		
Fill placed in maximum 8 inch lifts		
Backfill taken minimum 2 feet above top of anti-seep collar elevation before traversing with heavy equipment		

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>4. Riser / Outlet Structure Installation</b>		
Riser located within embankment		
A. Metal riser		
Riser base excavated or formed on stable subgrade to design dimensions		
Set on blocks to design elevations and plumbed		
Reinforcing bars placed at right angles and projecting into sides of riser		
Concrete poured so as to fill inside of riser to invert of barrel		
B. Pre-cast concrete structure		
Dry and stable subgrade		
Riser base set to design elevation		
If more than one section, no spalling in gasket interface area; gasket or approved caulking material placed securely		
Watertight and structurally sound collar or gasket joint where structure connects to pipe spillway		
C. Poured concrete structure		
Footing excavated or formed on stable subgrade, to design dimensions with reinforcing steel set		
Structure formed to design dimensions, with reinforcing steel set as per plan		
Concrete of an approved mix and vibrated into place (protected from freezing while curing, if necessary)		
Forms stripped & inspected for “honeycomb” prior to backfilling; pare if necessary		

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>5. Embankment Construction</b>		
Fill material		
Compaction		
Embankment		
1. Fill placed in specified lifts and compacted with appropriate equipment		
2. Constructed to design cross-section, side slopes and top width		
3. Constructed to design elevation plus allowance for settlement		
<b>6. Impounded Area Construction</b>		
Excavated / graded to design contours and side slopes		
Inlet pipes have adequate outfall protection		
Forebay(s)		
Pond benches		
<b>7. Earth Emergency Spillway Construction</b>		
Spillway located in cut or structurally stabilized with riprap, gabions, concrete, etc.		
Excavated to proper cross-section, side slopes and bottom width		
Entrance channel, crest, and exit channel constructed to design grades and elevations		

CONSTRUCTION SEQUENCE	SATISFACTORY / UNSATISFACTORY	COMMENTS
<b>8. Outlet Protection</b>		
A. End section		
Securely in place and properly backfilled		
B. Endwall		
Footing excavated or formed on stable subgrade, to design dimensions and reinforcing steel set, if specified		
Endwall formed to design dimensions with reinforcing steel set as per plan		
Concrete of an approved mix and vibrated into place (protected from freezing, if necessary)		
Forms stripped and structure inspected for “honeycomb” prior to backfilling; parge if necessary		
C. Riprap apron / channel		
Apron / channel excavated to design cross-section with proper transition to existing ground		
Filter fabric in place		
Stone sized as per plan and uniformly place at the thickness specified		
<b>9. Vegetative Stabilization</b>		
Approved seed mixture or sod		
Proper surface preparation and required soil amendments		
Excelsior mat or other stabilization, as per plan		

CONSTRUCTION SEQUENCE	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>10. Miscellaneous</b>		
Drain for ponds having a permanent pool		
Trash rack / anti-vortex device secured to outlet structure		
Trash protection for low flow pipes, orifices, etc.		
Fencing (when required)		
Access road		
Set aside for clean-out maintenance		
<b>11. Stormwater Wetlands</b>		
Adequate water balance		
Variety of depth zones present		
Approved pondscaping plan in place Reinforcement budget for additional plantings		
Plants and materials ordered 6 months prior to construction		
Construction planned to allow for adequate planting and establishment of plant community (April-June planting window)		
Wetland buffer area preserved to maximum extent possible		

**Comments:**

---

---

---

---

---

---

---

---

---

---

---

**Actions to be Taken:**

---

---

---

---

---

---

---

---

## Open Channel Operation, Maintenance, and Management Inspection Checklist

Project:  
 Location:  
 Site Status:

Date:

Time:

Inspector:

MAINTENANCE ITEM	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>1. Debris Cleanout (Monthly)</b>		
Contributing areas clean of debris		
<b>2. Check Dams or Energy Dissipators (Annual, After Major Storms)</b>		
No evidence of flow going around structures		
No evidence of erosion at downstream toe		
Soil permeability		
Groundwater / bedrock		
<b>3. Vegetation (Monthly)</b>		
Mowing done when needed		
Minimum mowing depth not exceeded		
No evidence of erosion		
Fertilized per specification		
<b>4. Dewatering (Monthly)</b>		
Dewaterers between storms		

MAINTENANCE ITEM	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>5. Sediment deposition (Annual)</b>		
Clean of sediment		
<b>6. Outlet/Overflow Spillway (Annual)</b>		
Good condition, no need for repairs		
No evidence of erosion		

**Comments:**

---

---

---

---

---

---

---

---

---

---

**Actions to be Taken:**

---

---

---

---

---

---

---

---

---

---

### Stormwater Pond/Wetland Operation, Maintenance and Management Inspection Checklist

Project \_\_\_\_\_  
 Location: \_\_\_\_\_  
 Site Status: \_\_\_\_\_  
  
 Date: \_\_\_\_\_  
 Time: \_\_\_\_\_  
  
 Inspector: \_\_\_\_\_

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
<b>1. Embankment and emergency spillway (Annual, After Major Storms)</b>		
1. Vegetation and ground cover adequate		
2. Embankment erosion		
3. Animal burrows		
4. Unauthorized planting		
5. Cracking, bulging, or sliding of dam		
a. Upstream face		
b. Downstream face		
c. At or beyond toe		
downstream		
upstream		
d. Emergency spillway		
6. Pond, toe & chimney drains clear and functioning		
7. Seeps/leaks on downstream face		
8. Slope protection or riprap failure		
9. Vertical/horizontal alignment of top of dam "As-Built"		

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
10. Emergency spillway clear of obstructions and debris		
11. Other (specify)		
<b>2. Riser and principal spillway (Annual)</b>		
Type: Reinforced concrete _____ Corrugated pipe _____ Masonry _____		
1. Low flow orifice obstructed		
2. Low flow trash rack. a. Debris removal necessary		
b. Corrosion control		
3. Weir trash rack maintenance a. Debris removal necessary		
b. corrosion control		
4. Excessive sediment accumulation insider riser		
5. Concrete/masonry condition riser and barrels a. cracks or displacement		
b. Minor spalling (<1" )		
c. Major spalling (rebars exposed)		
d. Joint failures		
e. Water tightness		
6. Metal pipe condition		
7. Control valve a. Operational/exercised		
b. Chained and locked		
8. Pond drain valve a. Operational/exercised		
b. Chained and locked		
9. Outfall channels functioning		
10. Other (specify)		

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
<b>3. Permanent Pool (Wet Ponds) (monthly)</b>		
1. Undesirable vegetative growth		
2. Floating or floatable debris removal required		
3. Visible pollution		
4. Shoreline problem		
5. Other (specify)		
<b>4. Sediment Forebays</b>		
1. Sedimentation noted		
2. Sediment cleanout when depth < 50% design depth		
<b>5. Dry Pond Areas</b>		
1. Vegetation adequate		
2. Undesirable vegetative growth		
3. Undesirable woody vegetation		
4. Low flow channels clear of obstructions		
5. Standing water or wet spots		
6. Sediment and / or trash accumulation		
7. Other (specify)		
<b>6. Condition of Outfalls (Annual , After Major Storms)</b>		
1. Riprap failures		
2. Slope erosion		
3. Storm drain pipes		
4. Endwalls / Headwalls		
5. Other (specify)		
<b>7. Other (Monthly)</b>		
1. Encroachment on pond, wetland or easement area		

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
2. Complaints from residents		
3. Aesthetics a. Grass growing required		
b. Graffiti removal needed		
c. Other (specify)		
4. Conditions of maintenance access routes.		
5. Signs of hydrocarbon build-up		
6. Any public hazards (specify)		
<b>8. Wetland Vegetation (Annual)</b>		
1. Vegetation healthy and growing Wetland maintaining 50% surface area coverage of wetland plants after the second growing season. (If unsatisfactory, reinforcement plantings needed)		
2. Dominant wetland plants: Survival of desired wetland plant species Distribution according to landscaping plan?		
3. Evidence of invasive species		
4. Maintenance of adequate water depths for desired wetland plant species		
5. Harvesting of emergent plantings needed		
6. Have sediment accumulations reduced pool volume significantly or are plants “choked” with sediment		
7. Eutrophication level of the wetland.		
8. Other (specify)		

**Comments:**

---



---



---



---



---

**Actions to be Taken:**

---

---

---

---


## **APPENDIX G**

### **Draft NYSDEC Notice of Intent and MS4 SWPPP Acceptance Form**



# DRAFT

## NOTICE OF INTENT



**New York State Department of Environmental Conservation**  
**Division of Water**  
**625 Broadway, 4th Floor**  
**Albany, New York 12233-3505**

NYR   
(For DEC use only)

**Stormwater Discharges Associated with Construction Activity Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-20-001**  
All sections must be completed unless otherwise noted. Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

**- IMPORTANT -**  
**RETURN THIS FORM TO THE ADDRESS ABOVE**  
**OWNER/OPERATOR MUST SIGN FORM**

### Owner/Operator Information

Owner/Operator (Company Name/Private Owner Name/Municipality Name)

E a s t P o i n t E n e r g y , L L C

Owner/Operator Contact Person Last Name (NOT CONSULTANT)

C o n n u c k

Owner/Operator Contact Person First Name

S c o t t

Owner/Operator Mailing Address

3 1 0 4 t h S t r e e t N E , 3 r d F l o o r

City

C h a r l o t t e s v i l l e

State

V A

Zip

2 2 9 0 2 -

Phone (Owner/Operator)

4 3 4 - 4 6 5 - 6 2 1 1

Fax (Owner/Operator)

-  -

Email (Owner/Operator)

s c o n n u c k @ e a s t p o i n t e n e r g y . c o m

FED TAX ID

-   
(not required for individuals)













**Post-construction Stormwater Management Practice (SMP) Requirements**

**Important:** Completion of Questions 27-39 is not required if response to Question 22 is No.

27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.

- Preservation of Undisturbed Areas
- Preservation of Buffers
- Reduction of Clearing and Grading
- Locating Development in Less Sensitive Areas
- Roadway Reduction
- Sidewalk Reduction
- Driveway Reduction
- Cul-de-sac Reduction
- Building Footprint Reduction
- Parking Reduction

27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).

- All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
- Compacted areas were considered as impervious cover when calculating the **WQv Required**, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.

28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout).

**Total WQv Required**

acre-feet

29. Identify the RR techniques (Area Reduction), RR techniques (Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to reduce the Total WQv Required(#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

**Note:** Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

Table 1 - Runoff Reduction (RR) Techniques and Standard Stormwater Management Practices (SMPs)

RR Techniques (Area Reduction)	Total Contributing Area (acres)		Total Contributing Impervious Area (acres)	
	Area (acres)	Area (acres)	Impervious Area (acres)	Impervious Area (acres)
Conservation of Natural Areas (RR-1) ...	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
Sheetflow to Riparian Buffers/Filters Strips (RR-2) .....	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
Tree Planting/Tree Pit (RR-3) .....	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
Disconnection of Rooftop Runoff (RR-4) ..	<input type="text"/>	<input type="text"/>	and/or	<input type="text"/>
<u>RR Techniques (Volume Reduction)</u>				
Vegetated Swale (RR-5) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Rain Garden (RR-6) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Stormwater Planter (RR-7) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Rain Barrel/Cistern (RR-8) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Porous Pavement (RR-9) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Green Roof (RR-10) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<u>Standard SMPs with RRv Capacity</u>				
Infiltration Trench (I-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
✓ Infiltration Basin (I-2) .....	<input type="text"/>	5		4
Dry Well (I-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Underground Infiltration System (I-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Bioretention (F-5) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Dry Swale (O-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
<u>Standard SMPs</u>				
✓ Micropool Extended Detention (P-1) .....	<input type="text"/>	3		8
Wet Pond (P-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Wet Extended Detention (P-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Multiple Pond System (P-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Pocket Pond (P-5) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Surface Sand Filter (F-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Underground Sand Filter (F-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Perimeter Sand Filter (F-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Organic Filter (F-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Shallow Wetland (W-1) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Extended Detention Wetland (W-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Pond/Wetland System (W-3) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Pocket Wetland (W-4) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>
Wet Swale (O-2) .....	<input type="text"/>	<input type="text"/>		<input type="text"/>



33. Identify the Standard SMPs in Table 1 and, if applicable, the Alternative SMPs in Table 2 that were used to treat the remaining total WQv(=Total WQv Required in 28 - Total RRv Provided in 30).

Also, provide in Table 1 and 2 the total impervious area that contributes runoff to each practice selected.

**Note:** Use Tables 1 and 2 to identify the SMPs used on Redevelopment projects.

33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question 29.

**WQv Provided**  

		0	.	9	4	3
--	--	---	---	---	---	---

**acre-feet**

**Note:** For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - RRv provided by the practice. (See Table 3.5 in Design Manual)

34. Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a). 

		2	.	0	5	7
--	--	---	---	---	---	---

35. Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)?  **Yes**    **No**

**If Yes, go to question 36.**

**If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.**

36. Provide the total Channel Protection Storage Volume (CPv) required and provided or select waiver (36a), if applicable.

**CPv Required**  

		2	.	0	5	7
--	--	---	---	---	---	---

**acre-feet**

**CPv Provided**  

		2	.	0	5	7
--	--	---	---	---	---	---

**acre-feet**

36a. The need to provide channel protection has been waived because:

- Site discharges directly to tidal waters or a fifth order or larger stream.
- Reduction of the total CPv is achieved on site through runoff reduction techniques or infiltration systems.

37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (37a), if applicable.

**Total Overbank Flood Control Criteria (Qp)**

**Pre-Development**  

	7	6	.	7	5	
--	---	---	---	---	---	--

**CFS**

**Post-development**  

	7	4	.	0	0	
--	---	---	---	---	---	--

**CFS**

**Total Extreme Flood Control Criteria (Qf)**

**Pre-Development**  

1	7	7	.	1	0	
---	---	---	---	---	---	--

**CFS**

**Post-development**  

1	6	9	.	4	1	
---	---	---	---	---	---	--

**CFS**









Department of  
Environmental  
Conservation

NYS Department of Environmental Conservation  
Division of Water  
625 Broadway, 4th Floor  
Albany, New York 12233-3505

**MS4 Stormwater Pollution Prevention Plan (SWPPP) Acceptance  
Form**

for

**Construction Activities Seeking Authorization Under SPDES General Permit**

\*(NOTE: Attach Completed Form to Notice Of Intent and Submit to Address Above)

**I. Project Owner/Operator Information**

1. Owner/Operator Name: East Point Energy, LLC

2. Contact Person: Scott Connuck

3. Street Address: 310 4th Street NE, 3rd Floor

4. City/State/Zip: Charlottesville, VA 22902

**II. Project Site Information**

5. Project/Site Name: Union Energy Center

6. Street Address: 24 Miller Road

7. City/State/Zip: Mahopac, NY 10541

**III. Stormwater Pollution Prevention Plan (SWPPP) Review and Acceptance Information**

8. SWPPP Reviewed by:

9. Title/Position:

10. Date Final SWPPP Reviewed and Accepted:

**IV. Regulated MS4 Information**

11. Name of MS4:

12. MS4 SPDES Permit Identification Number: NYR20A \_\_\_\_\_

13. Contact Person:

14. Street Address:

15. City/State/Zip:

16. Telephone Number:

**MS4 SWPPP Acceptance Form - continued**

**V. Certification Statement - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative**

I hereby certify that the final Stormwater Pollution Prevention Plan (SWPPP) for the construction project identified in question 5 has been reviewed and meets the substantive requirements in the SPDES General Permit For Stormwater Discharges from Municipal Separate Storm Sewer Systems (MS4s). Note: The MS4, through the acceptance of the SWPPP, assumes no responsibility for the accuracy and adequacy of the design included in the SWPPP. In addition, review and acceptance of the SWPPP by the MS4 does not relieve the owner/operator or their SWPPP preparer of responsibility or liability for errors or omissions in the plan.

Printed Name:

Title/Position:

Signature:

Date:

**VI. Additional Information**

## **APPENDIX H**

### **Draft Stormwater Maintenance and Access Agreement**



**Town of Carmel**  
**Stormwater Facility Maintenance Agreement**

Whereas, the Town of Carmel, County of Putnam, State of New York ("Municipality") and East Point Energy, LLC ("facility owner") want to enter into an agreement to provide for the long term maintenance and continuation of stormwater control measures approved by the Municipality for the below named project, and

Whereas, the Municipality and the facility owner desire that the stormwater control measures be built in accordance with the approved project plans and thereafter be maintained, cleaned, repaired, replaced and continued in perpetuity in order to ensure optimum performance of the components.

Therefore, the Municipality and the facility owner agree as follows:

1. This agreement inures to the benefit of the Municipality and binds the facility owner, its successors and assigns, to the maintenance provisions depicted in the approved project plans which are attached as Schedule A of this agreement.
2. The facility owner shall maintain, clean, repair, replace and continue the stormwater control measures depicted in Schedule A as necessary to ensure optimum performance of the measures to design specifications. The stormwater control measures shall include, but shall not be limited to, the following: swales, drainage structures, pipes, culverts, and stormwater management practices including pretreatment basins, infiltration basins and ponds.
3. The facility owner shall be responsible for all expenses related to the maintenance of the stormwater control measures and shall establish a means for the collection and distribution of expenses among parties for any commonly owned facilities.
4. The facility owner shall provide for the periodic inspection of the stormwater control measures, not less than once in every five-year period, to determine the condition and integrity of the measures. Such inspection shall be performed by a professional engineer licensed by the State of New York. The inspecting engineer shall prepare and submit to the Municipality, within 30 days of the inspection, a written report of the findings, including recommendations for those actions necessary for the continuation of the stormwater control measures.
5. The facility owner shall not authorize, undertake or permit alteration, abandonment, modification or discontinuation of the stormwater control measures except in accordance with written approval of the Municipality.

6. The facility owner shall undertake necessary repairs and replacement of the stormwater control measures at the direction of the Municipality or in accordance with the recommendations of the inspecting engineer.
7. The facility owner shall provide to the Municipality, within 30 days of the date of this agreement, a security for the maintenance and continuation of the stormwater control measures in the form of a bond, letter of credit or escrow account in the amount not to exceed \$\_\_\_\_\_ (*if applicable*).
8. This agreement shall be recorded in the Office of the County Clerk, County of Putnam together with the deed for the subject premises.
9. In the event that the Municipality determines that the facility owner has failed to construct or maintain the stormwater control measures in accordance with the project plan or has failed to undertake corrective action specified by the Municipality or by the inspecting engineer, the Municipality is authorized to undertake such steps as reasonably necessary for the preservation, continuation or maintenance of the stormwater control measures and to affix the expenses thereof as a lien against the property.
10. Nothing within this agreement shall be construed to impose any affirmative obligation or covenant of performance on the Municipality.
11. This agreement is effective \_\_\_\_\_.

Facility Owner: \_\_\_\_\_.

Owner's Representative: \_\_\_\_\_.

Representative Signature: \_\_\_\_\_.

**ACKNOWLEDGEMENTS**

STATE OF NEW YORK                    )  
   ) ss.:  
 TOWN OF \_\_\_\_\_ )

On this \_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, before me personally came \_\_\_\_\_ to me known and known to me to be the person described in and who executed the foregoing instrument and he acknowledged to me that he executed the same.


\_\_\_\_\_  
 Notary Public





## **FIGURES**





PROJECT: UNION ENERGY CENTER

MILLER ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK

DRAWING: LOCATION MAP

PREPARED BY:

**INSITE**  
ENGINEERING, SURVEYING &  
LANDSCAPE ARCHITECTURE, P.C.  
3 Garrett Place • Carmel, New York 10512  
Phone (845) 225-9690 • Fax (845) 225-9717  
www.insite-eng.com

**SITE**  
PUTNAM COUNTY  
WESTCHESTER COUNTY

DATE: 2-16-24

SCALE: 1"=1000'

PROJECT NO.: 21120.100

FIGURE: 1



**LEGEND**


	PRE 1	SUBCATCHMENT
	SF	TIME OF CONCENTRATION SHEET FLOW
	SCF	TIME OF CONCENTRATION SHALLOW CONCENTRATED FLOW
	CF	TIME OF CONCENTRATION CHANNEL FLOW
	DESIGN POINT	DESIGN POINT
		SUBCATCHMENT CONTRIBUTING AREA

**SOILS LEGEND**


SOILS	DESCRIPTION	HYDROLOGICAL GROUP
Fi	Fluvisols-Udfluvists complex, frequently flooded	A/D
NcA	Natchaug muck, 0% to 2% slopes	B/D
PhB	Paxton fine sandy loam, 2% to 8% slopes	C
PhC	Paxton fine sandy loam, 8% to 15% slopes	C
PhD	Paxton fine sandy loam, 15% to 25% slopes	C
RdA	Ridgebury loam, 0% to 3% slopes	D
RdB	Ridgebury loam, 3% to 8% slopes	D
RdC	Ridgebury loam, 2% to 8% slopes, very stony	D
Sh	Sun loam	C/D
Uo	Udorthents, wet substratum	A/D
WdB	Woodbridge loam, 3% to 8% slopes	C/D

NRCS Soil Boundary Line

ALLOCATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.




NO.	DATE	REVISION	BY
 <b>INSITE</b> ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.			
PROJECT: UNION ENERGY CENTER MILLER ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK			
DRAWING: PRE-DEVELOPMENT DRAINAGE MAP			
PROJECT NUMBER	21120.100	PROJECT MANAGER	R.D.W.
DATE	2-16-24	DRAWN BY	J.B.
SCALE	1" = 100'	CHECKED BY	E.J.P.
			DRAWING NO. <b>FIG-2</b>



LEGEND	
	SUBCATCHMENT
	STORMWATER MANAGEMENT PRACTICE
	TIME OF CONCENTRATION SHEET FLOW
	TIME OF CONCENTRATION SHALLOW CONCENTRATED FLOW
	TIME OF CONCENTRATION PIPE FLOW
	TIME OF CONCENTRATION CHANNEL FLOW
	DESIGN POINT
	SUBCATCHMENT CONTRIBUTING AREA
	STORMWATER MANAGEMENT / GREEN INFRASTRUCTURE PRACTICE AREA

SOILS LEGEND		
SOILS	DESCRIPTION	HYDROLOGICAL GROUP
F1	Fluvents—Ustifluents complex, frequently flooded	A/D
NcA	Natchaug muck, 0% to 2% slopes	B/D
PnB	Paston fine sandy loam, 2% to 8% slopes	C
PnC	Paston fine sandy loam, 8% to 15% slopes	C
PnD	Paston fine sandy loam, 15% to 25% slopes	C
RdB	Ridgebury loam, 0% to 3% slopes	D
RdB	Ridgebury loam, 3% to 8% slopes	D
RdB	Ridgebury loam, 2% to 8% slopes, very stony	D
Sh	Sun loam	C/D
Uo	Ustorthents, wet substratum	A/D
WdB	Woodbridge loam, 3% to 8% slopes	C/D


NRCS Soil Boundary Line



NO.	DATE	REVISION	BY
PROJECT: UNION ENERGY CENTER WELLS ROAD, TOWN OF CARROLL, PUTNAM COUNTY NEW YORK			
DRAWING: POST-DEVELOPMENT DRAINAGE MAP			
PROJECT NUMBER	21120.100	PROJECT MANAGER	R.D.W.
DATE	2-16-24	DRAWN BY	J.B.
SCALE	1" = 100'	CHECKED BY	E.J.P.
			FIG-3


ALLEGATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE SANGHVI LAW.





**LEGEND**

	EXISTING PROPERTY LINE
	EXISTING EASEMENT
	EXISTING STONE WALL
	EXISTING UTILITY POLE w/ w/ & overhead wire
	EXISTING WATERCOURSE
	EXISTING WETLAND
	EXISTING WETLAND FLAG
	EXISTING WETLAND ADJACENT AREA
	EXISTING MEDIAN
	EXISTING 1' CONTOUR
	EXISTING 2' CONTOUR



4	2-16-24	REVISED FOR NYDEC SUBMISSION	JMJ
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMITTED TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING &  
LANDSCAPE ARCHITECTURE, P.C.


3 Carlet Place  
Carmel, NY 12012  
(845) 225-8997  
(845) 225-8997  
www.insite-arg.com

PROJECT:		UNION ENERGY CENTER	
DRAWING:		EXISTING CONDITIONS PLAN	
PROJECT NUMBER	2120-100	PROJECT MANAGER	J.J.C.
DATE	8-30-23	DRAWN	J.L.B.
NO.	DATE	CHECKED	BY
			A.D.T.

ALL INFORMATION ON THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.



EX-1  
2  
13



**LEGEND**

- EXISTING PROPERTY LINE
- - - EXISTING EASEMENT
- ⊞ EXISTING STONE WALL
- ⊞ EXISTING UTILITY POLE w/ guy & overhead wires
- - - EXISTING WATERCOURSE
- - - EXISTING WETLAND
- - - EXISTING WETLAND FLAG
- - - EXISTING 100 YR. FLOODPLAIN BOUNDARY
- - - EXISTING TREELINE
- ⊞ PROPOSED OVERHEAD WIRES
- ⊞ PROPOSED SINGLE POLE SIGN
- ⊞ PROPOSED DOUBLE POLE SIGN
- ⊞ PROPOSED DOUBLE SIDA SIGN
- ⊞ PROPOSED BOLLARD
- ⊞ PROPOSED GUARD RAIL
- ⊞ PROPOSED POLE MOUNTED LIGHT
- ⊞ PROPOSED POST MOUNTED LIGHT
- ⊞ PROPOSED LOADING SPACE
- ⊞ PROPOSED LANDSCAPING

**SCHEMATIC PLANT LIST**

QTY	BOTANICAL/COMMON NAME	SIZE	ROOT
<b>EMERGENCY TREES</b>			
24	Juniperus virginiana / Eastern Redcedar	6"-10" HT.	B&B
10	Picea glauca / White Spruce	6"-10" HT.	B&B
10	Thuja occidentalis / Arborvitae	6"-8" HT.	B&B
<b>SHRUBS</b>			
10	Juniperus chinensis "Sea Green" / Sea Green Juniper	#3 CONT./8" O.C.	
10	Viburnum dentatum / Lacinellated Viburnum	#3 CONT./8" O.C.	
<b>PERENNIALS/GROUND COVERS</b>			
10	Asphodelus aestivus / Columbine	#1 CONT./18" O.C.	
10	Colchicum autumnale / Pulsine Colchicum	#1 CONT./18" O.C.	
10	Mertensia virginica / Virginia Bluebells	#1 CONT./18" O.C.	

**WETLAND MITIGATION PLANT LIST**

QTY	BOTANICAL/COMMON NAME	SIZE	SPACING
35	Aster multiflorus / Shadbolt	2"-3"	10' O.C.
35	Conium maculatum / Grey Dogwood	2"-3"	10' O.C.
35	Liatris scariosa / Shadbolt	2"-3"	10' O.C.
35	Sambucus racemosa / Elderberry	2"-3"	10' O.C.
35	Viburnum dentatum / Lacinellated Viburnum	2"-3"	10' O.C.
35	Viburnum lentago / Honeysuckle	2"-3"	10' O.C.

- NOTES:**
- All plantings to be verified by the Town of Carmel Natural Inspector.
  - All plantings shall be installed per size of the Town of Carmel Tree Code.
  - Wetland mitigation areas and plant lists provided by W&E, Inc.

4	2-16-24	REVISED FOR NYDEP SUBMISSION	JMM
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMISSION TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY


**INSITE**  
ENGINEERING, SURVEYING &  
LANDSCAPE ARCHITECTURE, P.C.

3 Carroll Place  
Carmel, NY 12012  
(845) 225-8997  
(845) 225-8997 fax  
www.insite-arg.com



PROJECT: **UNION ENERGY CENTER**  
MILLER ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK

DRAWING: **LAYOUT & LANDSCAPE PLAN**

PROJECT NUMBER: 21120.100 PROJECT MANAGER: J.J.C. DRAWING NO.: SHEET  
DATE: 8-30-23 DRAWN BY: J.L.B. 3  
SCALE: 1"=50' CHECKED BY: A.D.T. 13



ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 1009 OF ARTICLE 146 OF THE EDUCATION LAW.



**SCHEMATIC PLANT LIST**

KEY	BOTANICAL/Common NAME	SIZE	ROOT
<b>EVERGREEN TREES</b>			
JV	Japanese Yew / Eastern Redcedar	8'-10' HT.	B&B
PG	Pine glauca / White Spruce	8'-10' HT.	B&B
TD	Red-tipped Topiary cypripedium / Arborvitae	6'-8' HT.	B&B
<b>SHRUBS</b>			
VC	Japanese viburnum "Sea Green" / Sea Green Juniper	#3 CONT./18" G.C.	
UD	Viburnum dentatum / Leatherleaf Viburnum	#1 CONT./18" G.C.	
<b>PERENNIALS/GROUND COVERS</b>			
AC	Aquilegia canadensis / Columbine	#1 CONT./18" G.C.	
EP	Echinacea purpurea / Purple Coneflower	#1 CONT./18" G.C.	
MY	Mercurialis virginica / Virginia Bluebell	#1 CONT./18" G.C.	


4	2-16-24	REVISED FOR NYSDEC SUBMISSION	JMM
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMISSION TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING &  
LANDSCAPE ARCHITECTURE, P.C.

3 Carroll Place  
Carmel, NY 12016  
(518) 225-8997  
(518) 225-8997 fax  
www.insite-arg.com


PROJECT:  
**UNION ENERGY CENTER**  
SILVER GATE ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK

DRAWING:  
**LAYOUT & LANDSCAPE PLAN**



PROJECT NUMBER	21120-100	PROJECT MANAGER	J.J.C.	DRAWING NO.	SHEET
DATE	8-30-23	DRAWN BY	J.B.	SP-1.2	4
SCALE	1"=50'	CHECKED BY	A.D.T.		13

ALLOCATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.



**LEGEND**

	EXISTING PROPERTY LINE
	EXISTING EASEMENT
	EXISTING STONE WALL
	EXISTING UTILITY POLE/ W/ a control wire
	EXISTING MANHOLE
	EXISTING WETLAND
	EXISTING WETLAND FLAG
	EXISTING WETLAND BUFFER
	EXISTING 10' CONTOUR
	EXISTING 2' CONTOUR
	PROPOSED 10' CONTOUR
	PROPOSED 2' CONTOUR
	PROPOSED SPOT ELEVATION
	PROPOSED CURB/GATE/WHEEL
	PROPOSED DRAINAGE MANHOLE
	PROPOSED DRAINAGE INLET
	PROPOSED OUTLET STRUCTURE
	PROPOSED END SECTION
	PROPOSED GRASS SWALE
	PITCH TO DRAIN
	PROPOSED LEVEL SPREADER

**UTILITIES NOTES:**  
 1. All utilities except for overhead wires associated with the substations and Battery Energy Storage Systems (BESS) will be buried.

4	2-16-24	REVISED FOR NYDEC SUBMISSION	JMM
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMISSION TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY


**INSITE**  
 ENGINEERING, SURVEYING &  
 LANDSCAPE ARCHITECTURE, P.C.

3 Carroll Place  
 Carmel, NY 12512  
 (845) 225-8997  
 www.insite-arg.com


PROJECT: UNION ENERGY CENTER  
 MILLER ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK  
 DRAWING: GRADING & UTILITIES PLAN



PROJECT NUMBER	21120.100	PROJECT MANAGER	J.C.C.	DRAWING NO.	SHEET
DATE	8-30-23	DRAWN BY	J.L.B.	SP-2.1	5
SCALE	1"=50'	CHECKED BY	A.D.T.		13



ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.



**LEGEND**


	EXISTING PROPERTY LINE
	EXISTING EASEMENT
	EXISTING STONE WALL
	EXISTING UTILITY POLES per & without notes
	EXISTING WATERCOURSE
	EXISTING WETLAND FLAG
	EXISTING WETLAND BUFFER
	EXISTING 10' CONTOUR
	EXISTING 2' CONTOUR
	PROPOSED 10' CONTOUR
	PROPOSED 2' CONTOUR
	PROPOSED SPOT ELEVATION
	PROPOSED OVERHEAD WIRES
	PROPOSED DRAINAGE MANHOLE
	PROPOSED DRAINAGE INLET
	PROPOSED OUTLET STRUCTURE
	PROPOSED END SECTION
	PROPOSED GRASS SWALE
	PITCH TO DRAIN
	PROPOSED LEVEL SPREADER

4	2-16-24	REVISED FOR NYSEC SUBMISSION	JMM
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED FOR PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMISSION TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

3 Carroll Place  
Carmel, NY 12016  
(845) 225-8997  
(845) 225-8997 fax  
www.insite-arg.com


PROJECT:			
UNION ENERGY CENTER			
WELLS ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK			
DRAWING:			
GRADING & UTILITIES PLAN			
PROJECT NUMBER	21120.100	PROJECT MANAGER	J.J.C.
DATE	8-30-23	DRAWN BY	J.L.B.
NO.	DATE	CHECKED BY	A.D.T.



ALLOCATION OF THIS DOCUMENT, UNLESS UNDER THE Aegis OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.



SHEET  
SP-2.2  
6  
13



**LEGEND**

	EXISTING PROPERTY LINE
	EXISTING EASEMENT
	EXISTING STONE WALL
	EXISTING UTILITY POLE (per 2' overhead wires)
	EXISTING WATERCOURSE
	EXISTING WETLAND
	EXISTING WETLAND FLAG
	EXISTING WETLAND BUFFER
	EXISTING 10' CONTOUR
	EXISTING 2' CONTOUR
	PROPOSED SILT FENCE
	PROPOSED DOUBLE SILT FENCE
	PROPOSED CONSTRUCTION FENCE
	PROPOSED LIMITS OF DISTURBANCE
	PROPOSED STONE CHECK DAM
	PROPOSED TEMPORARY DIVERSION SWALE
	PROPOSED TEMPORARY SOIL STOCKPILE
	PROPOSED STABILIZED CONSTRUCTION ENTRANCE
	PROPOSED EROSION CONTROL BLANKET
	PROPOSED DRAINAGE STRUCTURE W/ INLET PROTECTION
	PROPOSED PHASING LINE

4	2-16-24	REVISED FOR NYDEC SUBMISSION	JMM
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMISSION TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING &  
LANDSCAPE ARCHITECTURE, P.C.

PROJECT: UNION ENERGY CENTER  
MILLER ROAD, TOWN OF GARDEL, PUTNAM COUNTY NEW YORK

DRAWING: EROSION & SEDIMENT CONTROL PLAN

PROJECT NUMBER: 21120.100 PROJECT MANAGER: J.J.C. DRAWING NO.: SHEET  
DATE: 8-30-23 DRAWN BY: I.B. SP-3.1 7  
SCALE: 1"=50' CHECKED BY: A.D.T. 13

ALTERNATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW



**LEGEND**

- EXISTING PROPERTY LINE
- - - EXISTING EASEMENT
- EXISTING STONE WALL
- EXISTING UTILITY POLE/PIPE (per 8' overhead wires)
- EXISTING WETLAND
- EXISTING WETLAND BUFFER
- EXISTING 10' CONTOUR
- EXISTING 2' CONTOUR
- PROPOSED SALT FENCE
- PROPOSED DOUBLE SALT FENCE
- PROPOSED CONSTRUCTION FENCE
- PROPOSED LIMITS OF DISTURBANCE
- PROPOSED STONE CHECK DAM
- PROPOSED TEMPORARY OVERFLOW DIBBLE
- PROPOSED TEMPORARY SOIL STOCKPILE
- PROPOSED STABILIZED CONSTRUCTION ENTRANCE
- PROPOSED EROSION CONTROL BLANKET
- PROPOSED DRAINAGE STRUCTURE W/ INLET PROTECTION
- PROPOSED PHASING LINE


4	2-16-24	REVISED FOR NYDEC SUBMISSION	JMU
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KJR
1	10-30-23	RESUBMITTED TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING &  
LANDSCAPE ARCHITECTURE, P.C.

3 Corbett Place  
Carmel, NY 12016  
(518) 225-8997  
(518) 225-8997 fax  
www.insite-arg.com


PROJECT: UNION ENERGY CENTER  
SILVER GATE ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK

DRAWING: EROSION & SEDIMENT CONTROL PLAN




PROJECT NUMBER	2120.100	PROJECT MANAGER	J.J.C.	DRAWING NO.	SHEET
DATE	8-30-23	DRAWN BY	J.B.	SP-3.2	8
SCALE	1"=50'	CHECKED BY	A.D.T.		13

ALLOCATION OF THIS DOCUMENT, UNLESS UNDER THE AEGIS OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.



**LEGEND**

- EXISTING PROPERTY LINE
- - - EXISTING EASEMENT
- ⊘ EXISTING STONE WALL
- ⊘ EXISTING UTILITY POLE w/ guy & overhead wires
- ⊘ EXISTING WATERCOURSE
- ⊘ EXISTING WETLAND
- ⊘ EXISTING WETLAND FLAG
- ⊘ EXISTING WETLAND ADJACENT AREA



**E-ONE HP95 MID MOUNT TURNING TEMPLATE**  
SCALE: 1" = 50'


ALLOCATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.

3	2-16-24	REVISED FOR NYCDEP SUBMISSION	JMM
2	1-29-24	GENERAL REVISION	TMM
1	12-11-23	REVISED PER PLANNING BOARD COMMENTS	KJK
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

3 Garrett Place  
Carmel, NY 12512  
(518) 225-8997  
(518) 225-8997 fax  
www.insite-arg.com



PROJECT: <b>UNION ENERGY CENTER</b>		
DRAWING: <b>VEHICLE MANEUVERING PLAN</b>		
PROJECT NUMBER 21120.100	PROJECT MANAGER J.C.C.	DRAWING NO. SP-4.1
DATE 10-30-23	DRAWN BY K.J.K.	SHEET 9
SCALE 1"=100'	CHECKED BY A.D.T.	13



LUMINAIRE SCHEDULE						
Sym	Qty	City Catalog Number	Description	Lamp Mounting Height	Notes	
4	34	RSX2 LED P1 30X R3 EGY	LITHONIX LIGHTING LED POLE MOUNTED LIGHT TYPE 3M DISTRIBUTION	LED	20'-0"	721



- LIGHTING NOTES:**
- All lighting shall be as noted on the plan or approved equit.
  - Style and finish of all luminaires to be selected by owner.
  - Proposed lights will run on motion sensors after hours for security only.
  - Type, location, and quantity of all proposed lighting shall prevent the spill-over of light onto all adjacent residential properties.
  - All light fixtures to be full cutoff to comply with state city guidelines.
- LIGHT CONTOUR LEGEND**
- 0.10 Foot Candles
  - 1.00 Foot Candles
- \* Photometric calculations shown on plan are in foot candles.



ALLOCATION OF THE DOCUMENT: UNDER THE PROVISIONS OF A LICENSED PROFESSIONAL ENGINEER, A PORTION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW


3	2-16-24	REVISED FOR NYC DEP SUBMISSION	JMM
2	1-29-24	GENERAL REVISION	TKM
1	12-4-23	REVISED PER PLANNING BOARD COMMENTS	KJK
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

300 West 10th Street  
New York, NY 10011  
(212) 224-9999  
www.insite-arg.com


PROJECT: **UNION ENERGY CENTER**  
UNION SQUARE, 100 WALL STREET, NEW YORK, NY

DRAWING: **LIGHTING PLAN**




PROJECT NUMBER	21120-100	PROJECT MANAGER	J.J.C.	DRAWING NO.		SHEET	
DATE	10-30-23	DRAWN BY	K.J.K.	CHECKED BY			
SCALE	1"=60'		A.D.T.				

SP-4.2 10 13




- NOTES:**
1. STRIP VEGETATION AND ORGANIC SOIL FROM WALL AREA.
  2. REMOVE CUT AND EXCAVATE SLOPES.
  3. DO NOT OVER EXCAVATE UNLESS DIRECTED BY SITE ENGINEER TO REMOVE UNSUBSIDIARY SOIL.
  4. SITE ENGINEER SHALL VERIFY FOUNDATION SOILS AS BEING COMPATIBLE FOR THE DESIGN STRENGTHS AND PARAMETERS.
  5. LEVELING PAD SHALL CONSIST OF COMPACTED COARSE SAND OR CRUSHED CORNEL #2 TRUCK MIX.
  6. CONTRACTOR MAY OPT FOR A LEAN CONCRETE PAD. CONCRETE PAD SHALL BE UNREINFORCED, 1" THICK MINIMUM.
  7. MINIMUM EMBEDMENT OF WALL BELOW FINISH GRADE SHALL BE 6".
  8. FOR UNITS TO BE EMBEDDED, COMPACT FILL IN FRONT OF UNITS AT THE SAME TIME FULL BEHIND UNITS IS COMPACTED.
  9. DRAINAGE AGGREGATE SHALL BE INSTALLED DIRECTLY BEHIND THE WALL WITHIN 12" OF THE TOP OF THE WALL. DRAINAGE AGGREGATE SHALL NOT EXTEND BELOW FINISH GRADE IN FRONT OF WALL.
  10. COMPLETION SHALL BE TO SORT OF MINIMUM STANDARD PROCTOR DENSITY (ASTM D-698).
  11. COMPACTION TESTS SHALL BE TAKEN AS THE WALL IS INSTALLED. THE MINIMUM NUMBER OF TESTS SHALL BE DETERMINED BY THE SITE SOILS ENGINEER.
  12. COMPACTION WITHIN 3 FT. OF WALL SHALL BE LIMITED TO HAND OPERATED EQUIPMENT.
  13. CONTRACTOR SHALL DIRECT SURFACE RUNOFF TO AVOID DAMAGING WALL WHILE UNDER CONSTRUCTION.
  14. ANY SURFACE DRAINAGE FEATURES, FRESH DRAINING PAVEMENT, OR TURF SHALL BE INSTALLED IMMEDIATELY AFTER WALL IS COMPLETED.
  15. FOLLOW APPLICABLE PROVISIONS OF THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND WRITTEN SPECIFICATIONS.


RETAINING WALL DETAIL (N.T.S.)




CHAIN LINK FENCE DETAIL (N.T.S.)




EVERGREEN TREE PLANTING DETAIL (N.T.S.)




TREE PLANTING DETAIL (N.T.S.)




SHRUB PLANTING DETAIL (N.T.S.)




GUIDERAIL DETAIL (N.T.S.)



PERENNIAL / ORNAMENTAL GRASS PLANTING DETAIL (N.T.S.)



GRAVEL PAVEMENT DETAIL FOR ENCLOSURES (N.T.S.)



GRAVEL PAVEMENT DETAIL FOR DRIVEWAYS (N.T.S.)

**GENERAL PLANTING NOTES:**

1. All proposed planting beds to receive a 12" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
2. Any new site added will be amended as required by results of soil testing and placed using a method that will not cause compaction.
3. No fertilizer shall be added in stormwater basin plantings. Nutrient requirements to be met by incorporation of acceptable organic matter.
4. All plant material to be nursery grown.
5. Plants shall conform with ANSI 2001 American Standard for Nursery Stock in all uses including dimensions.
6. Plant material shall be taken from healthy nursery stock.
7. All plants shall be grown under climate conditions similar to those in the locality of the project.
8. Plants shall be oriented in all locations designed on the plan or as stated in the field by the Landscape Architect.
9. The location and layout of landscape plants shown on the site plan shall take precedence in any discrepancies between the quantities of plants shown on the plans and the quantity of plants in the Plant List.
10. Plants to be 2" type of balled and burlapped (or as specified) new white wrapping material of all new pits or over entire planting bed. Do not place mulch within 2" of tree or shrub trunk.
11. All landscape plantings shall be established in a healthy condition at all times. Any dead or diseased plants shall be immediately replaced "in kind" by the contractor during warranty period or project close.

**GENERAL SITE SEEDING NOTES:**

1. All proposed seeded areas to receive 4" min. depth of topsoil. Soil amendments and fertilizer application rates shall be determined based on specific testing of topsoil material.
2. For temporary stabilization, apply annual ryegrass (Lolium perenne sp.) at 30 lbs./acre.
3. Upon final grading and placement of topsoil and any required soil amendments, areas to receive permanent vegetation cover in conjunction with sods shall be as follows:
  - select seed mixture per drawings and seeding rates
  - fertilizer applied at the manufacturer's recommended rate using Leaso
  - 10-10-10 (no phosphorus) fertilizer or equivalent
  - mulch - well hay or straw or other straw applied at a rate of 90 lbs./1000 sq. ft. or 2 tons/acre to be applied and anchored according to New York State Standards and Specifications for Gravel and Subbase Materials, Article 200.00A
  - If the season prevents the establishment of a permanent vegetation cover, the disturbed areas will be mulched with straw or equivalent.
4. Seed Mix #1 for areas as shown on the drawings, including tops of berms, backfills of embankments of stormwater basins, & any area to be seeded with the NYSDOT Bedding Adjustment Area, at a rate of 30 lbs. per acre. 20% annual ryegrass (Lolium perenne sp.), and 70% New England Conservatory/Walpole Mix from New England Wetland Plants, Inc. of Amherst, MA.
5. Seed Mix #2 for areas as shown on the drawings in stormwater basins with no standing water at a rate of 18 lbs. per acre: Grasses: Coastal/Prairie Mix from Dominion Botanic and Moist Sites from New England Wetland Plants, Inc. of Amherst, MA.
6. Seed Mix #3 for all other disturbed areas not specified as seed mix #1 or #2. Primary Seeding Rate: Fescue 20% Annual Ryegrass 20%

7. Seed mixes to be planted between March 21 and May 20, or between August 15 and October 15 or as directed by project representative.

8. Mow: Soft hay or small grain straw applied at a rate of 90 lbs./1000 sq. ft. or 2 tons/acre, to be applied and anchored according to New York Standards and Specifications For Gravel and Subbase Materials, latest edition.

9. Grass seed mix may be applied by either mechanical or hand-seeding methods. Seeding shall be performed in accordance with the current edition of the NYSDOT Standard Specifications for Road and Bridge Construction, Section 810-3.2. Method No. 1. Hydroseeding shall be performed using materials and methods as approved by the site engineer.

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE SUPERVISION OF A LICENSED PROFESSIONAL ENGINEER, IS A VIOLATION OF SECTION 2009 OF ARTICLE 146 OF THE EDUCATION LAW.

4	2-16-24	REVISED FOR NYSDOT SUBMISSION	JMU
3	1-29-24	GENERAL REVISION	TSM
2	12-6-23	REVISED PER PLANNING BOARD COMMENTS	KAR
1	10-30-23	RESUBMISSION TO PLANNING BOARD	MEL
NO.	DATE	REVISION	BY

**INSITE**  
ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

30 Carvet Place  
Carmel, NY 12016  
(518) 225-8997  
(518) 225-8997 fax  
www.insite-ny.com

PROJECT: UNION ENERGY CENTER  
MILLER ROAD, TOWN OF CARMEL, PUTNAM COUNTY NEW YORK

DRAWING: DETAILS & NOTES

PROJECT NUMBER: 21120.100 PROJECT MANAGER: J.J.C. DRAWING NO.: SHEET: D-1 11

DATE: 8-30-23 DRAWN: J.B. BY: A.D.T.

SCALE: AS SHOWN CHECKED BY: A.D.T.







February 19, 2024

Town of Carmel Planning Board  
60 McAlpin Avenue  
Mahopac, New York 10541

RE: DAG Route 6 LLC  
395 US Route 6  
Town of Carmel  
TM# 75.19-1-8 & 75.20-2-5

Dear Chairman Paepre and Members of the Board:

Please find enclosed the following plans and documents in support of an application for site plan approval for the above referenced project:

- Site plan set, revised February 19, 2024.
- Site Profile, by William Bersharat, dated February 19, 2024.

In response to open comments received from Code Enforcement Director, Michael Carnazza, dated January 23, 2024, we offer the following responses:

1. This accurately describes the proposed project, but for clarity the existing building that houses the dog daycare business will remain.
2. This comment is acknowledged.
3. The required side yard variance is acknowledged.

In response to open comments received from Town Engineer Richard Franzetti, PE, dated January 19, 2024, we offer the following responses:

#### General Comments

1. The required referrals are acknowledged. Though the property fronts on US Route 6 on the north side, it also has frontage on Bucks Hollow Road. There are no proposed improvements to the Route 6 driveway and it is anticipated that traffic related to the proposed buildings will gain access from their driveway to Bucks Hollow Road. No highway work permit is anticipated, but the applicant will coordinate with the NYDOT on the proposed NYSDOT drainage improvements on site.
2. The required permitting is acknowledged with the exception of NYSDOT as discussed above.
3. The requirement for SWPPP coverage under GP-0-20-001, for erosion control only, is acknowledged.
4. The requirement for a stormwater maintenance bond is acknowledged.

5. The requirement for a site work performance bond is acknowledged.

#### Detailed Comments

1. Drawing SP-3 has been added to the site plan set, which includes vehicle movements. Sight distances are shown on drawing SP-1. The driveway to Bucks Hollow Road exists and is proposed to remain as the primary access for the proposed project. Sight distances have been added to drawing SP-1.
2. No work is proposed in the Route 6 right of way.
3. Based on discussion with the owner, the onsite population is not anticipated to exceed thresholds requiring a public water supply. As such, the existing on site well will continue to be used, and the new buildings will be supplied with a service line connecting to the existing building. Details of the proposed septic will be provided with a future submission following testing with the PCDOH.
4. A note has been added to the Planting Notes on drawing D-1 that all plantings shall be verified by the Town of Carmel Wetland Inspector.
5. A note has been added to the Planting Notes on drawing D-1 that all plantings shall be installed per the town code.
6. A light spill plan is provided on drawing SP-3.
7. Rim elevations are shown on drawing SP-2. Inverts will be added with a future submission.
8. Hydraulic calculations and pipe sizing will be provided with a future submission.
9. Additional details on the proposed septic system will be provided with a future submission following testing with the PCDOH.
10. A note has been added to drawing SP-2 indicating that all utilities are to be buried.
13. A construction sequence has been added to drawing D-1.
14. Proposed site driveways will meet the code requirements.
15. The site pavement detail has been updated to meet the required specifications.

In response to open comments received from Town Planner, Patrick Cleary, dated January 24, 2024, we offer the following responses:

1. The proposed 10,000 sf building is proposed to house contractors and light manufacturers for storage, office, and general work use. Such contractors could include carpenters, plumbers, electricians, and contractors of other similar fields. Other potential tenants could be artisans/ light manufacturers such as cabinet makers, wood workers and other similar fields. The applicant does not intend to rent to automotive repair tenants. A summary of these uses and their potential number of daily users and vehicle trips is included in a table on drawing SP-1.
2. The required side yard variance is acknowledged.

3. This comment is acknowledged. The applicant has decided that they may provide mezzanine spaces in the 10,000 sf building upon tenant request. Given the possibility of these mezzanines being installed, we have included them in our revised parking summary on drawing SP-1.
4. The primary access for the proposed project will be from Bucks Hollow Road. Vehicle maneuvers are shown on drawing SP-3. The existing fencing through the proposed easement is now shown to be removed. The access easement would only be secondary access to the project location.
5. This comment is acknowledged.
6. A use table has been added to the site plan indicating the proposed user population and anticipated vehicle trips.
7. There is very little grading proposed as part of the project, as the site is relatively flat and already developed to some degree. There are no basements proposed for the two buildings.
8. As the project will create less than one acre of disturbance, there is no requirement to provide stormwater management practices. The applicant is proposing improvements to the existing drainage system that runs through the site to mitigate occasional flooding issues at the southern end of the property.
9. As discussed above, water service lines are shown on drawing SP-2. Based on discussion with the owner, the onsite population is not anticipated to exceed thresholds requiring a public water supply. As such, the existing on site well will continue to be used, and the new buildings will be supplied with a service line connecting to the existing building. Details of the proposed septic will be provided in a future submission following testing with PCDOH.  
  
Currently electrical service is provided to existing dog daycare building by an overhead service wire that connects at the southeast corner of the building. That service will be reconnected to serve the three buildings underground. The applicant will coordinate the connections with the utility. The buildings will be heated and cooled by a heat pump system. Currently there is no plan for back up generators.
10. As discussed, the applicant plans to infill the existing hedge at the property line to fill in areas that have died back, to provide a continuous hedge along the trailway frontage.
11. The main driver of the project is the construction of the two new buildings, but an additional benefit will be a significant improvement in the appearance of the south side of the site. As mentioned above, the applicant intends to fill in the existing hedge along the trailway frontage. The enclosed Site Profile is intended to clarify the visual impact of the project. The applicant is open to discussing the building façade.
12. A light spill plan and lighting specifications are provided on drawing SP-3.
13. The proposed lighting will run on photocells during business hours and will run on motion sensors after hours for security purposes.

We respectfully request to be placed on the February 28, 2024, Planning Board agenda for discussion of the project with the Board. Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:


  
Richard D. Williams Jr., PE  
Senior Principal Engineer

RDW/adt

Enclosures

cc: (All via email only) Nick Crecco

Insite File No. 16230.100





CRECCO DAG RT 6  
 SCALE: HORIZ. 1" = 30'  
 VER. 1" = 10'

**RAYEX**  
 DESIGN PLANNING CONSTRUCTION

ROY A. FREDRIKSEN, PE  
 DESIGN • PLANNING • CONSULTING ENGINEERING  
 286 SHEAR HILL RD. • MAHOPAC, NY 10541 • 845-621-4000  
 RAYEXDESIGN@GMAIL.COM

OWNER:	JOB #
DAG ROUTE SIX, LLC	DRN BY:
	CHKD BY:
PROJECT NEW INDUSTRIAL BUILDING TO BE BUILT ON 395 ROUTE 6 IN MAHOPAC, TOWN OF CARMEL NY.	TAX MAP #:
SHEET TITLE: VISION RANGE 1 OF 1 DIAGRAM	
REVISIONS:	DATE: 2/16/2024




**OWNER/APPLICANT:**  
 DAG ROUTE SIX, LLC  
 PO BOX 638  
 MAHOPAC, NY 10541

**SITE DATA:**  
 Zone: C  
 Total Acreage: 4.84 AC ±  
 Top Map No.: 7519-1-B  
 75-00-2-3

**GENERAL NOTES:**


- Boundary and topographic info shown hereon are taken from a survey entitled, "Topographic Survey of Property," prepared by Link Land Surveyors, P.C., dated January 2, 2013.
- The approximate locations of the pool displays and temporary trailer are taken from aerial orthorectified.




- Richard Sturjansson
- Link Land
- John L. Lemmas Revocable Trust
- F.Y.B. Properties, LLC
- William De Goopt
- 129 Buckshollow LLC
- Verizon New York Inc
- Verizon New York Inc
- Hallam American Club Inc
- J.P. Holding Corp
- John Carpin
- Richard & Bridget Carvone
- George Salomon
- Richard & Bridget Carvone
- John Battaglia
- Moranda Revocable Trust
- Starke Property Mgmt LLC
- Link Realty LLC
- Greg-Lee Realty LLC
- 373 US 6 LLC
- J.C. Realty Corp
- 381 Rt. 6 Holdings Corp.
- Albert Apple
- DAG Route Six, LLC
- DAG Route Six, LLC
- Conwell Properties Inc
- Willis Properties Inc
- Nicole Stern
- Robbie Cooper
- Fisher Thomas Inc
- Liam Borke
- Acary Realty Corp.
- Pure Real Estate Inc
- Scott Nygard
- Scott Nygard
- Thomas Simone
- Adam Walker
- Behuniak Filip
- Blina Family Inv Trust #1
- A Veschi Lane S LLC
- Anthony Scuderi
- Thomas Simone
- Louise Branson
- John L. Lemmas Revocable Trust
- John L. Lemmas Revocable Trust
- Richard Sturjansson
- Link Land
- John L. Lemmas Revocable Trust
- William De Goopt
- 129 Buckshollow LLC
- Hallam American Club Inc
- Hallam American Club Inc
- John Carpin
- Moranda Revocable Trust
- Shurgard Storage Centers, Inc
- Starke Property Mgmt LLC
- Link Realty LLC
- Greg-Lee Realty LLC
- 373 US 6 LLC
- J.C. Realty Corp
- 381 Rt. 6 Holdings Corp.
- Albert Apple
- DAG Route Six, LLC
- DAG Route Six, LLC
- Conwell Properties Inc
- Willis Properties Inc
- Nicole Stern
- Robbie Cooper
- Fisher Thomas Inc
- Liam Borke
- Acary Realty Corp.
- Pure Real Estate Inc
- Scott Nygard
- Scott Nygard
- Thomas Simone
- Adam Walker
- Behuniak Filip
- Blina Family Inv Trust #1
- Louise Branson
- John L. Lemmas Revocable Trust
- William Stein

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.

1	2-19-24	REVISED PER TOWN COMMENTS	KJK
NO.	DATE	REVISION	BY
<b>PROJECT:</b> CRECCO DAG RT 6			
385 US ROUTE 6, TOWN OF CAMEL, PUTNAM COUNTY, NY			
<b>DRAWING:</b> EXISTING CONDITIONS AND REMOVALS PLAN			
PROJECT NUMBER	16230.100	PROJECT MANAGER	R.D.W.
DATE	1-17-24	DRAWN BY	K.J.K.
SCALE	1" = 30'	CHECKED BY	A.D.T.
			DRAWING NO. SHEET <b>EX-1</b> 1 5





**ZONE REQUIREMENTS TOWN OF CARMEL COMMERCIAL DISTRICT**

	REQUIRED / EXISTING	EXISTING	PROPOSED
Minimum Lot Area:	40,000 s.f.	4.8 AC ± (210,171 s.f. ±)	4.8 AC ± (85,973 s.f. ±)
Minimum Lot Width:	200'	417' ±	417' ±
Minimum Lot Depth:	200'	511' ±	451' ±
Minimum Front Yard:	40'	103.5'	45.1'
Minimum Side Yard:	25'	8.9' ±	7' ±
Minimum Rear Yard:	30'	N/A	N/A
Maximum Permitted Height of Buildings:	35'	< 35'	< 35'
Minimum Permitted Floor Area of Buildings:	5,000 s.f.	15,110 s.f. ±	30,540 s.f. ±
Maximum Permitted Coverage of Lot by Buildings:	30%	7.2%	12.2%

\* Variance required.

**PARKING SUMMARY**

Service Establishment Use  
 12,300 SF @ 1 space per 200 SF = 62 Spaces Required  
 Spaces Provided = 63 Parking Spaces ±

Light Impact Industry Use  
 18,240 SF @ 1 space per 500 SF = 37 Spaces Required  
 Spaces Provided = 37 Parking Spaces

**LEGEND**

- EXISTING PROPERTY LINE
- EXISTING EASEMENT
- x-x-x- EXISTING CHAIN LINK FENCE
- EXISTING CONCRETE CURB
- EXISTING DROP IN CONCRETE CURB
- ⊙ EXISTING SIGN
- ⊙ PROPOSED # OF STALLS TO BE STRIPPED
- PROPOSED CONCRETE CURB
- PROPOSED DROP CURB & RAMP
- PROPOSED PAINTED STOPBAR
- ⊙ PROPOSED PAINTED HANDICAP PARKING SYMBOL
- ▨ PROPOSED STRIPPED ISLAND
- ⊠ PROPOSED LOADING SPACE
- ⊙ PROPOSED SINGLE POLE SIGN
- PROPOSED BUILDING MOUNTED LIGHT
- PROPOSED DOOR LOCATION
- PROPOSED OVERHEAD DOOR LOCATION

**SIGN DATA TABLE**

LOCATION NO.	TEXT	M.U.T.C.D. NUMBER	SIZE OF SIGN (s.f.)	DESCRIPTION
1	RED ON WHITE	R7-1	12" x 18"	Red on White
2	BLUE ON WHITE	R7-8	12" x 18"	Blue on White

**USE TABLE TOWN OF CARMEL COMMERCIAL ZONE**

	USE	AREA	TENANTS / EMPLOYEES	ANTICIPATED HOURS
Building 1:	Office Warehouse	5,000 SF ± 10,000 SF ± 18,000 SF ± TOTAL	5 Units Fulltime 1-24hr 5-10 Total	0-10 Service / Day 5-10 Employees / Day
Building 2:	Warehouse	3,240 SF	0-2 Intermittent	0-2 / Day

1	2-19-24	REVISED PER TOWN COMMENTS	KJK
NO.	DATE	REVISION	BY

**INSITE**  
 ENGINEERING, SURVEYING &  
 LANDSCAPE ARCHITECTURE, P.C.

3 Corbett Place  
 Carmel, NY 12052  
 (845) 225-9630  
 (845) 225-9717 fax  
 www.insite-emp.com


PROJECT: **CRECCO DAG RT 6**

385 US ROUTE 6, TOWN OF CARMEL, PUTNAM COUNTY, NY


DRAWING: **LAYOUT & LANDSCAPE PLAN**

PROJECT NUMBER: 16230.100 PROJECT MANAGER: R.D.W.  
 DATE: 1-17-24 DRAWN BY: K.J.K.  
 SCALE: 1" = 30' CHECKED BY: A.D.T.

DRAWING NO. SHEET  
 SP-1 2 5



ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.



**LEGEND**


- EXISTING PROPERTY LINE
- - - EXISTING EASEMENT
- x-x- EXISTING CHAIN LINK FENCE
- EXISTING CONCRETE CURB
- EXISTING DROP IN CONCRETE CURB
- EXISTING UNDERGROUND DRAINAGE PIPE
- EXISTING CATCH BASIN
- EXISTING POST MOUNTED LIGHT
- EXISTING LIGHT POLE
- EXISTING WELL
- - - EXISTING 10' CONTOUR
- - - EXISTING 2' CONTOUR
- EXISTING SPOT GRADE
- PROPOSED 10' CONTOUR
- PROPOSED 2' CONTOUR
- PROPOSED SPOT ELEVATION
- PROPOSED SEWER MANHOLE
- PROPOSED DRAINAGE MANHOLE
- PROPOSED WATER SHUT OFF VALVE
- PROPOSED WATER VALVE
- PROPOSED DRAINAGE PIPE
- PROPOSED SEWER MAIN
- PROPOSED SEWER FORCE MAIN
- PROPOSED SEWER SERVICE LINE
- PROPOSED DOMESTIC WATER SERVICE LINE
- PROPOSED SILT FENCE
- PROPOSED LIMITS OF DISTURBANCE
- PROPOSED TEMPORARY SOIL STOCKPILE
- PROPOSED STABILIZED CONSTRUCTION ENTRANCE
- PROPOSED STONE RIP-RAP

**UTILITY NOTES:**  
 1. All proposed utilities are to be buried.

18" CMP TO BE FILLED & ABANDONED  
 20 FT. & 10 FT. WIDE DRAINAGE EASEMENTS AS SHOWN ON MAP ENTITLED "MAHOPAC HOLDINGS, INC. FILED MAY 8, 1974 FILED MAP No. 1390"

PROPOSED ACCESS AND STORMWATER EASEMENT

ALTERATION OF THIS DOCUMENT, UNLESS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER IS A VIOLATION OF SECTION 7209 OF ARTICLE 145 OF THE EDUCATION LAW.



1	2-19-24	REVISED PER TOWN COMMENTS	KJK
NO.	DATE	REVISION	BY
PROJECT: <b>CRECCO DAG RT 6</b> 385 US ROUTE 6, TOWN OF CAMEL, PUTNAM COUNTY, NY			
DRAWING: <b>GRADING, UTILITIES, &amp; EROSION CONTROL PLAN</b>			
PROJECT NUMBER	16230.100	PROJECT MANAGER	R.D.W.
DATE	1-17-24	DRAWN BY	K.J.K.
SCALE	1" = 30'	CHECKED BY	A.D.T.
DRAWING NO.			SHEET
SP-2			3
			5







February 14, 2024

Town of Carmel Planning Board  
Carmel Town Hall  
60 McAlpin Avenue  
Mahopac, New York 10541  
Via Email: Rose Trombetta - [rtrombetta@ci.carmel.ny.us](mailto:rtrombetta@ci.carmel.ny.us)

RE: MK Realty Site Plan  
U.S. Route 6 and Old Route 6  
Tax Map No. 55.06-1-44 & 45

Dear Chairman Paepre and Members of the Board:

The above referenced Site Plan was re-granted Site Plan Approval at the March 11, 2023 Planning Board meeting. Since the project was originally approved in 2006, the Bond amount was reviewed by the Board's consultants in 2015 and increased to reflect the current construction costs for with the project. It should be noted that the applicant has kept all of the regulatory permits associated with the subject project current.

It is respectfully requested that this project be placed on the Planning Board's next available agenda for consideration of a one-year extension of Site Plan Approval. The \$2,000.00 approval extension fee will be forwarded under separate cover.

Should you have any questions or comments regarding this information, please do not hesitate to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:

  
\_\_\_\_\_  
Zachary M. Pearson  
Principal Engineer

ZMP

Enclosure(s)

cc: Kevin Dwyer, Via Email: [kevinbdwyer@msn.com](mailto:kevinbdwyer@msn.com)

Insite File No. 04235.100

**From:** [michelle.gervasi](#)  
**To:** [Trombetta,Rose](#)  
**Subject:** Jordano/Gervasi Subdivision Bond Return  
**Date:** Wednesday, January 31, 2024 11:45:43 AM

---

**CAUTION:** This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Hello Rose

I am requesting to be placed on the planning board agenda for February 28,2024 to request a release of the remainder of the subdivision bond associated with 182 Bullethole Rd.

Thank you  
Michelle Gervasi



Timothy S. Allen, P.E.  
Nicholas Gaboury, P.E.  
Matthew J. Gironda, P.E.

February 9, 2024

Town of Carmel Planning Board  
60 McAlpin Avenue  
Mahopac, NY 10541-2340

Attn: Mr. Craig Paeprer, Chairman

Re: Proposed 14-Lot Subdivision  
Yankee Land Development Subdivision  
Bayberry Hill Road & Owen Drive  
TM # 76.15-1-12

Dear Chairman and Members of the Board:

On behalf of the owners of the above captioned property we are hereby requesting an additional 180-day extension of Preliminary Subdivision Approval. This project was granted a 180 day extension until February 15, 2024. Check # 114 in the amount of \$ 2,500 for the renewal fee is enclosed.

We respectfully request to be placed on your next available agenda. Should you require any additional information, please feel free to contact me.

Very truly yours,

A handwritten signature in blue ink, appearing to read "T.S. Allen", is written over a large, faint circular watermark or stamp.

Timothy S. Allen, P.E.  
*Senior Partner*

TSA/mme  
Enclosure

cc: Angelo Luppino  
Michael Sirignano  
File

*Site Design • Environmental*

---

Mill Pond Offices • 293 Route 100 • Suite 203 • Somers, New York 10589  
Phone: 914.277.5805 • Fax: 914.277.8210  
Website: [www.bibboassociates.com](http://www.bibboassociates.com) • E-mail: [bibbo@bibboassociates.com](mailto:bibbo@bibboassociates.com)